


ATTACHMENT 8

Superfund Record of Decision: Hardage/Criner, OK (EPA/ROD/R06-90/054)
November 1989

SEPA

Superfund Record of Decision:

Hardage/Criner, OK



NOTICE

THIS DOCUMENT HAS BEEN REPRODUCED FROM THE BEST COPY FURNISHED US BY THE SPONSORING AGENCY. ALTHOUGH IT IS RECOGNIZED THAT CERTAIN PORTIONS ARE ILLEGIBLE, IT IS BEING RELEASED IN THE INTEREST OF MAKING AVAILABLE AS MUCH INFORMATION AS POSSIBLE.

EPA/ROD/RO6-90-054 Hardage/Criner, OK

16. Abstract (Continued)

and ground water are VOCs including benzene, PCBs, PCE, TCE and other carcinogenic compounds; other organics including pesticides; and metals including arsenic, chromium, and lead.

The selected remedial action for the site includes source control and ground water components. Source control remediation includes installation of liquid extraction wells to pump out free liquids currently pooled in the three waste areas and any liquids released from drums buried in the mounds, followed by offsite treatment of the removed organic liquids and onsite treatment of aqueous liquids; excavation of drummed organic liquids for offsite destruction; excavation and consolidation of contaminated soil adjacent to the main source areas with placement in the main source areas, followed by temporary capping; treatment of the main source areas using in-situ soil vapor extraction with treatment of air used in soil extraction by thermal destruction; installation of a permanent RCRA-compliant cap once remedial activities are complete. Ground water components are designed to control the spread of ground water plumes and protect downgradient areas because of the technical impracticability of restoration of the bedrock aquifer. Ground water remediation includes installation of an interceptor trench downgradient of the source areas to intercept and collect contaminated ground water migrating in bedrock zones, and a second trench or equally effective system of extraction wells to intercept and collect contaminated ground water contaminating the alluvium; design and construction of an onsite ground water treatment system to treat both organic and inorganic contaminants before discharge of treated water to surface water. Contaminants already present in the alluvium will be allowed to dissipate by natural dilution, natural attenuation, and flushing; however, active restoration will be implemented if contaminant reduction goals are not met. In addition, institutional controls, surface water controls, and multimedia monitoring will be implemented, and the current provision of an alternate water supply will be continued. The estimated present worth cost of this remedial action is \$62,904,655, which includes an annual OAM cost of \$1,300,000.

ATTENTION

PORTIONS OF THIS REPORT ARE NOT

FULLY LEGIBLE. DUE TO THE IMPORTANCE

OF THE MATERIAL IT IS MADE AVAILABLE

TO THE PUBLIC. HOWEVER, IT IS THE BEST

REPRODUCTION AVAILABLE FROM THE COPY SENT

TO NTIS.

DOCUMENT COMPLETE AS PAGINATED PER SOURCE.

DIRECT QUESTIONS RESULTING FROM ILLEGIBILITY TO:

U.S. EPA OSWER - HSCD RECORD OF DECISION AMENDMENT HARDAGE/CRINER SITE McCLAIN COUNTY, OKLAHOMA NOVEMBER 1989

U.S. ENVIRONMENTAL PROTECTION AGENCY REGION 6, DALLAS, TEXAS

1.0

DECLARATION FOR THE RECORD OF DECISION AMENDMENT

SITE NAME AND LOCATION

Hardage/Criner McClain County, Oklahoma

STATEMENT OF BASIS AND PURPOSE

This decision document represents the selected remedial action for the Hardage/Criner site developed in accordance with the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), as amended by the Superfund Amendments and Reauthorization Act of 1986 (SARA), and to the extent practicable, the National Oil and Hazardous Substances Pollution Contingency Plan (NCP).

This decision is based on the contents of the administrative record for the Hardage/Criner site. The attached index (Appendix C) identifies the items which comprise the administrative record upon which the decision to amend the 1986 Record of Decision (ROD), and the selection of the modified remedial action is based.

The State of Uklahoma supports a number of the components of the amendment but has not concurred with all elements of the selected remedial action.

ASSESSMENT OF THE SITE

Actual or threatened releases of hazardous substances from the site, if not addressed by implementing the response action selected in this ROD, may present an imminent and substantial endangerment to public health, welfare, or the environment.

DESCRIPTION OF THE REMEDY

The 1989 proposed remedy is a comprehensive site remedy addressing both Source Control and Groundwater operable units at the Hardage/Criner site. It involves a modification of the 1986 ROD for Source Control, and incorporates new Groundwater response actions. The major components of this remedial action consist of the following source control and groundwater components:

SOURCE CONTROL

o the installation of liquid extraction wells in three main source areas to pump out free liquids current y pooled in these areas and any liquids released from drums buried in the mounds. The liquids would be collected and shipped offsite for treatment, thereby permanently reducing the volume of haz dous substances in the source areas and the potential for the r migration.

- o excavation as per the 1986 ROD for the direct removal of drummed liquids in the Barrel Mound and Main Pit. Drum excavation and liquids removal would reduce the volume of hazardous liquids within the source areas during the early phases of remedy implementation, thereby reducing the reliance on long-term active controls otherwise necessary to address the continued release and migration of hazardous liquids, many of which are highly toxic, resulting from gradual and difficult to predict corrosion of drums.
- o excavation of contaminated soils in areas adjacent to the three main source areas and transport to the source areas. These materials would be consolidated under a temporary cap in the main source areas where they would be treated using soil vapor extraction.
- o use of soil vapor extraction to draw air through the source areas after consolidation to evaporate contaminants and permanently remove them to the surface through air extraction wells. The air would be treated to destroy the contaminants using the best available control technology (BACT) by thermal destruction.
- o permanent source area capping once remediation activities are complete. A temporary cap will be installed during remediation activities, followed by a permanent RCRA-compliant cap at the end of remediation.

GROUNDWATER

Groundwater components summarized below would be implemented in conjunction with a substantial reduction of the contaminant source areas thereby reducing the long-term potential contribution of the sources to groundwater.

- o the installation of a V-shaped trench located downgradient (west, south and east) of the three main source areas to intercept and collect contaminated groundwater migrating in all bedrock zones existing above Stratum IV. This trench would capture contaminated groundwater onsite and near the source areas minimizing migration of contaminants beyond the trench and into the alluvium of North Criner Creek.
- o the installation of an interceptor trench, or equally effective system of extraction wells, in the southwestern part of the site to contain contaminated groundwater moving into the alluvium from bedrock zones above Stratum IV. This interceptor system would capture migrating contaminants between the V-trench and alluvium of North Criner Creek.
- o the design and construction of an onsite ground ater treatment system incorporating treatment processes to tre t both organic and inorganic contaminants to surface water dismarge standards. Collected groundwater would be pumped to the treatment unit, and the treated water discharged to North Criner Creek.

o alluvial groundwater restoration. Contaminants already present in the alluvium would be allowed to dissipate by natural dilution, natural biodegradation and flushing. The interceptor trenches, in conjunction with source control actions, would abate contaminant migration into the alluvium of North Criner Creek and allow natural restoration to Maximum Contaminant Levels to occur. If alluvial monitoring reveals that estimated natural restoration times and plume dilution rates are not being met, then active restoration of the alluvium would be implemented. An increase in contaminant concentrations in the alluvium after trench installation and pumping, or a decline in the mass of contaminants of less than 40 percent in 10 years, will trigger active restoration in the alluvium.

In addition to the Source Control and Groundwater components listed above, the comprehensive remedy calls for the following monitoring and support components (further described in Section 6) which are necessary as part of remedy implementation:

- o institutional controls, including fencing, deed restrictions, and maintenance of the availability of an alternate water supply system. These will be implemented to restrict access to the site and contaminated groundwater.
- o surface water controls to collect surface water drainage from the source areas during remedy implementation, and to divert uncontaminated runoff away from the working area in order to minimize the generation of contaminated groundwater.
- o remedial monitoring to verify that the migration of contaminants has been halted. This monitoring program includes monitoring of surface water in North Criner Creek, monitoring of alluvial and hedrock groundwater onsite and offsite, including downgradient of the alluvial contamination plume, and monitoring of the performance of the groundwater interceptor trenches (or wells if used in place of the southwest interceptor trench) to determine their effectiveness in containing and reducing contamination. The caps proposed as part of the Source Control will be monitored for differential settlement or erosion. Finally, air quality would be monitored during implementation of the remedy both onsite and at the fenceline houndary. Action levels will be set onsite to assure that Maximum Ambient Air Concentrations are not exceeded at the fenceline.

DECLARATION

The selected remedy, if implemented, is protective of human health and the environment, attains Federal and State requirements that are applicable or relevant and appropriate to this remedial action and is cost-effective.

This remedy satisfies the statutory preference for remedies that employ treatment that reduces toxicity, mobility or volume as a principal element and utilizes permanent solutions and alternative treatment technologies to the maximum extent practicable.

Because this remedy will result in hazardous substances remaining onsite above health based levels, a review will be conducted within five years after commencement of remedial action to ensure that the remedy continues to provide adequate protection of human health and the environment.

Robert E. Layton Jr. P.E.

Mov. 27, 1989

HARDAGE/CRINER - RECORD OF DECISION AMENDMENT

TABLE OF CONTENTS

1.0 Site Location and Description 2.0 Site History and Enforcement Activities 2.1 Disposal Operations 2.2 Enforcement 2.3 Site Investigations 2.4 Highlights of Community Participation 3.0 Scope of Response Action 4.0 Site Characteristics 4.1 Site Conditions 4.1.1 Surface Water Hydrology 4.1.2 Site Geology 4.1.3 Groundwater Hydrology 4.2 Site Contamination 4.2.1 Impact of Disposal Operations 4.2.2 Remaining Contaminant Sources 4.2.3 Pathways and Extent of Contamination 4.2.4 Future Contaminant Migration 5.0 Site Risks 6.0 Description of Alternatives 6.1 Alternative Source Control Components 6.1.1 No Action
6.1.2 On-site Landfill (EPA 1986 ROD)
6.1.3 Containment of Wastes (HSC Proposal) 6.1.4 Incineration 6.1.5 Liquid Extraction Wells 6.1.6 In-Place Drum Lancing 6.1.7 Drum Excavation 6.1.8 Excavation of Wastes in Adjacent Areas 6.1.9 Soil Vapor Extraction and Treatment 6.1.10 Source Area Capping 6.2 Groundwater Remediation Objectives and Alternative Groundwater Components 6.2.1 U-shaped Trench 6.2.2 V-shaped Trench 6.2.3 Southwest Interceptor Trench 6.2.4 Groundwater Treatment System 6.2.5 Alluvial Groundwater Restoration 6.3 Monitoring and Support Components 6.3.1 Remedial Support Facilities6.3.2 Institutional Controls5.3.3 Surface Water Controls6.3.4 Remedial Monitoring

- 6.4 Comprehensive Alternatives
 - -6.4.1 Common Elements
 - 6.4.2 Revised EPA Remedy
 - 6.4.3 Partially Revised EPA Remedy
 - 6.4.4 HSC Remedy
- 7.0 Comparative Analysis of Alternatives
 - 7.1 Overall Protection of Human Health and the Environment
 - 7.2 Compliance with Applicable or Relevant and Appropriate Requirements
 - 7.3 Long-term Effectiveness and Permanence
 - 7.4 Reduction of Toxicity, Mobility, or Volume
 - 7.5 Short-term Effectiveness
 - 7.6 Implementability
 - 7.7 Cost
 - 7.8 State and Community Acceptance
- 8.0 Selected Remedy Description
 - 8.1 Remediation Goals
- 9.0 Statutory Determinations
 - 9.1 Protection of Human Health and the Environment
 - 9.2 Compliance with ARARs
 - 9.3 Cost Effectiveness
 - 9.4 Utilization of Permanent Solutions and Alternative Treatment Technologies
 - 9.5 Preference for Treatment as a Principal Element
 - 9.6 Documentation of Significant Changes

REFERENCES

APPENDICES

- A. Evaluation of Applicable or Relevant and Appropriate Requirements
- B. Agency for Toxic Substances and Disease Registry (ATSDR)/Center for Disease Control (CDC) Evaluation
- C. Administrative Record Index
- D. State of Oklahoma Correspondence
- E. Responsiveness Summary
- F. 1986 Source Control Record of Decision
- G. Detailed Cost Evaluation of the Selected Remedy

LIST OF FIGURES

- 1-1. Vicinity Map
- 1-2. Site and Disposal Operations Map
- 4-1. North Criner Creek Drainage Basin Map
- 4-2. Surface Water Hydrology
- 4-3. Geologic Cross-Section
- 4-4. Hydrogeologic Cross-Section
- 4-5. Main Pit and Barrel Mound Pit Cross-Section
- 4-6. Approximate Extent of Groundwater Contamination
- 4-7. Distribution of Total Volatile Organics in Stratum III and the Alluvium
- 6-1. Conceptual Drum Lancing Diagram
- 6-2. Areas Targeted for Drum Excavation 6-3. Schematic of Soil Vapor Extraction 6-4. Final Source Area Cap

- 6-5. Alternative C Site Schematic, Second Operable Unit
- Feasibility Study 6-6. Alternative E Site Schematic, Second Operable Unit
- Feasibility Study 6-7. Site Cross-Section Showing Trenches
- 8-1. Schematic of Selected Remedy

LIST OF TABLES

- 2-1. Summary of Drummed Wastes from Manifests
- 4-1. Carcinogens Detected in the Source Area Characterization
- 4-2. Comparison of Groundwater Data with MCLs.
- 6-1. Summary of Alternative Elements, Second Operable Unit Feasibility Study
- 6-2. Comparison of Alternatives
- 7-1. Comparison Summary According to Statutory Criteria
 7-2. Drum Excavations Performed at Other Sites
 8-1. Cost of Selected Remedy

1.0 SITE LOCATION AND DESCRIPTION

The Hardage site is located in a rural area of McClain County in central Oklahoma, approximately 25 miles south-southwest of Oklahoma City (Figure 1-1). The site is bounded on the South by old Oklahoma State Highway 122, on the north by open farmland, on the west by a gravel (County) road, and on the east by a series of three small ponds (Figure 1-2).


The Hardage site was operated from 1972 to 1980 under a permit issued by the Oklahoma State Department of Health (OSDH) for the disposal of industrial wastes. In 1983, EPA placed the site on the "National Priorities List" (48 Fed. Reg. 40658) for response under the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA). EPA has taken the lead in response to this site. OSDH has provided technical support and advice to EPA, particularly in the early stages of work on the site, and has been consulted on remedy selection.

As a result of waste disposal practices at the site, chemicals have migrated vertically and laterally resulting in the contamination of approximately 70 acres of groundwater beneath and adjacent to the site as well as several acres of surface soil in the immediate vicinity of the main disposal areas. The principal source of contamination is some 278,000 cubic yards of sludges, waste drums, highly contaminated soils, and waste liquids contained in three waste areas near the center of the property.

The disposal areas at the site were a number of permanent and temporary impoundments into which a variety of liquid, sludge, and solid wastes were disposed and mixed. These areas, described more fully in Section 2.1, were primarily the Main Pit, Sludge Mound, and Barrel Mound, and in addition the North Pit, West (mixing) Ponds, and East (mixing) Ponds (see Figure 1-2). During 1980 - 1981 the operator consolidated wastes into the Main Pit, Barrel Mound, and Sludge Mound and capped those areas with two to three feet of local soil in an effort to permanently close the site. Closure efforts failed, however, to prevent the migration of hazardous substances vertically and laterally into groundwater from the impoundments. More specifically, dense non-aqueous phase liquids have pooled beneath the Main Pit, Barrel Mound and to some extent the Sludge Mound and now serve as a continuing source of contamination to the groundwater. Volatile organic compounds, many of them known or suspected carcinogens, have migrated from these areas offsite into the alluvium of North Criner Creek, forming a plume of contamination extending a distance of about 2800 feet southwest of the Main Pit. Total concentrations of volatile organic compounds in the plume exceed 25,000 ppb near the source areas and decrease systematically away from the source areas, with concentrations as high as a few hundred pph more than 2500 feet away from the Main Pit to the southwest. Volatile organic compounds are entering North Criner Creek at sufficient quantities to cause detectable concentrations in surface water in the Creek.

Present and near-term risks are related primarily to groundwater resources and any individuals who might use the contaminated groundwater. Over the long-term, risks will also be posed due to erosion of wastes and their gradual surface and subsurface migration across and from the site.

I



2.0 SITE HISTORY AND ENFORCEMENT ACTIVITIES

2.1 Disposal Operations

In 1972 the site owner and operator Royal Hardage, received a permit from the Oklahoma State Department of Health (OSDH) to operate a hazardous and industrial waste landfill at the site. This permit was based on an application by Mr. Hardage that consisted of a general outline of planned operations and limited subsurface horing data on site geology.

From September 1972 until November 1980 the site accepted approximately 21 million gallons of hazardous and industrial wastes including paint sludges and solids, ink solvents, tire manufacturing wastes, oils and solvents such trichloroethene, corrosives, plating wastes sludges, cyanides, and caustic wastes, many of which are now regulated as hazardous waste under the Resource Conservation and Recovery Act (RCRA). The liquid portion of this waste was initially discharged into the Main Pit. Early in the operation, problems began to occur due to slower than expected evaporation of wastes. To deal with this problem, the operator began spraying liquids over the Main Pit to enhance evaporation and also drained some of the liquids into adjacent temporary mixing ponds for bulking with soil. The soil/waste mixture was disposed in a new area called the Sludge Mound. Sludge waste, including residue from oil recycling and styrene tar production, and some drums of solid material, were also disposed in the Sludge Mound.

In addition to the hulk waste liquids disposal described above, drums of waste were also received at the site. These waste drums were initially opened and dumped into the Main Pit. This practice, however, hecame less common after about 1974. During most of the operations, drums were dumped off trucks into two areas, the west side of the Main Pit and the Barrel Mound. The Barrel Mound area adjoins the north end of the Main Pit and was huilt to a height of 25 to 30 feet by trucks dumping drums off of the south side of the mound, filling soil over and around the drums, and dumping of additional drums onto the previously dumped drums. Many of the drums at the site were carelessly dumped into the pits, without any attempt to avoid rupturing. Some drums were rolled off trucks down the face of the Barrel Mound. Other drums dumped into the pits were not sealed to hegin with. As a result, a substantial number of these drums spilled or broke open during the disposal operation resulting in the direct release of large volumes of hazardous and carcinogenic chemicals into soils and eventually groundwater. Many of the drums, however, were disposed intact, as shown by accounts of the site operation (Hardage, 1987). Moreover, intact drums were excavated and removed from the site during exploratory excavations in 1988 (EPA, 1988). A summary of drummed wastes brought to the site (from manifests) is presented in Table 2-1.

In addition to disposal practices in the source areas (Barrel Mound, Main Pit, and Sludge Mound) waste mixing and transfer operations were conducted over much of the site in areas known as the North Pit, East Pond area, and West Pond area. The disposal areas and site activities described above are illustrated in Figure 1-2.

Table 2-1 SUMMARY OF DRUMMED WASTES FROM MANIFESTS

Waste Category	No. of Containers Received	Estimated Volume Received(1) (gallons)
Paint		
Sludge	5,897	324,047
Paints and Related Wastes	1,044	57,420
Solids	451	24,805
Mixed Wastes		
Mixed Wastes Tire Manufacturing Wastes (Carbon Black Sonn	2,557	138,600
(Carbon Black, Soap, Oil, Solvents, Rubber	1,405	77,275
Soap, Oil, Solvents	304	16,720
Soap, Oil, Solvents	304	10,720
Acid	1 067	102 695
Rinse Water Sulfuric Acid	1,867	102,685 48,400
	880 676	37,180
Sludges		18,755
Acids	341	13,565
Chromic Acid	248	10,670
Nitric Acid	194	1,705
Acids and solvents	31 13	715
Muriatic Acid		660
Acrylic Acid	12	220
Hydrofluoric	4	220
Oils and Solvents (TCE,		177 016
Stoddard)	3,253	177,815
Asbestos	1,345	73,975
011		
Oils	660	36,300
Sludge	132	5,790
Alumina Silica Slurry	747	41,085
Ink		
Inks	520	30,425
Solvent	57	3,135
Sludge	47	2,585
Caustic	580	31,900

CVOR211/033.50/1

Table 2-1 (continued)

Waste Category	No. of Containers <u>Received</u>	Estimated Volume Received(1) (gallons)
	_NEVEA-VV	
Cupric Ammonium Persulfate and Toxic Tin	435	23,925
Corrosive	357	19,635
MDI (methylene bisphenyl isocyanate)	299	16,325
Plastic Wastes	261	14,355
Aromatic Residue	232	12,760
Chemical Wastes	229	12,595
Plating Waste Sludge	214	11,770
Cyanide (Copper, Potassium, Sodium)	142	7,760
Shopwaste	111	6,105
Nitric Alumina	91	5,005
Glue	84	4,620
Alumina Oxide	80	4,400
Filter Cake	80	4,400
Methanol	80	4,400
Sediment Pit Waste	62	3,410
Zinc, Arsenic	33	1,782
PCBs	29	1,595
Laboratory Chemical Packs (Phosgene Gas Canister, Reagents, Waste Chemicals)	27	1,385
_	145	1,375
Toxaphene	143	1,3/3

CVOR211/033.50/2

Table 2-1 (continues,

Waste Category	No. of Containers Received	Estimated Volume Received(1) (gellons)
Polyacrylamide	14	770
Sand Filter Sludge	11	605
Ammonium Bifloride	8	440
Selenium	8	440
Emulsion	6	330
Trichloroethene and Aluminu	m 63	315
Chromium	20	300
Waste Chlorides	142	142
Insecticides	3	165
Salt Sludge	2	110
Ammonium Hydroxide	55	55
Chlorine	1	55
Sodium Lead Alloy	1	28
2,4-Dinitrophenyl Hydrazine	1	-
Pesticide with Arsenic	1	-
Vaccine	1	
TOTAL	25,593	1,437,809

⁽¹⁾ Unless indicated on manifest, Hardage (1972-1980) containers were assumed to be 55-gallon drums. All containers were assumed to be full.

2.2 Enforcement

In 1979, OSDH and EPA inspections and sampling of the site indicated waste management-practices were posing potential threats to public health and the environment. In September 1980, the United States, on behalf of EPA, filed a complaint in the U.S. District Court for the Western District of Oklahoma. The complaint sought injunctive relief under Section 7003 of RCRA for the proper cleanup and closure of the site. The facility ceased operations in early November 1980, before Interim Status Standards under the RCRA came into effect.

In 1982, United States amended the existing complaint against the facility owner and operator Royal Hardage, to request relief under Sections 106 and 107 of the CERCLA. In December 1982, the Court found that the site posed an "imminent and substantial endangerment to public health and welfare and the environment" as defined by CERCLA Section 106 and RCRA Section 7003. In August 1983, the Court granted a partial judgment for over \$211,000 in response costs, which EPA had incurred through 1982, against Royal Hardage. Hardage filed for bankruptcy in 1983 and again in 1985, and EPA has to date not recovered its partial judgment.

In December 1984, EPA mailed letters to 289 Potentially Responsible Parties (PRPs) requesting information about their waste disposal at the Hardage site under authority of Section 104(e) of CERCLA and Section 3007 of RCRA and notifying the PRPs of their potential liability for site cleanup. As further information was gained, information request and notice letters were sent to additional PRPs identified. At the present time, over 400 PRPs have been identified. Various PRPs have gone out of business or cannot be located; therefore, approximately 340 have been contacted. A group of these parties organized into the Hardage Steering Committee (HSC) and met with EPA and OSDH on numerous occasions concerning the site. Initial meetings with the HSC were held in January of 1985.

In May 1985, EPA released a report entitled Field Investigation and Data Summary Report (DSR) for the Royal Hardage Waste Disposal Site (EPA, 1985) documenting investigations conducted in 1984 and earlier. This document served as a remedial investigation (RI) report for the site.

After completion of the DSR, EPA determined that sufficient data were available to develop a remedy for the contaminant source areas, but that the information was inadequate to develop remedial alternatives for the contaminants that had already migrated from the source areas into ground—water. Accordingly, selection of a comprehensive alternative for a complete remedial action, addressing surface and subsurface contamination beyond the source areas, was not possible at that time. The need for control of the source areas at the site prompted EPA to consider alternatives that would reduce or eliminate the spread of contaminants off the site. Therefore,

EPA decided, in accordance with Section 300.68(c) of the National Oil and Hazardous Substances Pollution Contingency Plan (NCP), to divide the remedial process of the site into two operable units: 1) Source Control and 2) Management of Migration (groundwater).

During 1985, EPA began preparing a Feasibility Study (FS) for the Source Control Operable Unit primarily addressing the three principal waste source areas: the Main Pit, the Barrel Mound and the Sludge Mound.

EPA's FS, entitled <u>Feasibility Study</u> - <u>Source Control</u> - <u>Royal Hardage Industrial Waste Site Near Criner</u>, <u>Oklahoma (EPA, 1986a)</u>, presented the methodology used to develop several remedial action alternatives for the Source Control Operable Unit. The alternatives, further discussed in Section 6, were evaluated in accordance with the NCP, and four alternatives were developed in detail. These four alternatives included onsite waste stabilization with disposal in a RCRA-compliant landfill, onsite incineration and disposal, offsite incineration and disposal, and onsite waste stabilization and disposal in an offsite RCRA-compliant landfill.

In November 1986, EPA issued its Record of Decision (ROD) outlining the selected final remedy for the Source Control Operable Unit (see Appendix F). This remedy was selected in a manner consistent with CERCLA, as amended, and the NCP as the most appropriate remedy for source control considering all relevant selection criteria. The selected remedy consisted of excavaring, treating, and disposing of solids in a RCRA-compliant onsite landfill; removal and offsite incineration of free organic liquids; and the onsite treatment and disposal of other water-based liquid wastes. After potentially responsible parties declined to implement the selected remedy, EPA subsequently initiated the remedial design process with the design-related field activities. The detailed design was presented in EPA's Design Report - Source Control Remedial Design - Hardage Industrial Waste Site - Criner Oklahoma (EPA, 1988).

Prior to EPA's 1986 ROD, additional field studies were initiated by the HSC. This work involved the gathering of geologic and hydrologic data at the Hardage site to assess an in-place containment remedy later proposed by the HSC. As a result of this work, the HSC submitted the Final Confirmatory Bedrock Study in December of 1986 (HSC 1986). As a part of the EPA's public comment process for the ROD, the HSC's report also briefly presented the the HSC's proposed source control remedy. The HSC remedy ca'led for in-place containment of the waste source areas by a cut-off wall supplemented by groundwater pumping. Differences between the HSC and EPA source control proposals were not resolved and resulted in litigation over implementation of the selected remedy. Work by the HSC in support of the proposed remedy continued at the site through November 1, 1988. Accitional characterization of the source areas was conducted and

reported in the HSC's <u>Mound Characterization Field Study</u> (HSC, 1988). From these and other studies performed as a part of the HSC's litigation efforts, the HSC prepared a <u>Recommended Source Control Remedy</u> design report (HSC, 1988) which provided additional technical details of the HSC's proposed remedy.

Meanwhile, in July 1985 the Court administratively closed the 1980 case against Hardage, providing that the U.S. could re-open the case for the poppose of seeking appropriate relief until April 1, 1986, at which time the case would otherwise he dismissed. The United States, on behalf of EPA, filed a motion on March 27, 1986, to amend the existing complaint and add newly discovered generators and transporters to the existing case. The Court ultimately denied the motion and dismissed the case. On June 25, 1986, the United States filed a new complaint naming 36 generators and transporters of waste at the site. The complaint asked for performance of the EPA selected source control remedy, maintenance of site security, conduct of a RI/FS for the management of migration (groundwater) operable unit, implementation of the groundwater operable unit remedy to be selected by EPA, and recovery of EPA's past and future response costs.

In 1987 the District Court issued a ruling indicating that the case would be decided in a "de-novo" trial, as opposed to a trial on the Administrative Record. The Court, in issuing that ruling, cited two factors peculiar to the case. First, the case was filed prior to the enactment of the Superfund Amendments and Reauthorization Act of 1986 (SARA), which called for Administrative Record review at trial. Second, the case was filed under RCRA as well as CERCLA; and RCRA does not mandate an Administrative Record trial.

After lengthy negotiations, a Partial Consent Decree between EPA and HSC was entered by the Court in February 1988. Under this Decree, HSC agreed to conduct a RI/FS addressing management of contaminant migration at the site under EPA oversight. The second operable unit RI/FS, and Endangement Assessment reports were submitted to EPA in the spring of 1989, finalized and sent to repositories in October of 1989.

Throughout 1988 both EPA and HSC took extensive depositions of both fact and expert witnesses. In early 1989, the Government initiated meetings with HSC to discuss ways of resolving on-going litigation.

On April 7, 1989 a Consent Decree was lodged with the U.S. District Court between EPA and approximately 170 "de minimis" (small quantity) PRPs for the site. Under this agreement, the de minimis parties resolved their liability for the site by making two cash payments: one to EPA to cover past cost incurred, and a second to a trust fund to be supervised by the District Court. The trust fund will be used for site remediation. This Consent Decree was entered by the court on September 22, 1989. The de minimi agreement was prepared in accordance with EPA's Interim Guidance on Settle -nt with De Minimis Waste Contributors under Section 122(q) of SARA (Junc 19, 1987) 52 Fed. Reg. 24333 (June 30, 1987).

2.3 Site Investigations

Studies of the Hardage site have been conducted since 1982. These studies, some of which were mentioned in Section 2.2, are part of EPA's administrative record for the site, and are described below:

March 1982

Ecology and Environment (E&E), an EPA contractor, sampled surface soils, drainage ways, and existing wells at the site. E&E also installed and sampled ten monitoring wells on and around the site. These wells are designated EW-1 through EW-10. This investigation is documented in a May 7, 1982 letter report from Imre Sekelyhidi of E&E.

August 1984

EPA contractor CH₂M Hill and its subcontractors Chen Associates, Wright Water Associates, and Davenport-Hadley conducted a site investigation in 1984 to supplement the 1982 E&E data and allow selection by EPA of a source control remedy. This investigation involved installation and sampling of monitoring wells (the "GTW", "BW", "PW", and "AW" series of wells), limited coring of bedrock, sampling of the source areas, and sampling of shallow test pits. This investigation is documented in the the May 1985 report "Field Investigation and Data Summary Report" (DSR) prepared by CH₂M Hill.

July - November 1985

HSC contractor ERM-Southwest conducted an investigation centering on conditions of the hedrock in the immediate vicinity of the source areas. This investigation included installation of monitoring wells and well nests MW-1 through MW-11, sampling of the shallow wells, resampling of some existing wells, and drilling vertical and slanted test borings B-1 through B-13 and SB-1 through SB-7. This investigation is documented in the December 1986 report "Confirmatory Bedrock Study" prepared by ERM-Southwest.

May 1987

E&E, on behalf of EPA, collected samples from all monitoring wells at the site. This work was monitored, and split samples collected by ERM-Southwest on behalf of HSC. HSC also recorded all work under the six week long project on videotape. The results of their sampling are documented in an August 31, 1987 letter repc t from E&E and in the Management of Migration RI.

October 1987 and March 1988

ERM-Southwest, c behalf of HSC, drilled fourteen cores MB-1 through MB-14 into the waste source areas for chemical sampling and observation of physical conditions. This activity is documented in the HSC's "Mound Characterization Field Study" prepared by ERM-Southwest in November of 1988.

January - April 1988

ERM-Southwest, acting as litigation consultants on hehalf of HSC, conducted a variety of activities on the site, including drilling of deep core holes (the "DH" holes), drilling of slant cores, photo-linear analysis, geophysical logging, reflection and cross-hole geophysics, radioisotope dating, and sampling of chloride for geochemical modeling. This activity is documented in the November 1988 report "Hydrogeologic Issues of Relevance to the Hardage Site" prepared by S.S. Papadopulos Associates.

April 1988 - October 1988

CH₂M Hill and its subcontractor Chen Associates, acting on behalf of EPA, drilled eight hore holes into the source areas to retrieve samples for geotechnical and stabilization testing and to provide data on air emission of VOCs. Two test pits were also excavated to provide further data on air emmissions and on integrity of the buried steel drums. This activity is documented in the November 1988 report "Source Control Remedial Design" prepared by CH₂M Hill.

July - October 1988

ERM-Southwest, on behalf of HSC and working under EPA oversight, conducted a comprehensive investigation of the extent of contamination and physical conditions at the site relative to migration of contaminants. This activity is documented in the May 1989 draft report "Second Operable Unit Remedial Investigation" (also refered to as the Management of Migration RI or Groundwater RI). ERM-Southwest also prepared and submitted to EPA a May 1989 draft "Second Operable Unit Feasibility Study Report" (or Groundwater FS). Both of these reports underwent revision based on EPA comment, were then approved by EPA and sent to repositories in October of 1989. HSC provided replacement pages to EPA during the public comment period which are addressed in the responsiveness summary in Appendix E.

2.4 Highlights of Community Participation

In preparation for this ROD amendment, EPA held a public comment period on the proposed comprehensive remedy. The comment period began October 13, 1989, and closed November 2, 1989. EPA provided notice of the public comment period through announcement in the newspaper on October 1, 1989, and at that time announced a public meeting on the proposed remedy. A fact sheet was prepared by EPA summarizing alternatives for both source control and groundwater and was sent to repositories and addressees on the site mailing list on October 12, 1989. EPA's Remedy Comparison Report and Remedy Report, along with the Administrative Record, were also sent to repositories on this date. A public meeting on the proposed remedy for the site was held on October 26, 1989, and approximately 40 people were in attendance.

EPA has addressed questions received during the public comment period, including those received at the public meeting, in the responsiveness summary (Appendix E).

3.0 SCOPE OF RESPONSE ACTION

The proposed remedy would address both the Source Control and Groundwater (Management of Migration) aspects of the Hardage site in a comprehensive remedial action. This proposed comprehensive remedy would remove a substantial portion of the liquid wastes, including many highly toxic and mobile volatile organic compounds, from source areas, thereby reducing the volume, toxicity, and mobility of the hazardous substances at the site. Moreover, this proposed comprehensive remedy would prevent further contamination of the alluvial aquifer.

To date the site has been investigated as two "operable units" - Source Control and Management of Migration or Groundwater. This approach was adopted in 1985 in an effort to speed remediation of the site. On November 14, 1986, EPA issued a ROD for the Source Control Operable Unit. This ROD selected a remedy, as previously discussed in Section 2.2, consisting of waste excavation and segregation followed by incineration of organic liquids and stabilization and consolidation of solids into a new landfill to be constructed on the site. Protracted litigation from 1986 through 1989 delayed implementation of the selected source control remedy.

In 1987 HSC agreed, pursuant to a partial Consent Decree with EPA, to conduct a RI/FS for the Groundwater Operable Unit of the site. Field studies were conducted in 1988 and a draft FS report was completed in May 1989 evaluating several remedial alternatives for groundwater at the site. It was proposed that any groundwater actions would be implemented in conjunction with a Source Control remedy.

Subsequent to the completion of EPA's Remedial Design Report, an issue arose concerning the potential impact of the RCRA land disposal restrictions on certain elements of the Source Control remedy selected in the 1986 ROD. The Agency's interpretation of the applicability of the land disposal restrictions to CERCLA response actions was then still evolving. Due to uncertainties over the ultimate resolution of this issue, EPA began to consider other alternatives for the Source Control remedy, which could unquestionably he implemented consistent with the RCRA requirements. Because of the timing of the draft Groundwater FS, and the concurrent evaluation of new Source Control technologies, EPA found it efficient and logical to combine Groundwater and Source Control alternatives in order to develop remedial alternatives that would address the entire site. As a result, a number of comprehensive remedial alternatives were assembled from source control and groundwater operable unit alternatives. Comprehensive alternatives are addressed in Section 6.4 and involve amendments to the 1986 ROD for source control and the selection of a remedial response actions for contaminated groundwater. One of those alternatives is presented as the selected comprehensive remedy for the site (see Section 7 for remedy selection criteria).

The proposed remedy would remove a substantial portion of the liquid wastes from the source areas. The Barrel Mound, and those portions of the Main Pit believed to contain drums, would be excavated. Containerized liquids, and free-phase liquids in the source areas, would be removed for offsite destruction. In addition, a relatively new technology, in-situ soil vapor extraction, would be implemented in the source areas to reduce those compounds most mobile in the environment. Soil vapor extraction would be effective in removing volatile and semi-volatile compounds, a number of which are carcinogenic, from the vadose zone, and from the surface of free-phase liquids in the source areas.

The proposed remedy would also prevent further contamination of the alluvial aquifer associated with North Criner Creek. Groundwater interceptor trenches (or possibly interceptor wells in the alluvial recovery area) would be installed to arrest migration of the plume of contamination from the site, and thereby allow the gradual process of restoration in the bedrock and alluvial systems to begin. Groundwater monitoring, institutional controls, and controls on the use of groundwater and surface water would be implemented to assure that humans are not exposed to contaminants.

4.0 SITE CHARACTERISTICS

4.1 Site Conditions

The Hardage site is situated on gently rolling property in a rural area of South Central Oklahoma. The principal disposal operations were conducted along a north-south trending ridge at the center of the property. Relief is about 100 feet from the ridge to the adjacent stream valley. The site is bounded on the southwest by the floodplain of a small perennial stream, and on the east by a series of three small ponds. Soil cover on the site is thin and subject to erosion. The underlying hedrock consists of a series of interbedded sandstones, siltstones, and mudstone. These rocks are fractured, as is well documented in various published studies including observation of cores, rock outcrops, and geophysical logs of borings.

The waste remaining onsite is primarily located in three source areas, the Main Pit, Barrel Mound and Sludge Mound. These three source areas will continue to release contaminants into the environment primarily via ground-water flow. At present, a groundwater plume of volatile organic contamination extends some 2800 feet southwest of the Main Pit with concentrations of volatile organic compounds exceeding 25,000 ppb. The plume ranges in width from about 1800 feet near the source areas to about 800 feet in the southwest corner of the site (see Section 4.2.3, Figure 4-6). Contaminants have migrated vertically and laterally from the source areas into the surrounding and underlying hedrock, both in dissolved form and as non-aqueous phase liquids (NAPL). The present and future migration of contaminants will continue via groundwater flow. Eventually, erosion may also carry wastes off the site from the three source areas and adjacent mixing areas.

4.1.1 Surface Water Hydrology

The site is situated in the North Criner Creek drainage hasin, approximately 0.8 miles from the confluence of North Criner Creek and Criner Creek (Figure 4-1). The drainage hasin drains approximately 5,000 acres, and extends about four miles north of the site to the regional drainage divide between the Washita and Canadian rivers. The site, as stated above, is disected by a north-south trending ridge which controls runoff from the site (see Figure 4-2). Runoff from the western side of the site eventually enters a perennial stream, North Criner Creek, west and southwest of the site. Runoff from the east side of the site enters a series of three small ponds (the East Farm Ponds). These ponds drain southward through a fourth pond located on adjacent property before entering North Criner Creek south of the site. Drainage from the east side of the site is diverted from the east farm ponds by a berm and enters the stream below the southern most pond.

Drainage on the west side of the site from the source areas and much of the former operation area is channeled around an interceptor trench constructed by Royal Hardage to an impourment known as the South Pond at the southwest corner of the site. The sout pond is constructed such that an open discharge

1





FIGURE 4-2
SURFACE WATER HYDROLOGY



pipe near its base releases water to flow south into a roadside ditch. An unknown fraction of this water infiltrates downward from the pond. Runoff from the westernmost portion of the site is diverted around the south pond and enters-the roadside ditch directly.

The southwest corner of the site abuts the North Criner Creek flood plain. North Criner Creek is a perennial stream with a nominal discharge of 0.8 to 1.3 cfs. The stream has been channelized directly south of the site.

The principal ponds, streams, and surface flow divides and paths are shown on Figure 4-2.


4.1.2 Site Geology

Bedrock heneath the site consists of a sequence of Permian aged sediments which grade from sandstone to siltstone, and mudstone. Despite the graditional nature of these deposits, extensive core samples have illustrated lateral continuity of four shallow bedrock zones refered to as Stratum I through IV. Bedding dips at outcrop locations near the site are less than one degree to the west and southwest.

Bedrock immediately beneath the Main Pit and Barrel Mound is comprised of a thin sequence of sandstone and siltstone (Stratum I). Approximately twenty feet beneath the Main Pit begins a sequence of mudstone/siltstone (Stratum II) approximately 20 feet thick. Beneath this is a sandstone/siltstone sequence (Stratum III) which is about 30 feet thick. Underlying Stratum III is a thick sequence of low permeability siltstone and mudstone, the upper 20 feet of which exhibits a predominance of siltstone. This bedrock sequence is illustrated in the generalized geologic cross-section shown in Figure 4-3. Bedrock over the entire site has been subject to natural weathering processes. As a result, the upper 20 to 40 feet of bedrock has been appreciably altered.

Fracturing has been observed in the bedrock layers, both in surface outcrops and in subsurface drill cores recovered from site investigations. Both low angle (less than 10 degrees from horizontal) and high angle (40 degrees on up to vertical) fractures have been reported. All three primary rock types (sandstones, siltstones, and mudstones) have had fractures reported. In addition, EPA believes that free-phase organic chemicals released from the source areas may have desiccated materials adjacent to fractures causing further opening of the fractures. The irregularity and heterogeneity of fracture distribution, interconnection and openness contribute to a relatively high degree of uncertainty regarding the large-scale hydraulic properties of the bedrock strata at the site, and therefore, high uncertainty regarding future waste migration rates and patterns.

Adjacent to the site, and associated with North Cri ar Creek, is an unconsolidated alluvial deposit with thicknesses up to feet. Alluvial horings completed during the second operable unit RI typically encountered a thin silt/clay zone at a depth of 10-15 feet, which in trn was underlain by medium to coarse-grained silty sands. Bedrock underlying the alluvium was found to be a fine-grained silty mudstone, with sor degree of weathering immediately heneath the alluvium.



4.1.3 Groundwater Hydrology

The geologic units described above, given their fractured and weathered conditions, have combined to form a hydrogeologic system as illustrated in Figure 4-4. This figure illustrates the hydrogeologic units at the site: (A) moderately permeable weathered shallow hedrock with general groundwater flow to the southwest-into the alluvium of North Criner Creek (Stratum I-III and the top of Stratum IV, especially in the vicinity of the southwest alluvium); (B) a sequence of variably fractured siltstone and mudstone (the lower portions of Stratum IV); and (C) the North Criner Creek alluvium, a third hydrogeologic unit. The weathered zone and alluvial aquifer are the most permeable units at the site and, consequently, are the units most active in the local groundwater flow regime.

The water table across the site forms a continuous surface across Stratum I, II, and III, and is roughly parallel to the land surface as shown in Figure 4-4. The hydraulic conductivity reported for Stratum I through III ranges from about 2×10^{-7} cm/sec to about 1.5×10^{-3} . Flow in these units has a large horizontal component with a gradient of about 0.01 to 0.07. Lower and higher hydraulic conductivities correspond to an estimated average flow velocity of 18 to 180 feet per year, consistent with the known distribution distances and patterns of contaminants in groundwater at the site. Stratum II has a somewhat lower hydraulic conductivity than Stratum I or III.

Groundwater flow in Stratum I-III in the vicinity of the east farm ponds varies seasonally and is affected by surface water levels in the ponds and recharge to soils. It is generally accepted that the ponds form a discharge boundary for groundwater flow. However, monitoring during and after any remedial action will be required to assure that contaminants are not migrating eastward, beneath the ponds.

Alluvial deposits of North Criner Creek can be separated into upper and lower portions that act as a single unit hydraulically. Nested monitoring wells in the alluvium indicate a general upward gradient through these deposits, implying upward flow out of Stratum IV into the alluvium. Pumping tests indicated an overall effective permeability on the order of 5 x 10^{-3} cm/sec. Transmissivity values range greatly in the alluvium, however, the overall transmissivity is about 3200 to 3500 gpd/ft. Effective porosity ranges between 0.25 and 0.30.

Groundwater flow in the alluvium of North Criner Creek is generally toward the Creek, though skewed down-valley. Contaminants detected in the alluvial aquifer are also found in the source areas of the site. The concentration of total volatile organic compounds (which include toxic substances such as 1,2-dichloroethene and trichloroethene) are several hundred pph in at least three alluvial aquifer wells. In general, North Criner Creek for 3 the discharge houndary to groundwater flow from the site, limiting minimation of contaminants across the Creek.




FIGURE 4-4
HYDROGEOLOGIC CROSS-SECTION
HARDAGE/CRINER SITE

4.2 Site Contamination

During the site operations, approximately 21 million gallons of industrial wastes including acidic, caustic and corrosive wastes, many classified as carcinogenic, were disposed on the Hardage site. During and after the operations, waste liquids migrated downward from several unlined impoundments, principally the Main Pit, North Pit, and West Pond (mixing) areas and to a lesser extent from the Sludge Mound, and East Pond (mixing) areas, and random spills on the site. Presently, approximately 70 acres of groundwater on and adjacent to the site is contaminated by organic compounds. Groundwater contaminant plumes have migrated east and southwest of the site. Contamination has entered the North Criner Creek alluvium, and has recently had a low but measurable impact on surface water quality (August 7, 1989 sampling). Surface and shallow subsurface soils at and around the source areas are contaminated by low levels of metals. Approximately 278,000 cubic yards of highly contaminated material exists in the Main Pit, Barrel Mound and Sludge Mound which contains soil, sludge, waste liquid, and intact drummed waste.

4.2.1 Impact of Disposal Operations

During operation of the site, several potential sources of groundwater contamination existed. These were:

- o Main pit/Barrel mound
- o Sludge Mound
- o North Pit
- o West Pond (mixing) areas
- o East Pond (mixing) areas
- o Miscellaneous spills, drum leaks, etc.
- o Contaminated runoff paths and south pond

Since liners were not constructed in any of these areas to limit waste seepage, and since the permeability of the soil profile and shallow bedrock is relatively uniform across the site, it is believed that those areas where waste liquids were impounded for the longest periods of time contributed most to groundwater contamination. The longer-term liquid storage and disposal areas were the Main Pit, Barrel Mound, Sludge Mound, West Pond, North Pit, and to some extent, the East Pond (see Figure 1-2). The remaining areas contributed lesser amounts of contaminants to groundwater contamination for reasons as follows:

o Miscellaneous Spills - these were due to the nature of operations.
Although drums were occasionally stored on site, the typical practice was to immediately discharge or dump wastes into the pits upon receipt.
Therefore, spills probably did not release large volumes of waste liquids.

Runoff - No information exists to indicate any impoundments were breached, or liquid waste was directly released except for limited seeps. Rainfall presumably contacted wastes, dissolving contaminants and carrying them down slope from the source areas. However, the contaminants in runoff would be highly dilute, as compared to that in waste pits. In addition, any infiltration of runoff would be transient, as compared to the continuous release from pooled waste liquids such as those in the main pit.

4.2.2 Remaining Contaminant Sources

In addition to contaminants which have dissolved into groundwater beneath and adjacent to the site, several potent "sources" exist which will tend to release further contamination from the site. These sources are:

- a) Main Pit/Barrel Mound
- h) Sludge Mound;
- c) Residual soil contamination in the North pit and immediately west of the main pit; and
- d) NAPL in hedrock beneath the source areas.


The content and character of these four sources is generally as follows:

a) Main Pit/Barrel Mound:

The Barrel Mound was built by random dumping of drums and the periodic spreading of soil to allow further drum dumping. As a result, the Barrel Mound is highly variable. Based on the history of disposal operations and data from three exploratory borings done in 1988, the mound consists of a two to three foot cover of native soils underlain by randomly oriented drums mixed with soils and waste sludges. At a depth of 5 to 10 feet, drilling yielded little data other than the depth to liquids, due to minimal core recovery. The liquids present at the base of the Barrel Mound appear to consist of a 6 inch layer of waste floating on water (L-NAPL or light non-aqueous phase liquids); 4 feet of water; and 4 feet of heavier than water wastes (D-NAPL or dense non-aqueous phase liquids) on the hedrock surface (see schematic illustration, Figure 4-5). The Barrel Mound would, due to the nature of its construction, he expected to have a large number of voids in and around drums. This expectation was supported by difficulties encountered in closing one boring (high grout take) and the inability to hail down waste liquid levels in two other borings. The other significant finding in the harrel mound horings was the apparent contamination of bedrock immediately underlying wastes.

At its southern end, the Barrel Mound grades into the Main Pit. The Main Pit is predominantly contaminated soil, however, concentrations of drums similar to those found in the Barrel Mound are present in about 1/3 of the main pit, particularly along the west bank. Locallized pools of waste, similar to that in the Barrel Mound, are likely to be present in the Main Pit. While exploratory borings did not encounter such pooled liquids, areas of drum concentrations, those areas where pooled liquids would most likely be present, were intentionally avoided in drilling.

FIGURE 4-5
MAIN PIT AND BARREL MOUND CROSS-SECTION



Approximately 113,500 gallons of liquid are present in the soils of the the Main Pit/Barrel Bound (vadose zone) which together total 3.62 acres. An estimated 18,000 drums are buried in these areas representing some 660,000 gallons of stored liquids. (This assumes that two-thirds of the drums may be full).

h) Sludge Mound:

The Sludge Mound consists of layers of contaminated soil, oil recycling residues, and styrene tar wastes. Borings in the Sludge Mound indicated pockets of moist "stringy" sludge in addition to the overall soils contamination.

Approximately 58,000 gallons of liquid are present in the Sludge Mound (totalling 1.72 acres) weakly held in soil pores under capillary forces.

- c) Residual Soil Contamination:
 The former North Pit is underlain by a number of pockets of contaminated soils and 50 to 80 drums huried in shallow trenches. Sediment in the drainage channel along the west side of the Main Pit has been heavily contaminated by waste seepage from the Main Pit to a depth of five to ten feet. Contaminated soils are also present in the west pond area.
- d) NAPL in Bedrock:
 Pure free-phase (NAPL) has been observed at three locations adjacent to the source areas (B-13, MW-6, and MW-2). These wastes are present both at the water table and in the deeper more competent sandstone (Stratum III). The NAPL tends to be several thousand times as contaminated as the surrounding groundwater. However, similar to an oil layer floating on water, the separate phase waste cannot fully dissolve into the water. In the subsurface, clean groundwater tends to pick up dissolved contaminants as it flows around and through the NAPL. In this manner, the NAPL acts as a potent source of continuing contamination within the normal groundwater flow regime. Pockets at and beneath the water table are in a position to readily contaminate the surrounding groundwater.

Liquid accumulations have created a pool of liquids at the bottom of the main source areas estimated to be 956,000 gallons (see Figure 4-5).

The Main Pit, Barrel Mound and Sludge Mound are the largest sources of potential further site contamination. Exploratory horings have indicated that these areas consist of 278,000 cubic yards of wastes. Chemical sampling has indicated that some 171,500 gallons (113,500 + 58,000) of volatile chemicals are suspended in the soil vadose zone. Pooled liquids and intact drums are estimated to total 1,616,000 gallons (560,000 + 956,000), although precise quantification of the volume is not possible.

Table 4-1 lists a number of EPA classified carcinogens detected in the source area characterization holes.

Table 4-1 CARCINOGENS¹ DETECTED IN THE SOURCE AREAS CHARACTERIZATION HOLES²

Compound	Class
2,4,6-trichlorophenol	B 2
bis(2-chloroethyl)ether	B2
1,4-dichlorobenzene	B2
2,6-dinitrotoluene	B 2
1,2-diphenylhydrazine	B 2
isophorone	С
N-nitrosodiphenylamine	B2
bis(2-ethylhexyl)phthalate	B2
butyl benzyl phthalate	С
beno (a) anthracene	B 2
benzene	A
1,2-dichloroethane	B2
1,1,2,2-tetrachloroethane	С
chloroform	B 2
1,1-dichloroethene	С
methylene chloride	B2
tetrachloroethene	B2
trichloroethene	B2
PCB-1260	B2
toxaphene	B2
vinyl chloride	A
1,1,2-trichloroethane	C

EPA classified carcinogens
Reference: USEPA, Health Effects Assessments Summary
Tables, Second Quarter, 1989.

1

² Source USEPA (1985)

4.2.3 Pathways and Extent of Contamination


Contaminants have been transported on and away from the site by groundwater flow. Additional contaminants have also migrated from the source areas by way of surface water runoff; however, sampling data from wells in the alluvial aquifer indicate that groundwater flow, rather than surface water runoff, has been the predominant pathway for migration. Groundwater containing dissolved contaminants migrates vertically and southwestward toward the North Criner Creek alluvium and then upward into the alluvium and into the Creek.

Upward migration of groundwater from Stratum IV into the alluvium of North Criner Creek is documented by upward gradients in water levels of wells constructed at different depths in the alluvium. If contaminants are entering the alluvium primarily from the underlying bedrock (Stratum IV) and moving upward, contaminant concentrations should be higher in the lower part of the alluvial aquifer than in the upper portion. Conversely, if the contaminants are entering the alluvial aquifer primarily by percolating downward from the surface runoff water, the concentrations in the upper groundwater should be higher than in the lower groundwater. Sample analyses data from two different depths in the aquifer (wells MW-12S, -12M and MW-13S, -13M) show that the volatile organic chemical concentrations are greatest in the lowest portion of the aquifer, indicating that the contaminants have probably migrated through the hedrock from the site and into the lower alluvium (as opposed to the surface water pathway) (Reference, Affidavit of John B. Robertson).

During site operations, volatilization of chemicals into ambient air resulted in the release and transport chemicals offsite. This pathway was reduced with closure of the pits and capping of wastes. No residual effects have been identified, and none are believed to exist from air pathway transport due to the volatile organic nature of contaminants. At the present time and in the near future, transport of contaminated groundwater and discharge to surface waters are the only pathways of consequence. If the site is not properly remediated, contaminants will also eventually be released from the site in substantial quantities by erosion and runoff and to a lesser extent through slow volatilization to the atmosphere. As contaminants are exposed there would be an additional pathway for risk through direct contact with contaminated materials. The above pathways are discussed in further detail below.

Groundwater:

The principal pathway of contaminant migration at the Hardage site is through dissolved phase groundwater flow. Groundwater contamination emanating from the source areas extends approximately 600 to 800 feet to the east farm ponds. The contamination plume extends offsite to North Criner Creek, approximately 1600 feet. The plume in the alluvial aquifer is distorted, both parallel to and towards North Criner Creek. Overall, the groundwater plume underlies approximately 70 acres on and adjacent to the site (Figure 4-6, Area 3).



- (1) Predominantly NAPL Plume
- 2 Semi-volatile Plume
- 3 Volatile Plume

FIGURE 4-6
APPROXIMATE EXTENT OF
GROUNDWATER CONTAMINATION

Reproduced from best svallable copy.

The groundwater contaminant plume contains a wide variety of volatile organic chemicals which include toxic compounds such as 1,2-dichloroethene and trichloroethene. A summary of contaminants and their concentration for onsite wells is presented in Table 4-2. Beneath and immediately adjacent to the source areas (Figure 4-6, Area 1) volatile, semivolatile, and pesticide compounds are present at their highest levels, in some cases exceeding 25,000 pph for volatile organics. At three locations NAPL has been encountered (MW-6, B-13, and MW-2). Additional pockets of NAPL are almost certainly present in other areas beneath the source areas, particularly at the Barrel Mound. A somewhat larger portion of the plume (Figure 4-6, Area 2) contains both volatile and semivolatile contaminants, but not NAPL. This, the "semi-volatile plume", extends over 600 feet eastward to where the plume discharges into the east farm ponds. To the southwest, the semi-volatile plume extends only about 200 feet (to well MW-45). Contamination by volatile organic chemicals (VOC) is most widespread and defines the extent of contamination. The VOC plume extends southeast into the alluvium of North Criner Creek (see Figures 4-6, Area 3). Contaminated groundwater flowing southwest through the onsite hedrock discharges to the alluvial aquifer. This discharge constitutes the source of continuing contamination in the alluvium (see Figures 4-4 and 4-7,. Average flow rates along this pathway have been estimated at 110 feet per year (Affidavit of John B. Robertson).

Discharge of Contaminated Groundwater to Surface Water:

Both the east farm ponds and North Criner Creek receive contaminants via discharge of groundwater to the surface waters. The contaminants entering North Criner Creek are chlorinated ethanes and chlorinated ethenes. Since these chemicals are volatile, natural processes rapidly strip volatiles from the surface waters, and release them to the air. Sampling of North Criner Creek has only most recently detected contamination (1-2 dichloroethene, 5 pph and trichloroethene approximately 2 pph), and supports the helief that the discharge of contaminated groundwater can have a measureable impact on surface water quality in the Creek.

Volatile chemicals also enter the east farm ponds. Sampling to date has not indicated the presence of volatiles; however, more persistent semivolatile chemicals are seeping into the southernmost east farm ponds and are impacting water quality in the immediate vicinity of the seeps. These compounds appear to be entering the farm pond due to seepage of NAPL along the bedrock surface. Dilution of this seepage is presently occuring so that impacts on water quality of the pond have not been measureable.

Comparison of the Groundwater Data from the Alluvial Wells Adjacent to the Hardage/Criner Site with Maximum Contaminant Levels Set by the Safe Drinking Water Act

TABLE 4-2

Contaminant	MCL ug/l	- Greatest Concentration ug/l	Total Detections	Total Detections >MCL	Grantest "Ouantitative" Concentration up/l	Total "Quantitative" Detections	Total "Quantitative" Delections >MCL
Trihalomethanes	100	8.7	7	0	8.7	7	0
1,2-Dichloroethane) 5	240	13 }	8	240	13	
1,1,1-Trichioroethane	200	120	26	0	120	26	0
Vinyl chloride	2	4.5	a	2	4.5	4	2
1,1-Dichloroethene	7	57	27	20	57	27	20
trans-1,2-Dichloroethene	70	370	25	13	370	25	13
Trichloroethene	5	290	29	28	290	29	20
Tetrachforoethene	5	29	17	11	29	17	11
Benzene	5	1 1	1	0	1	1	•
PCBs	1 5	4.4	1;	0	4.4	•	0
Arsenic	50	l e:	19]	0	12	18	0
Barlum	1000	990	52	0	606	41	0
Cadmium	10	11	4	1	•	1	0
Chromium	50	129	6 \	2	37	2	
Fluoride	4000	380	21	ō	380	21	o
_ead	50	28	7	ō	28	4	ا ة
Aercury	2	0.6	2	ō	0.6	2	. o
Vitrate	10000	6100	20	ō	6100	20	Č
Selenium	10	76	14	4	78	12	4
Silver	50	6	2:	0		2	Ô

References:

K. W. Brown & Associates, Inc. August 9, 1989. Groundwater Contamination at the Hardage Site: Organic Data Tabulated by Well.

K. W. Brown & Associates, Inc. August 9, 1989. Groundwater Contemhation at the Hardage Site: Inorganic Data Tabulated by Well.

TABLE 4-2 (continued)

A Comparison of the Groundwater Data at the Hardage/Criner Site with Maximum Contaminant Levels Set by the Safe Drinking Water Act

· · · · · · · · · · · · · · · · · · ·					Greatest	Total	Total
ı		Greatest	Total	Total	"Quantitative"	"Quantitative"	"Quantitative"
Contaminant	MCL	Concentration	Detections	Detections	Concentration	Detections	Detections
	ug/l	υρ/Ι		>MCL_	Ngu		>MCL
Trihalomethanes	100	154900	74	18	154900	60	15
Carbon tetrachloride	5	4	1	0	0	0 '	0
1,2-Dichloroethane	5	350000	69	76	350000	76	65
1,1,1~Trichloroethane	200	32000	110	26	32000	85	23
Vinyl chloride	2	10000	37	31	10000	33	27
1,1-Dichloroethene	7	8200	119 (95	8200	97	76
trans-1,2-Dichloroethene	7C	9500	114 [64	9500	91	52
Trichioroethene	5	11000	125	107	11000	100	82
Tetrachioronthene	5	28000	92	68	26000	74	55
Benzene	5	420	24	9	420	21	7
1,2-Dichlorobenzene	75	2500	20	5	2500	16	2
PCBs	5	1000	7	6	1000	6	6
Arsenic	50	26	56	0	26	52	0
Barium	1000	3300	204	202	712	138	0
Cadmium	10	75	20	9	75	14	7
Chromium	50	1180	52	17	1180	26	6
Fluorice	4000	11000	76	1	11000	76	1
Lead	50	94	22	1	94	9	1
Mercury	2	1.1	12	0	0.7	9	0
Nitrate	10000	7000	71	0	7000	71	o
Selenium.	10	76	53	13	1	34	8
Säver	50	17	10	0	17	9	ā

References:

K. W. Brown & Associates, Inc. August 9, 1989. Groundwater Contamination at the Hardage Site: Organic Data Tabulated by Well.

K. W. Brown & Associates, Inc. August 9, 1989. Groundwater Contamination at the Hardage Site: Inorganic Data Tabulated by Well.




FIGURE 4-7

Reproduced from best available copy.

DISTRIBUTION OF TOTAL VOLATILE ORGANICS IN STRATUM III AND THE ALLUVIUM

Surface Water Runoff and Sediment Transport:

Surface water runoff and sediment transport will constitute substantial pathways for contaminant transport from the site over the long-term if the site is left unremediated. Vegetation over much of the site, including the source areas, is sparse due to the removal of the topsoil in the course of site operations. The lack of vegetation contributes to soil erosion. In addition, the final contour of the waste mounds is not conducive to long-term stability. Leachate seeps from the western side of the waste mounds are common in the wet, spring months. Rainfall runoff tends to spread this leachate downslope, resulting in visible contamination as far southwest as the existing interceptor trench.

4.2.4 Future Contaminant Migration

Left unremediated, contaminants will continue to migrate off of the site and spread on the site by the following general pathways:

1. expansion of the plumes of contaminated groundwater;

leakage and spread of waste liquids from the Barrel Mound and Main Pit, which will in turn continue to feed the plumes on contaminated groundwater;

 dissolution of contaminants by groundwater infiltrating through the the Sludge Mound, Main Pit, Barrel Mound, and areas of residual contamination; and

 transport of wastes and contaminated soils from the Main Pit, Barrel Mound, Sludge Mound and adjacent mixing areas via erosion and runoff.

5. long-term low-level releases of volatile compounds to the atmosphere

The groundwater contaminant plumes present at the Hardage site have developed over the 17 years since operations started at the Hardage site. Left unremediated, plumes of contamination in the vicinity of both the east farm ponds and North Criner Creek will expand. Modelling of the southwest alluvial plume in the Remedy Report (EPA, 1989) predicted a gradual expansion approaching 2000' (with dilution) even with the source of contamination to the alluvium cut off. Without source control and groundwater remedial actions, the southwest alluvial contaminant plume would certainly continue to expand southeastward, parallel to the stream. The plume near the east farm ponds may expand eastward beneath the ponds, although this is uncertain due to remaining questions about groundwater and surface water interaction acting as a barrier to migration around the ponds.

Waste liquids in the Barrel Mound and Main Pit will continue to migrate into the surrounding hedrock and groundwater in accordance with the conceptual model illustrated in Figure 4-5. Liquids in the Barrel Mound are released as drums of waste liquid corrode and as liquids drain from saturated soils (under gravity and consolidation). These liquids drain downward through the permeable mounds and accumulate on the less permeable sandstone and siltstone hedrock surface at the hase of the pit. This pool of waste liquids tends to drain downward under gravity through pores and fractures in the shallow hedrock. As the liquids move downward some 10-15 feet helow the base of these pits, they encounter a less permeable hedrock horizon and tend to spread out across the upper surface of that horizon and migrate with a lateral component, as seen at locations MW-2 and MW-6.

In their present condition, the source areas are susceptible to infiltration of rainfall. As this water percolates downward through the source materials, it dissolves contaminants and carries them downward to the groundwater system. This is a potential continuing source of release on the site.

Over time, erosion of contaminated soils is expected to increase to a point where substantial offsite releases occur via erosion and runoff.

5.0 SITE RISKS

The Hardage site received hazardous wastes that are either known or suspected carcinogens such as vinyl chloride and benzene. Table 4-1 gives a more complete list of carcinogens found at the site. Other compounds either are or are believed to be acutely toxic or capable of causing damage to specific organs. Some of these compounds also bio-accumulate in plant, animal, and human tissues. The Hardage Site was permitted to receive all types of industrial and hazardous wastes except radioactive wastes. Table 2-1 lists some of the wastes known to have been received at the site.

There are four primary ways humans can be exposed to the hazardous wastes at the Hardage site. The first and most important of these is exposure to contaminated groundwater. The groundwater at the Hardage site is contaminated with waste migrating from the source areas into the bedrock and alluvial groundwater systems. Not only is the groundwater under the site contaminated with these hazardous wastes, but the contamination has spread beyond the site to the south and has already forced local residents to stop using their water wells.

The contaminated water wells are located in the North Criner Creek Alluvium which lies below the Creek south of the site. This aquifer is contaminated with the chemicals exceeding the standards for consumption of drinking water as set under the Safe Drinking Water Act that are also given under the column titled MCL in Table 4-2.

As Table 4-2 shows, eight of these contaminants are already above the limits. The nearest of the contaminated residential wells is the old Corley well. The old Corley well is located approximately 500 feet southwest of the site. Estimates of the risk of cancer from lifetime use of residential water contaminated at the level of the old Corley well range from 0.0007 (seven per ten thousand) to 0.006 (six per thousand) far above the one in one million level commonly used as an acceptable risk. These estimates were arrived at using average concentrations of contaminants in the old Corley well and making assumptions about standard ingestion of water, inhalation exposures and dermal exposures from household use.

With the North Criner Creek alluvium already contaminated, one of the goals of the cleanup will be to restore the groundwater to a useable condition. The standards used to judge the effectiveness of the cleanup alternatives for groundwater will be the Maximum Contaminant Levels set under the Safe Drinking Water Act (MCLs). The effect of the proposed cleanup plans can be compared through their effects on the concentration of contaminants in the North Criner Creek alluvium. The proposed EPA remedies would result in lower concentrations of contaminants in groundwater in the alluvium of North Criner Creek through removal and destruction of contaminants at the source and interception and treatment of groundwater by trenches. While it is not possible to accurately assess how long the source areas would continue to bleed contaminants into the groundwater systems, it does not require and expert to conclude that if the HSC remedy leaves 10 or 100 times more of the most problematic waste liquids in the site than EPA's remedy, then the long-term duration of the EPA remedy would be shorter. The EPA remedy would therefore attain MCLs more quickly than the HSC remedy.

Direct contact with wastes on the surface of the site also poses hazards; however, the health risk is highly variable depending upon area of exposed waste and level of human traffic and has not been quantified. Human traffic on the site is minimal; but cattle did occasionally graze on the site. Contamination of the food-chain (for example beef and milk from cattle eating contaminated grass) by lead, chromium, pesticides, and PCBs on the surface of the site poses long-term hazards. This concern prompted construction of a fence to keep cattle and people off of the source areas. Certain compounds such as pesticides and PCBs have the ability to bioconcentrate through successively higher levels of the food chain (EPA, 1985a).

Inhalation of volatiles and concentrated airborne particulates on and possibly adjacent to the site may also pose long-term hazards if the site remains unremediated, but again this risk is highly variable depending upon the quantity of exposed contamination.

6.0 DESCRIPTION OF ALTERNATIVES

A large number of remedial alternatives have been formulated to address part or all of the Hardage site. As discussed in Section 3, the site has been considered as two "operable units". Source Control measures were considered by EPA in a 1986 FS. In November 1986, EPA issued a ROD which selected a Source Control remedy with incineration of liquid wastes and stabilization and containment of solids in a new landfill to be built on-site. HSC objected to the selection of this Source Control remedy and proposed an alternate Source Control remedy in December 1986 which called for in-place containment of the waste source areas by a cut-off wall and groundwater pumping. HSC declined to implement the EPA selected remedy which resulted in litigation in 1986. EPA maintained that the remedy selected in the 1986 ROD was technically sound and completed the Source Control Remedial Design in 1988. In 1987, HSC signed a partial Consent Degree with EPA for the conduct of an RI/FS for groundwater (Management of Migration). In May 1989 HSC, pursuant to the Consent Decree, submitted a draft FS on Management of Migration to EPA for review and approval.

During conduct and preparation of the groundwater RI/FS, uncertainty arose over the impact of RCRA Land Disposal Restrictions on the EPA selected Source Control remedy. To alleviate this uncertainty, EPA undertook consideration of an alternative Source Control remedy based upon the new technology of in-situ soil vapor extraction. Evaluation of soil vapor extraction in conjunction with alternative presented in the groundwater FS resulted in consideration of alternatives addressing the entire site in contrast to the original Operable Unit approach. On June 30, 1989, the United States advised the District Court of EPA's decision to consider a comprehensive site remedy.

On July 6th and in greater detail on October 13, 1989 the defendants presented to the court their plan to further define an additional remedial alternative. This, the HSC alternative, was similar to EPA's alternative except that the HSC plan did not include soil vapor extraction, enhanced recovery of containerized liquids, or the shallow waste liquid recovery trench proposed by EPA.

Previous and new alternatives for the control of the contaminant sources are summarized below in Section 6.1. Alternatives for groundwater as contained in the groundwater FS are summarized in Section 6.2. Common monitoring and support components for Groundwater and Source Control alternatives are listed in Section 6.3. Finally, Source Control and Groundwater alternatives are combined and summarized in Section 6.4.

6.1 Alternative Source Control Components

A number of alternatives were considered for remediation of the Source Control areas prior to the 1986 ROD. These can be seen in more detail in the 1986 ROD in Appendix F, along with evaluation criteria for remedy selection. Those remedies which were considered fell into four basic categories: no action; disposal onsite in a landfill (the EPA selected remedy in the 1986 ROD); containment of wastes in place (the HSC counter proposal of a cut-off wall); and incineration (also considered in the 1986 ROD). The following four sections summarize each of these categories.

- 6.1.1 No action. As the title implies, no work would be done to mitigate hazards from the site. The alternate water supply, security fence, and site stability measures would not be maintained.
- 6.1.2 Onsite Landfill (EPA 1986 ROD Remedy). The source areas would be excavated and separated for treatment. Organic liquids would be bulked and shipped offsite for thermal treatment at a permitted facility. Inorganic liquids would be treated and discharged to an onsite impoundment for evaporation. Solids would be stabilized by blending with 8-10% cement kiln dust and placed in a new double lined landfill cell constructed on-site in accordance with the Minimum Technology Requirements (MTR) of RCRA. The 1986 estimate of most probable cost was 70 million dollars.
- 6.1.3 Containment of wastes, Cap and Cut-off wall (HSC Proposal). A plastic cement "cut-off" wall would be constructed in panels so as to encircle the source areas. This wall would range from 70 to 130 feet in depth and, at its base, key 10 to 20 feet into the low permeability siltstone and mudstone of Stratum IV. Wells would be drilled through the Source areas and completed in the bedrock within the periphery of the wall. The water and wastes would be pumped from these recovery wells in an effort to induce a hydraulic gradient inward through the wall and prevent the outward migration of contaminants. Pumping would be conducted indefinitely.

Vertical waste liquid extraction wells would be drilled into the Barrel Mound and pumped in an effort to remove pooled liquid for treatment. In addition, lateral drains would be drilled from the west into the base of the Barrel Mound. These drains would slope slightly downward out of the mound to allow free drainage of waste liquids and groundwater from the Barrel Mound over time.

An effort would be made to speed consolidation of the Barrel Mound by placing a 20 foot thick soil layer as a surcharge for a period of 6 months to a year. After removal of the surcharge, a MTR cap would be installed over the source areas. The most probable cost estimate was 25 million dollars. 6.1.4 Incineration (EPA Proposal in 1986 ROD). The source areas would be excavated. Wastes would be incinerated in a kiln constructed onsite or at a commercial incinerator offsite. The ash would still contain metals and until it could be proven otherwise through de-listing, would require disposal as a hazardous waste. Estimates in 1986 for cost of incineration ranged from 133 to 374 million dollars.

The no action alternative was eliminated from consideration early as not being protective of human health or the environment due to continued vertical and lateral migration source area wastes offsite. Containment of the contamination in place was eliminated due concerns over continued migration of the contamination, doubts that containment techniques such as slurry walls could be installed effectively, and concerns relating to merely containing the sources of contamination rather than actively remediating them to achieve a permanent reduction in their volume, toxicity, or mobility.

The alternatives that remained were onsite disposal and incineration. The onsite landfill alternative was eventually selected as providing a degree of protection to human health and the environment similar to that which could be achieved with complete incineration, but which could be carried out in a shorter time and at a reduced cost. A more detailed comparison is given in the 1986 ROD in Appendix F. With this background, onsite disposal was selected in the 1986 ROD.

The new alternative for Source Control in the October 1989 Proposed Plan contained components for a new approach to Source Control. These components are as follows:

6.1.5 Liquid Extraction Wells

A system of vertical extraction wells would be installed throughout the three main source areas. The wells would be used for extracting free liquids that are found in the source areas, and liquids that would be released from the drums as a result of the lancing procedure described below, should it be used. The wells could also be used as part of the soil vapor extraction process described below.

An estimated approximately 956,000 gallons of aqueous and nonaqueous liquids presently reside in the saturated portions of the source areas. The quantity of residual liquids trapped within the unsaturated portion of the source areas is estimated as at least 170,000 gallons.

Additional liquids are likely to be found in drums buried in the source areas. Assuming that one third of the 18,000 drums estimated to be in the Main Pit/Barrel Mound contain organic liquids, an additional 660,000 gallons of liquids may be present that require removal and offsite disposal.

The liquids pumping operation is not expected to remove all of the free fluid found within the source areas due to localized pooling between wells, nor will it address the liquids residing in the unsaturated zone. The nonaqueous-phase liquids removed from the extraction wells and trenches will be sent to a hazardous waste treatment, storage, and disposal (TSD) facility for incineration.

6.1.6 In-PTace Drum Lancing

One method considered to assist in the removal of the liquids remaining in the huried drums was to lance the drums in place. The lancing process would release the liquids for subsequent removal by the wells or through the soil vapor extraction process (see Figure 6-1).

The lancing effort would be accomplished using commercially available construction equipment capable of driving solid spark-resistant Cu-Be rods to subsurface depths greater than 40 feet. The lancing would take place throughout the Barrel Mound and in areas of significant concentration of drums in the Main Pit. 'Magnetometer data highlighting areas of drum concentrations would be used to select appropriate areas in the Main Pit for lancing.


The lances would be advanced to the bottom of each target area at a nominal triangular spacing of 22 inches. The released liquids would be collected and removed via the extraction wells, a U-shaped trench (described later), or the soil vapor extraction system (described later).

The progress of the lancing operations would be controlled by monitoring the rise of fluid levels in nearby extraction wells. The effort would be made to prevent the accumulation of fluids to greater levels than those that currently exist in the source mounds. Non-aqueous phase liquids (NAPL) released by the lancing process and removed in the liquid extraction system would be sent to a TSD facility for treatment and disposal.

While lancing was considered as an option for the removal of drummed liquids, excavation of drums has several advantages over lancing for the removal of liquids. These include the assurance that all liquids are removed and the elimination of the introduction of additional liquids to the vadose zone on the short-term.

6.1.7 Drum Excavation

Liquids in drums from the Barrel Mound and the west side of the Main Pit can be removed from the source areas by excavating the drums as originally intended in the 1986 ROD instead of performing drum lancing. The excavation option would remove free liquids directly from the surface and from any drummed liquids in the source areas by direct removal. It is expected that excavation, utilized successfully at a number of other sites, would be more efficient than lancing in removing free and containerized liquids in the Main Pit/Barrel Mound. Figure 6-2 indicates areas that would be targeted for drum excavation. Drums that are removed from the source areas would be staged for sampling and consolidation with similar wastes. Drummed organic liquids would be consolidated for offsite treatment and disposal. The liquids would be transported to a hazardous waste treatment, storage and disposal (TSD) facility for incineration. Aqueous liquids would be treated onsite by the groundwater treatment facility. Any drums containing solids, or having solid residues in them after liquids are removed would be placed back into the source areas.



CONCEPTUAL OPERATION OF DRUM LANCING

FIGURE 6-2 AREAS TARGETED FOR DRUM EXCAVATION BARREL MOUND AREA LEGEND EXTENT OF DRUM REMOVAL DRUM CONCENTRATIONS SCATTERED DRUMS AREA OF SIDE SLOPES EXPECTED TO BE REMOVED TO FACILITATE DRUM REMOVAL MAIN PIT AREA 1 INCH - 100 FEET

6.1.8 Excavation of Wastes in Adjacent Areas

Contaminated surface soils and waste materials located away from the source areas will be excavated and transported to the source areas. These materials will be consolidated under a temporary cap for soil vapor extraction along with trench excavation materials and other materials generated during implementation of the remedy. The greatest concentration of contaminated soils and wastes away from the source areas occurs in the North Pit area, where up to 80 drums of wastes as well as contaminated soils are believed to be buried, and in the West and East Pond Areas (see Figure 1-2).

If contaminated water or liquid wastes are encountered in these drums, they will be treated in the groundwater treatment facility to surface water discharge standards, or taken offsite for disposal, whichever is appropriate. The contaminated solids and soils will be remediated as part of the overall remediation program, once they are placed within the source areas and capped.

6.1.9 Soil Vapor Extraction and Treatment

Soil vapor extraction would be conducted in the three main source areas as a means to further capture and destroy the liquids present. Soil vapor extraction is expected to remove a large volume of the highly toxic and mobile volatile organic compounds present in the source areas. The soil vapor extraction systems would consist of a network of extraction wells screened in the contaminated (vadose) zone of the Main Pit/Barrel Mound and Sludge Mound. The dual-purpose extraction wells installed to remove liquids would be used as part of the vapor extraction system.

The liquids pumping operation is not expected to remove 100 percent of the liquids present. Numerous field studies have shown that in excess of 40 percent of the available liquids may remain trapped in the unsaturated zone following gravity drainage and pumping efforts. While not readily amenable to pumping, these residual liquids are subject to further removal by vapor extraction.

Soil vapor extraction works by drawing air through areas containing contamination thereby creating a vacuum in the source areas (see Figure 6-3). This, in turn results in a high evaporation rate of volatile and semi-volatile organic compounds, including significant quantities of toxic and carcinogenic contaminants that are in contact with groundwater and atmosphere. Such contaminants evaporate into the air drawn into the mounds. The contaminated air is then extracted through air extraction wells and is treated onsite to destroy the ontamination.

If lancing used, vapor extraction is also expected to remove a significant uantity of the liquids that remain trapped in the drums.

If there are pockets or low spots in the mounds between the liquid extraction \ lls, the vapor extraction process will further aid in the removal of \ quids that cannot migrate towards the extraction wells.

The air strong and vapors removed by the soil vapor extraction system will be treated in the Best Available Control Technology for thermal destruction

FIGURE 6-3

SOIL VAPOR EXTRACTION--SCHEMATIC

of toxic vapors prior to discharge to the atmosphere. Vapors generated by the groundwater treatment system will also be destroyed in this thermal treatment system.

5.1.10 Source Area Capping

Two types of source area capping are planned for the site. A temporary cover would be installed during remediation activities, and a permanent RCRA-compliant cap would be installed once soil vapor extraction and liquid extraction activities are complete. The temporary cover will consist of compacted, minimum 1-foot thick, low-permeability soil with vegetation to minimize erosion. Repairs will be made as needed to compensate for damage from settlement and erosion.

Permanent RCRA-cap installation would be initiated once the drummed liquids are removed, soil vapor extraction has been completed, and the liquid extraction wells have been decomissioned. The cap will be location over the Main Pit. Barrel Mound and Sludge Mound areas as illustrated in Figure 6-4.


<u>Section 6.2 Groundwater Remediation Objectives and Alternative Groundwater Components</u>

In addition to the new components considered for Source Control, remedial alternatives for contaminated groundwater were developed and described in detail as part of the Management of Migration Operable Unit RI/FS reports. All alternatives were developed assuming some form of concurrent Source Control remedial action. The alternatives were developed in light of the overall goal of restoring groundwater to its beneficial use within a reasonable timeframe.

Consideration of the hydrology and contamination of the hedrock aquifer at the site has led to the conclusion that restoration of bedrock groundwater underneath the source areas is technically impractical over a reasonable time period (a few decades). This conclusion is supported by the fact the some D-NAPL has escaped from the source areas and will continue to serve as as source for dissolved contaminants in groundwater. Also, some contaminants have diffused into dead-end cracks and fine-grained pores in the rock matrix; those materials will take a relatively long time to diffuse out of the pores and cracks during an active or passive restoration program. In view of these facts, the most effective way to address groundwater contamination onsite is through various containment efforts designed to control the spread of groundwater plumes and rotect downgradient areas from future plume migration. Such efforts will be significantly aided by source control actions that in a timely manner permanently reduce the potent source liquids which continue to load the groundwater system with contaminants. Consequently, component alternatives wer screened and refined based on their effectiveness in meeting the following c jectives:

o intercept and captu: groundwater that is migrating towards the alluvial aquifer an the east farm ponds, thereby protecting offsite areas from sture contaminant impacts, and commencing the process of natu il restoration in the alluvial system;

FIGURE 4-4
FINAL SOURCE AREA CAP



Reproduced from best svallable copy.

- o monitor and control contaminated groundwater discharge to North Criner Creek to assure that Oklahoma Water Quality Standards for North Criner Creek and Criner Creek are met; and
- o prevent domestic and agricultural use of contaminated groundwater through continued supply of alternate water to affected residents.

In view of these objectives, ERM-Southwest, on behalf of the HSC (and pursuant to a partial Consent Decree with EPA) developed and evaluated 21 remedial action alternatives by combining 6 remedy elements (see Table 6-1). Details of this analysis is presented in the Management of Migration FS. All of the initial alternatives developed included groundwater and surface water monitoring, as well as actions to minimize runoff from the source areas. All alternatives relied on institutional controls (such as deed restrictions) to prevent the use of potentially contaminated groundwater as a drinking water supply. The alternatives also included continued operation of alternate water supplies to nearby residents.

Screening of these alternatives was conducted in the FS based on effectiveness in containing and capturing contamination, and cost. Six groundwater alternatives were retained after this screening for detailed analysis, and were summarized below:

Alternative	Description
A	No Action
В	Primary Controls - institutional controls on groundwater use, maintenance of alternate water supplies, and surface water controls to limit the discharge of contaminated groundwater to surface water.
С	Alternative B and Alluvial Recovery - groundwater recovery from the North Criner Creek alluvium using a well network or interceptor trench system (see Figure 6-5)
Ε	Alternative B and Alluvial, South Pond and Southeast Area Recovery - groundwater recovery from the North Criner Creek alluvium, from hedrock southwest of the Main Pit, Barrel Mound and Sludge Mound, and from hedrock east and southeast of these three source areas (see Figure 6-6) using a well network or interceptor trench system
К	Alternative B and South Pond Area Recovery - groundwater recovery from hedrock buthwest of the three main source areas using a well network or trench system, with the the option of a local st-off wall along the site fence houndary in place of a umber of recovery wells
N	Alternative B and Main Source Area Recovery - groundwater recovery associated with source control measures using a well network.

Summary of Afternative Elements

Second Operable Unit Feasibility Study Royal Hardage Sife - Criner, Oktahoma

1			1	1 (
1 1 1	Remedy Elements	 	Primary (i in Situ Bio-i I remediation i		Southeast b Recovery t	Recovery I Trench I
IA I	"No Action"	x	 				1	i 1
18	Primary Controls		X	1			1	
1c 1	Primary Controls and Alluvial Ground Water Recovery)	K .	l x			1	1
10	Primary Controls, Alluvial and South Pond Area Recovery	1 X	х	1 x	 	1		1
1 = 1	Primary Controls, Attuvial South Pond Area and Southeast Recovery	i v	T	 	1	¥	T.	1
) r 1	Primary Controls, Alluviat and Southeast Recovery	1 x	r I x	t t t x	1		R I	
10	Primary Controls and in Silu Bioremediation	i u	 	; t	1 1 x		i i	
IH:	Primary Controls, in Situ Bioremediation and South Pond Area Recovery	t u	1 x	1 1 1	 	T T	1	1
1	Primary Controls, in Situ Bloremediation, South Pond Area and Southeast Recovery	} } ! u	! ! !	1 1 1	{	1 u	i x	
11	Primary Controls, in Situ Bioremediation, and Southeast Recovery	t 1 m] 	ł !	1 x	†	l l x	
IK I	Primary Controls, and South Pond Area Recovery	1 1 x	1 ! x 1	† { }	† † †	f x	† · · · · · · · · · · · · · · · · · · ·	

TABLE 4-1 (Continued)

Revision #0 May 30, 1984


Summary of Alternative Elements


Second Operable unit Feasibility Study Royal Hardage Site Criner, Oktahoma

	CFINET, OKTANOMA						
I I I Remedy Elemanis	i I monttoring i	Primary Controls		in Silu Bio-i i remediation i			Recovery 1 Trench 1
It Primary Controls 1 South Pond Area and 1 Southeast Recovery	1 1 3 1 (t I x) 	i	я () R	; t l
IM Primary Controls and I Southeast Recovery) {	l K	1			R)
IN Primary Controls and Main Source Area Recovery) x	т Т	 	; ;			1
10 Primary Controls, Alluvial Recovery and Main Source 1 Area Recovery	1 x 1	1 X	; ;	; ;	 		# 1
IP Primary Controls, Alluvial and South Pond Area Recovery and Main Source Area Recovery	 	, , , , , , , , , , , , , , , , , , ,	f l l u) } {	т 1 1 1] 	я ,
10 Primary Controls, in Silu 1 Bioremediation, and Main 1 Source Area Recovery	(j K	1 1	Г 1 ж 3			х
IR Primary Controls, in Situ 1 Bioremediation, South Pond 2 Area Recovery and main 3 Source Area Recovery	1 1 1 I	† 	 	i i r	i i i x	i i i	
IS Primary Controls, South Pond Area Recovery and main Source Area Recovery) x 		 	i g		
If Primary Controls, main Source Area Recovery, Southeast and South Pond Recovery		f l u	; ; ;	1 1 5	7 (R) (x 1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
IU Primary Controls, Alluvial, I South Pond, Southeast Recovery and Main Source I Area Recovery		† 1 † х †	/		Г	;	1

HOTES

^{&#}x27;a' indicates element is included in potential remediation afternative for screening purposes





Alternative E (illustrated in Figure 6-6) involves the recovery of contaminated groundwater in the southwest alluvial area of North Criner Creek and onsite groundwater recovery west, south, and east of the main source areas. Alternative E has been modified and includes two groundwater components. The onsite interceptor system is known as the V-Shaped Trench. The southwest interceptor system is known as the Southwest Interceptor Trench. Both the V-shaped and Southwest interceptor trenches would be capable, in combination with Source Control components of the comprehensive remedy, of modifying groundwater gradients at the site so as to contain and capture groundwater and D-NAPL migrating from the source areas and off the site.

A third trench, known as the U-Shaped Trench, was considered by EPA during the development of groundwater alternatives in order to prevent uncontaminated groundwater in the vicinity of the Main Pit/Barrel Mound from coming into contact with the source waste materials during remediation, as well as to support source liquids removal operations by intercepting lateral seepage that may ensue from the source areas.

These three recovery systems could be installed at the site to capture contaminated groundwater migrating towards the alluvium and the east farm ponds, provided Source Control measures are also instituted. Collected groundwater from any or all of these systems would be treated onsite to discharge standards before discharge to North Criner Creek. These collection systems are illustrated in Figure 6-7 and each is further described below:

6.2.1 U-shaped Trench

The first trench, known as the U-shaped trench, would intercept shallow seepage issuing laterally from the Barrel Mound and the Main Pit and to collect contaminated groundwater from Stratum I in the vicinity of the Barrel Mound and Main Pit.

6.2.2 V-shaped Trench

The V-shaped trench would intercept and collect contaminated groundwater from all bedrock zones existing above Stratum IV. The trench will be located so that groundwater contaminants already migrating eastward towards the east farm ponds will be captured by the trench, negating the need for additional gorundwater recovery measures east and southeast of the trench.

6.2.3 Southwest Interceptor Trench

The Southwest Interceptor Trench is to intercept and collect contaminated bedrock system groundwater prior to its natural discharge to the offsite alluvial aquifer along North Criner Creek. The trench will extend to Stratum IV and will collect contaminated groundwater from all bedrock zones above Stratum IV. A system of extraction wells could be used as an alternative to the Southwest Interceptor Trench provided they are equally effective at intercepting and collecting contaminated groundwater.

- 52




FIGURE 7

SITE CROSS: ECTION SHOWING TRE VCHES

6.2.4 Ground Water Treatment System

An onsite treatment plant would be provided to treat collected groundwater and surface water. The plant would be sized to handle flows from the groundwater collection trenches and the surface water collection system. The plant incorporates appropriate treatment processes to handle both organic and inorganic contaminants as necessary.

Following treatment, the plant would discharge to North Criner Creek. The plant would be designed to meet the applicable discharge requirements set by the Oklahoma Water Resources Board and the Oklahoma State Department of Health.

6.2.5 Alluvial Ground Water Restoration

Contaminants already present in the alluvial aquifer would be allowed to dissipate by natural dilution, biodegradation, and flushing. Future contaminant inputs to the aquifer will be abated by the trenches and the Source Control elements presented above to allow restoration to Maximum Contaminant Levels in the North Criner Creek alluvium. If alluvial monitoring reveals that estimated natural restoration time and plume dilution rates are not being met, then active restoration would be implemented. An increase in contaminant concentrations in the alluvium after trench installation and pumping, or a decline in the mass of contaminants of less than 40 percent in 10 years, would trigger active restoration in the alluvium.

6.3 Monitoring and Support Components

6.3.1 Remedial Support Facilities

Several components are needed to support the implementation of the remedy. These site control facilities consist of a command post, medical services station, close support analytical laboratory, sanitary facility, equipment maintenance shop, decontamination facilities for both equipment and personnel, and a supply center, gate guard, and communication center.

6.3.2 Institutional Controls

Institutional controls, including fencing, deed restrictions, and maintenance of the availability of an alternate water supply system would be implemented to restrict access to the site and contaminated groundwater.

6.3.3 Surface Water Controls

During implementation of the remedy, surface water drainage from the source areas would be collected as needed. Berms would be constructed to divert uncontaminated runoff water away from the working area to minimize the generation of contaminated water. A retention pond would be used to collect and store surface water prior to treatment. A Treated Water Retention Por would also be used to store treated groundwater prior to discharge to the surface drainage system for North Criner Creek.

Once the temporary cover is in place and the remedy has been implemented, surface water control and treatment would not be necessary. The diversions would be maintained over the life of the remedy as a means to control erosion of the cover.

6.3.4 Remedial Monitoring

A monitoring program would be instituted as part of the remedy to verify that the migration of contaminants has been halted. Streamwater in North Criner Creek would be monitored periodically for an indefinite future time to provide assurance that surface water discharge limits are not being exceeded downstream.

A line of monitoring wells at the downstream end of the alluvial contamination plume would be used to provide assurance that the plume is not expanding downgradient in the alluvial aquifer above acceptable levels.

The quantity and quality of liquids collected from the trenches would also be monitored. The effectiveness of the trenches in maintaining the desired hydraulic gradients and capture zones will be monitored by a series of piezometers positioned along lines perpendicular to the orientation of the trenches.

Bedrock groundwater monitoring wells (both new and existing) would be used to further verify the effectiveness of the trenches in controlling the spread of contaminated ground water.

The cap will also be monitored periodically to assure that differential settlement or erosion processes are not compromising the integrity of the caps.

Monitoring would be used to verify that the quality of downstream water resources is not being jeopardized during the natural restoration process.

Air quality would be monitored both onsite and at the site fenceline to assure that both onsite action levels and Maximum Ambient Air Concentrations are being met during remedy implementation.

6.4 Comprehensive Alternatives

From all of the components described in Sections 6.1, 6.2 and 6.3, three comprehensive remedial alternatives were assembled for consideration. These three alternatives, the Revised EPA Remedy, the Partially Revised EPA Remedy, and the HSC Remedy are described below and in Table 6-2.

6.4.1 Common Elements

Certain of the components from Section 6.1 are included in all three of the comprehensive alternatives. These are Institutional Controls (6.3.2), Surface Water Controls (6.3.3), Remedial Monitoring (6.3.4), and Remedial Support Facilities (6.3.1)

6.4.2 Revised EPA Remedy

The Revised EPA Remedy is a new source control remedy combined with ground-water collection and treatment. This remedy would remove a substantial portion of the liquid wastes, including many highly toxic and mobile volatile organic compounds, from source areas, thereby reducing the volume, toxicity and mobility of hazardous substances at the site. It calls for:

```
- Liquid Extraction Wells (6.1.5)
```

- In-Place Drum Lancing (6.1.6)
- Excavation of Wastes in Adjacent Areas (6.1.8)
- Soil Vapor Extraction and Treatment (6.1.9)
- Source Area Capping (6.10)
- U-shaped Trench (6.2.1) V-shaped Trench (6.2.2)
- Southwest Interceptor Trench (6.2.3)
- Groundwater Treatment (6.2.4)
- Alluvial Groundwater Restoration (6.2.5)

6.4.3 Partially Revised EPA Remedy

This remedy is essentially the same as the Revised EPA Remedy except that the buried drum concentrations in the Main Pit and Barrel Mound would be excavated (6.1.7) rather than lanced, and the U-shaped trench would not be needed. The use of excavation assures that all drummed liquids are removed and eliminates the short-term introduction of additional free liquids to the vadose zone resulting form lancing.

6.3.4 The HSC Remedy

This remedy is described in the Remedy Status Report which the HSC filed with the Federal District court in Oklahoma City on June 30, 1989 and described in greater detail in the HSC's Preliminary Design Report dated October 12, 1989, and also filed with the Court. It includes the following elements:

- Liquid Extraction Wells (6.1.5)
- V-shaped Trench (6.2.2)
- Southwest Interceptor Trench (6.2.3)
- Excavation of Wastes in Adjacent Areas (6.1.8)
- Groundwater Treatment (6.2.4)
- Alluvial Ground Water Restoration (6.2.5)

The HSC Remedy also includes capping of the three main source areas, but with a less effective cap than that proposed in the EPA remedies. The HSC cap does not meet RCRA requirements.

TABLE 6-2

HARDAGE SITE COMPARISON OF ALTERNATIVES

HSC REMEDY	REVISED EPA REMEDY	PARTIALLY REVISED EPA REMEDY
		×
×	×	*
	×	
	×	
	×	*
×	×	×
×	×	×
×	×	×
×	×	×
	*	HSC REMEDY REMEDY REMEDY REMEDY

The HSC remedy does not contain the following Source Control components integral to both of the $\ensuremath{\mathsf{EPA}}$ remedies:

- Drum Excavation (6.1.7)
- Soil Vapor Extraction and Treatment (6.1.9)
- In-Place Drum Lancing (6.1.6) & U-shaped Trench (6.2.1) (in Revised Remedy)

A comparative analysis of each of these remedies is the subject of Section 7.

7.0 Comparative Anaysis

The remedial alternatives described in Section 6 have been assessed in light of criteria defined in CERCLA Section 121. This Section of CERCLA specifies that remedial actions must:

- Be protective of human health and the environment;
- Attain applicable or relevant and appropriate requirements (ARARs);
- Be cost-effective;
- Utilize permanent solutions and alternative treatment technologies or resource recovery technologies to the maximum extent practicable;
- Satisfy the preference for treatment that reduces volume, toxicity, or mobility as a principal element or provide an explanation in the ROD as to why it does not.

In addition, CERCLA places an emphasis on evaluating long-term effectiveness and related considerations for each of the alternative remedial actions $(\S121(b)(1)(A))$. These statutory considerations include:

- A) the long-term uncertainties associated with land disposal;
- B) the goals, objectives, and requirements of the Solid Waste Disposal Act (i.e., RCRA)
- C) the persistence, toxicity, and mobility of hazardous substances and their constituents, and their propensity to bioaccumulate;
- D) short- and long-term potential for adverse health effects from human exposure:
- E) long-term maintenance costs;
- F) the potential for future remedial action costs if the alternative remedial action in question were to fail; and
- G) the potential threat to human health and the environment associated with excavation, transportation, and redisposal or containment.

Nine evaluation criteria have been developed to address the CERCLA requirements and considerations listed above, and to address the additional technical and policy considerations that have proven to be important for selecting among remedial alternatives. These nine criteria are discussed in a memorandum entitled "Interim Guidance on Superfund Selection of Remedy" from J. Winston Porter, Assistant Administrator dated December 24, 1986. The nine criteria are organized into three groups:

Threshold Criteria:

1. Overall protection of human health and the environment;

,

- 2. Compliance with applicable or relevant and appropriate requirements (ARARs);
- Primary Balancing Criteria:
- 3. Long-term effectiveness and permanence;
- 4. Reduction of volume, toxicity and mobility through treatment;
- 5. Short-term effectiveness:
- Implementability;
- 7. Cost

Modifying Criteria:

- 8. State acceptance;
- 9. Community acceptance.

If an alternative satisfies the threshold criteria, it is eligible for further analysis under the Primary Balancing criteria. The comparison of alternatives is given below as well as in Table 7-1. This comparative analysis provides the basis for EPA preference for the EPA excavation remedy.

7.1 Overall Protection of Human Health and the Environment:

The EPA excavation remedy provides the most overall protection of human and the environment. Both the EPA remedies provide short-term protection through the provision of alternate water supply the maintenance of site security, and land use controls to prevent exposure to contaminated groundwater. Although the EPA excavation remedy involves certain additional short-term risks in implementation, these risks can be significantly reduced or eliminated, primarily through controls on the emission of vapors and dust during excavation.

The EPA remedies provide long-term protection through the removal of a substantial volume the most highly toxic and mobile contaminants present in the source areas. The EPA excavation remedy is more effective in the removal of these contaminants than the EPA lancing remedy. Further long-term protection is provided by continued monitoring to assure that the remedy components continue to function as expected.

The HSC remedy provides the least overall protection of human health and the environment, particularly over the long-term. It would leave a large volume of untreated, toxic and mobile compounds, both in buried drums and in source area soils. These contaminants would pose a continuing threat threat to human health and the environment. The HSC remedy does not address the liquids from the source areas until they have migrated to the interceptor trenches. This process will take a long period of time, resulting in considerable uncertainty. The HSC remedy also relies on institutional controls to limit exposure to contaminated groundwater and surface water. The long-term maintenance of institutional controls

Table 7-1 COMPARISON SUMMARY ACCORDING TO STATUTORY CRITERIA

1. Overall Protection of Human Health and the Environment

HSC's Remedy

- Leaves drummed and adsorbed wastes/contaminants in the Sludge Mound and Main Pit/Barrel Mound resulting in long-term presence of contaminant sources onsite. More specifically, drums will corrode over time releasing their contents, and vadose/adsorbed contaminants would remain as a source of contamination.
- Downward and horizontal migration of contaminants from sources left in place poses longterm risks (100's of years) which will need to be monitored.
- Requires increased reliance on institutional controls.
- Releases to air will also occur to a greater extent over the long term.

EPA's Remedy With Lancing

- · Reduces the magnitude of longterm risks to human health and the environment.
- · Removes a significant mass of contaminants from the environment (drums, soils in Main Pit/Barrel Mound and Sludge Mound) through the use of soil vapor extraction (SVE) enhanced by lancing, and liquid extraction wells.
- · Meets statutory preference for utilizing treatment technology which permanently reduces the Minimizes the source term. volume/mass of contaminants subject to long-term storage/monitoring.
- Reduces the potential contaminants being released from sources, migrating away from sources, and escaping from downgradient collection areas and offsite.

EPA's Remedy With Excavation

- Reduces the magnitude of longterm risks to human health and the environment.
- Removes a significant mass of contaminants from the environment (drums, soils in Main Pit/Barrel Mound and Sludge Mound) through the use of SVE combined with removal of liquids by drum excavation and extraction wells.
- Meets statutory preference for utilizing treatment technology that permanently reduces the source term. Minimizes the volume/mass of contaminants subject to long-term storage/monitoring.
- Reduces the potential contaminants being released from sources, migrating away from sources, and escaping from downgradient collection areas and offsite.

t

2. Compliance With ARARs

HSC's Remedy

- Will need to meet surface water discharge standards.
- Would not meet requirements of RCRA for unit closure as a hazardous waste management unit (eg., would allow migration between source areas and V-Shaped Trench).

EPA's Remedy With Lancing

- Will need to meet surface water discharge standards.
- Can be designed to work with best available control technology (BACT) for air treatment (technology ARAR).
- These alternatives involve SVE and the collection of vapors and treatment. Treatment will meet ARARs contained in the Oklahoma 3.8 regulations that allow for maximum ambient air concentration (MAAC) exceedances as long as monitoring and risk assessments assure safety.

EPA's Remedy With Excavation

- Will need to meet surface water discharge standards.
- Can be designed to work with BACT for air treatment (technology ARAR)

t

 These alternatives involve SVE and the collection of vapors and treatment. Treatment will meet ARARs contained in the Oklahoma 3.8 regulations that allow for MAAC exceedances as long as monitoring and risk assessments assure safety.

رم

HSC's Remedy

- The remaining sources of risk and the magnitude of the residual risk will be greater because the HSC's remedy does not remove the mass of contaminants that the EPA's remedy does.
- It is unlikely that the V-Shaped Trench will meet its intended objectives of intercepting and removing DNAPLS from the Main Pit and Barrel Mound.
- Would require very long-term (indefinite) operation of the V-Shaped Trench and the liquid extraction wells to remove liquids from the Main Pit/Barrel Mound.

EPA's Remedy With Lancing

- Provides for greater long-term effectiveness by removing a significant mass of contaminants and therefore decreases the magnitude of the residual risk.
- The degree of long-term management necessary will be minimized because contaminants are removed and treated.
- SVE is a treatment technology that permanently removes contaminants from the Main Pit/Barrel Mound and Sludge Mound, resulting in a reduced waste mass and reduced source of contaminants to groundwater and air.

EPA's Remedy With Excavation

- Provides for greater long-term effectiveness by removing a significant mass of contaminants and therefore decreases the magnitude of the residual risk.
- The degree of long-term management necessary will be minimized because contaminants are removed and treated.
- SVE is a treatment technology that permanently removes contaminants from the Main Pit/Barrel Mound and Sludge Mound, resulting in a reduced waste mass and reduced source of contaminants to groundwater and air.
- Excavation is a treatment technology that directly removes contaminants from the Main Pit/Barrel Mound and further reduces the abste to the second for contaminated migration.

ġ.

•

HSC's Remedy

- Does not treat sources at the site to the maximum extent possible and, therefore, does not reduce the same volume of contaminants that the EPA's remedy does.
- The mobility of the contaminants that are not treated will increase with time as the drums corrode and release liquids.
- Does not satisfy the statutory preference for treatment as a principal element of the remedy.
- Allows mobility between the three source areas and the V-Shaped Trench, whereas EPA's remedy prevents this.

EPA's Remedy With Lancing

- Treatment-based remedy that addresses each of the sources and media at the site.
- Removal and destruction of contaminants is irreversible.
- Satisfies the statutory preference for treatment as a principal element of a remedy.
- The volatiles removed via soil vapor extraction are among the most toxic at the site and, therefore, a significant reduction in toxicity is provided and hence residual risk to human health and the environment.
- Lancing with liquids extraction removes toxic and hazardous wastes from the site.

EPA's Remedy With Excavation

- Treatment-based remedy that addresses each of the sources and media at the site.
- Removal and destruction of contaminants is irreversible.
- Satisfies the statutory preference for treatment as a principal element of a remedy.

t

- The volatiles removed via soil vapor extraction are among the most toxic at the site and, therefore, a significant reduction in toxicity is provided and hence residual risk to human health and the environment.
- Excavation further removes toxic hazardous wastes from the site.

Ç

5. Short-Term Effectiveness

HSC's Remedy

- Vapors currently dispersing into the atmosphere at the site will be reduced by capping.
- Impacts on community during remediations will be minimal
- Vapors from liquid extraction and temporary onsite storage will be controlled.
- Vapors from groundwater treatment will be controlled through BACT.

EPA's Remedy With Lancing

- Area residents will be protected from contaminant releases by treating SVE air stream with catalytic oxidation.
- Impacts on community during implementation will be minimal.
- Controlled or remote lancing will be used if worker risks during lancing are unacceptable.
- · Vapors will be produced from SVE and treated onsite to meet ARARs. In the event that MAACs, are exceeded, particularly during early periods of SVE operation, levels will be monitored continuously at the fence lines and stack, and releases minimized through pilot testing during design implementation.
- Controlled lancing, but untested here.

EPA's Remedy With Excavation

- Area residents will be protected from contaminant releases by treating SVE air stream with catalytic oxidation.
- · Impacts on community during excavation will be evident but controllable.
- Vapors will be produced from SVE and treated onsite to meet ARARs. In the event that MAACs are exceeded, particularly during early periods of SVE operation, levels will be monitored continuously at the fence lines and stack, and releases minimized through piner care a during implementation.
- Proven technology, controlled risks.

Table 7-1 (Continued)

5. Short-Term Effectiveness (continued)

HSC's Remedy	EPA's Remedy With Lancing	EPA's Remedy With Excavation
	 Vapors from liquid extraction and temporary onsite storage will be controlled (treated). 	 Vapors from excavation and temporary onsite storage of liquid wastes will be controlled (treated).
	 Risk exists from the mixing of incompatible wastes 	

6. Implementability

HSC's Remedy	EPA's Remedy With Lancing	EPA's Remedy With Excavation
Technologies and technology components are implementable.	 SVE systems have been constructed and successfully operated at sites with similar characteristics. 	 SVE systems have been constructed and successfully operated at sites with similar characteristics.
	 Lancing has been demonstrated in the field, except at a hazardous waste site. 	 Trenching, capping, liquids extraction, water treatment, and air treatment are proven technologies.
	 Trenching, capping, liquids extraction, water treatment, and air treatment are proven technologies. 	 Excavation of drummed wastes has been successfully completed at other hazardous waste sites.

Table 7-1 (Continued)

7. Costs

HSC's Remedy	EPA's Remedy With Lancing	EPA's Remedy With Extraction
 Capital Cost = \$26.88 - \$40.32 million 	• Capital Cost = \$43.9 million	Capital Cost = \$48.6 million
 Annual O&M = \$720,000 - \$960,000 	 Annual O&M = \$1.4 million 	• Annual O&M = \$1.3 million
• 30-year Present Worth = \$36.4 million - \$54.6 million	 30-year Present Worth = \$58.9 million 	 30-year Present Worth = \$62.9 million

Table 7-1

(Continued)

8. State Acceptance

	HSC's Remedy		EPA's Remedy With Lancing		EPA's Remedy With Excavation
*	Components are acceptable, but State would prefer more removal.	*	State supports all ground water removal and treatment elements.	•	State supports all ground water removal and treatment elements.
t	State supports common remedy elements.	*	State supports common remedy elements.	*	State supports common remedy elements.
		*	State has concerns regarding safety of drum lancing and risk to workers and the public.	*	State has concerns regarding safety of excavation and risk to workers and the public.
		*	State supports liquid extraction, excavation of adjacent areas, capping, and soil vapor extraction.	*	State supports liquid extraction excavation of adjacent areas, capping, and soil vapor extraction.

9. Community Acceptance

HSC's Remedy	EPA's Remedy With Lancing	EPA's Remedy With Excavation
* Community prefers more removal and destruction of contaminant sources.	* Community supports addi- tional removal and destruction in the EPA remedy.	* Community supports additional removal and destruciton in the EPA remedy.

results in further uncertainty.

The EPA remedies take a more direct approach to protection of human health and the environment. The first element of this is the removal of contaminants from the source areas and destroying them. By removing and destroying the contamination at the source, any uncertainties as to their future threat are minimized.

The threat to human health and the environment is most acute from those wastes which migrate the easiest and by those which are known or suspected to cause cancer. The EPA remedies both protect human health and the environment through the rapid removal and destruction of those contaminants that are the most mobile and carcinogenic. Both minimize contaminant migration through the elimination of contaminants at the source not only through removal of liquids through extraction wells and either excavation or lancing of drums, but have the added protection of soil vapor extraction (SVE). The SVE system is predicted to remove 99% of the volatile, carcinogenic wastes from the source areas. When they are destroyed following their removal the threat from these contaminants will have been eliminated. In addition to controlling the contamination at the source, the EPA remedies also protect against those contaminants which remain through the groundwater recovery trenches and elimination of infiltration with a regulatorily compliant cap. Therefore, the EPA remedies have the multiple protection of extensive removal and destruction of the contaminant sources combined with a groundwater collection and treatment system to capture any residual contamination. The primary element of the HSC remedy, on the other hand, is groundwater capture and treatment alone.

In terms of two EPA proposals, the comparison is hasically between the excavation of the buried drums or lancing them in association with the U-shaped trench. Both activities have elements of risk associated with implementation, but the risk associated with excavation of the drums is less than that of lancing as discussed in Sections 6.1.6 and 6.1.7. . Therefore the combined remedy retaining excavation of the drums is overall, more protective.

7.2 Compliance with ARARS:

Section 121 of CERCLA provides that, except under certain narrow exemptions, remedial actions shall comply with Federal and State laws that are legally applicable or relevant and appropriate to the contaminants and circumstances of the site. The process by which potential ARARs are identified, screened, and analyzed to determine if they actually are ARARs is described in "CERCLA Compliance with Other Laws Manual" (EPA 1988a). The alternatives described in Section 6.4 are broken down below into remedial elements to facilitate the analysis:

ARARs may be identified in three general classes:

- chemical specific for example, a drinking water "MCL" defines a maximum acceptable concentration for drinking water;
- action specific for example, a landfill huilt to accept hazardous
 wastes would have to meet RCRA 264. Subpart N regulations and associated requirements on design of the
 landfill;
- location specific for example, the hazardous waste landfill described above could not be built on a flood plain.

Key among those ARARs, shown in more detail in Appendix A, are the chemical specific drinking water requirements or Maximum Contaminant Levels (MCLs) established under the Safe Drinking Water Act, and the requirements under the Resource Conservation and Recovery Act (RCRA) which relate to the construction of hazardous waste facilities and their closure. Table 4-2 gives the chemical specific MCLs that would apply to those contaminants that have already migrated into the North Criner Creek alluvium. None of the alternatives would result in rapid restoration of the groundwater onsite to drinking water standards. However, the two EPA remedies would accomplish this goal more rapidly than the HSC through the elimination of contaminant sources. The HSC remedy would also fail to meet the RCRA requirements for its cap. The RCRA requirements for the construction of caps are very specific and the HSC cap does not meet them. The cap proposed under the EPA remedies would meet these requirements.

7.3 Long-term Effectiveness and Permenance

Both of the EPA remedies emphasize recovery and destruction of the contamination at the source. Through the removal of the liquids still contained in the drums, and of contaminants in the contaminated soils and sludges through soil vapor extraction, direct elimination of contaminants

at their source is achieved. These contaminants are then destroyed through treatment. It is through this early removal of the contaminants at their source that the EPA alternatives are superior to the HSC alternative. Longterm effectiveness is dependent upon the performance of the alternative over time. This long-term effectiveness is best enhanced through the elimination of uncertainties associated with an alternative. The greatest uncertainty with these alternatives is the potential for long-term migration of contaminants out of the source areas. The uncertainty of the capture of migrating contaminants by the groundwater trenches will always remain and will grow as the time of operation needed for those trenches increases. The EPA remedies effectively address these uncertainties through the elimination of contaminants at the source. Once the contaminants are removed and destroyed the uncertainty is eliminated. Moreover, the uncertainty as to long-term effectiveness of the groundwater capture and treatment systems is also reduced by the elimination of contaminants at the source. If the magnitude of the sources of the migrating contaminants is reduced, then any future risk of their movement through or around the capture and treatment system is also reduced as is the time of operation of the trenches.

The HSC remedy would do considerably less than the EPA remedy to remove contaminants at the source and would allow their continued migration for an undetermined amount of time. By allowing contaminants to remain in place for a longer period, the HSC remedy is less effective over the long-term than either of the EPA remedies. This is shown through the compound uncertainties associated with the HSC alternative. The first of these is uncertain length of operation of the HSC alternative due to remaining contaminant sources. Added to this uncertainty are those of the ability to maintain the system over this length of time and the increased opportunity for contaminants to escape over this period.

7.4 Reduction of Volume, Toxicity or Mobility

CERCLA states, in section 121(a)(1), a clear preference for remedies which reduce the volume, toxicity, and mobility of waste. The EPA remedies would both reduce the mobility and volume of the contaminants through their removal and destruction at the source. The soil vapor extraction, moreover, would remove the most highly mobile volatile organic compounds from the soils of the source areas. The HSC remedy allows both greater mobility and volumes of waste since the HSC alternative would only recover the contaminants that enter the two HSC interceptor trenches. Waiting for the wastes to migrate to the trenches allows for a greater volume of contaminated material as the contamination spreads to greater amounts of groundwater and soils as it migrates. The mobility of the wastes is also greater in the HSC remedy than in the EPA remedies as it allows the wastes to migrate and become more dilute rather than taking the more efficient approach of capturing them and destroying them in concentrated form in the source areas.

The treatment of source areas with soil vapor extraction would remove a large portion of the carcinogenic compounds in those areas and destroy them thereby reducing the toxicity of the contaminants rapidly. Again, the HSC relies on all contaminants to enter their collection systems. As for volume of contaminants, the EPA remedies, by eliminating contamination at the source, would directly reduce contamination through the recovery and destruction of contaminants and would reduce the future volume of contaminated material by eliminating the migration of these (contaminants and their subsequent contamination of soil and groundwater as they spread). The HSC remedy would allow the migration of contaminants out of the source areas not only further contaminating the groundwater and soils between the source areas and the collection trenches, but increasing the potential for the escape of contamination both vertically and horizontally either under or around the control systems.

7.5 Short-term Effectiveness

The short-term effectiveness for the HSC remedy would be higher than that for either EPA remedy as, since nothing would be done about the contamination at the source, there would be none of the attendant risks of taking action. It should be noted, however, that the short-term risks of taking action can be addressed through use of appropriate safety and engineering methods.

Both EPA remedies pose certain short-term risks. If the drums in source areas are excavated, then the soils around the drums will be disturbed and exposed to air. This creates an opportunity for volatilization of contaminants. The risks associated with excavation and lancing of drums have been examined. The risks to onsite workers are related to the excavation and handling of the waste drums and the surrounding materials. Drum excavation has been successfully implemented at a number of hazardous waste sites (see Table 7-2) and the effects are known. Exposure of site workers to hazardous substances and situations during the implementation of either EPA remedy can be minimized or prevented with well-planned and implemented personnel training programs, the supply and utilization of the appropriate safety and personal protection equipment and the development and use of an effective site safety plan.

The risk to individuals offsite has also been examined. The primary risk to those offsite comes from release of volatile chemicals or contaminated dust from the site. This contamination could reach individuals through two primary pathways, inhalation of volatile chemicals or consumption of beef and milk from livestock maintained in the area. The total extra lifetime human cancer risk from ingestion of beef and milk is estimated to be seven in ten million. This also assumes, conservatively, that the ten million individuals exposed obtain 100% of their beef and milk from the effected area. More realistic stimates of exposure and ingestion would reduce the seven extra cancer ri ; in ten million exposures even further.

SELECTED HAZARDOUS WASTE SITE HISTORIES - DRUM REMOVALS

TABLE 7-2

SITE NAME/	SOURCE OF	NUMBER OF	DATE DRUMS	
LOCATION	INFORMATION	DRUMS REMOVED	REMOVED	RE_EVANT COMMENTS
Demode Site Rose Township	Paul Gauthier OSC	4,500	1979-80	No reported accidents to onsite workers. Drums contained PCB & other wastes.
MI	Michigan DNR (617) 873-8427			
Springfield Township Mi	Paul Gauthier OBC Michigan DNR (617) 873-8427	1,500	1979-80	No reported accidents to oneste workers. Drums contained PCB & other wastes.
Gilson Rd./Sylvester/ Nashus Site NH	Chet Janowski RPM Region 1 (617) 573-9625	1,300	1980	Ne reported accidents to onsite workers. Drums removed from surface of site.
Piccola Farm RI	EPA Record of Decision	30,000	1980	Drume contained PCB's and VOC's.
Goose Parm NJ	EPA Record of Decision	5,000	1980	Drume 10 to 40 years old.
Enterprise Ave Philadelphia PA	EPA Record of Decision, and Walt Graham, RPM EPA Region 3 (215) 597-2193	1,700	1982	No reported incidents. Age of drums estimated at 10 to 20 years. Mostly solvents, rosins & resins. Site removed from NPL.
Taylor Burrough Scranton PA	Pat Tan RPM EPA Region 3 (215) 597-3164	1,200	1963	No reported accidents to onsite workers. Drums were removed firm site surface only. Half were empty.
Tower Chemical Lake City FL	EPA Record of Decision	72	1965	Drums 2 to 32 years old.

2

SELECTED HAZARDOUS WASTE SITE HISTORIES - DRUM REMOVALS

TABLE 7-2 (continued)

SITE NAME/	SOURCE OF	NUMBER OF	DATE DRUMS	
LOCATION	INFORMATION	DRUMB REMOVED	REMOVED	RELEVANT COMMENTS
leve Reber	EPA Record of	1,100	1983	More drums on site to be removed.
.Α	Decision			
lerlin Farro	Pote Ollila	20,000+	1984	No reported accidents to onsite workers.
41	Michigan DNR			Drums excevated up to 22 ft. Says drums have been
	(517)873-8174			removed at over 300 sited in M1.
Byron/Johnson Salvage	Bill Bolon	100°e	1986	No accidenta.
Byron, IL	RPM		_	Drums excavated and removed. Used buildozer to remove
	EPA Region 5			them from surface & ravines.
	(312) 363-4316			
Aberdeen Pesticide Dump	Ned Jeanup	667	1984-87	No accidente or injuries.
Aberdeen	OSC			Excavated to 10 ft Most drums empty when removed.
9C	EPA Region 4	1		The state of the s
	(404) 347-3931			
Denver-Arapahoe Chem	EPA Record of	30,000	1986-87	Drums 8 to 10 years old.
Waste Mgmt Pacility	Decision	1		
co				
Bioecology	Stove Veale	3,000 (ast.)	1987-88	No accidents related to drum removal operations.
Dullas	RPM			Level B & C. Excavated 85,000 cu. yards soil & debrie
rx	EPA Region 6	}		including buried drums (drums approx. 1 % of waste).
	(214) 665-6715			mine approx. 1 % of water.
ackawanna Rofuse Site	Walter Orsham	8.000	1986	No reported accidents to onsite workers.
ackawanna City	RPM			Drums removed from stripmine landfill. None intact.
PA	EPA Region 3	1		Excepted 30-35 ft. deep over 5 acre area.
	(215) 597-2193			ELECTRONIC SUP-SO IL GOOD OVER 5 ACTS APSA.
Jeman Grames Landfill	Ross Powers	2.200	1986	No manufacture and the state of
Monroe County	080		1200	No reported accidents to ensite workers.
41	EPA Region 5			Slow work. Level B. Excavated to 6 ft. with buildozer
	(313) 675-3178	I ·		å grappler.

3

SELECTED HAZARDOUS WASTE SITE HISTORIES - DRUM REMOVALS

TABLE 7-2 (continued)

SITE NAME/	SOURCE OF INFORMATION	NUMBER OF DRUMS REMOVED	DATE DRUMS REMOVED	RELEVANT COMMENTS
Syntex Landfill Lyons, CO	Gary Kaufman Env. Engineer Syntax (803) 938-8430 & Mark Davis CO Gool. Survey (503) 888-2611	15,000	1986	No reported accidents to onsite worker- USPCI excavated 28,000 tons of contaminated soi! . i 16,000 drums of contaminated wastes which were sent off-site for disposal and treatment. Drums 10 to 20 years old or older.
Great Lakes Container MI	Paul Gauthior OBC Michigan DNR (617) \$73-8427	750+	on-going	No reported accidents to onsite workers. Shallow operation (1 to 2 ft.).
O'Imperio Drum Dump Atlantic City NJ	Remona Pezsella RPM Region 2 (212) 254-8216	130 (aut.)	1986-87	No reported accidente to onsite workers. Excavated 3900 cu. yards of soil & drums.
Auburn Rd. Landfill NH	Don Burger OSC, Region 1 (617) 860-4360	to be provided		Major drum excavation close to residential area. Buried 8 to 10 ft
Ottati Goss N H	Don Burger OSC, Region 1 (617) 860-4360	to be provided		Drums excavated under U.S. EPA Emergency Response Cleanup Services Contract (ERCS).
Davis Liquid R1	Don Burger OSC, Region 1 (617) 860-4360	to be provided		Drume excavated under ERCS.
Blosinski Landfill PA	Walter Graham RPM EPA Region 3 (215) 597-2193	50-60	1962	No reported accidents to ensite workers. Only surface drums & a tank truck were removed.

The total extra lifetime human cancer risk from inhalation of chemicals released during excavation of the Barrel Mound and part of the Main Pit is estimated to be one in ten million. The estimated risk from operating of the SVE system is six in ten billion.

The opportunity for volatilization can be reduced through using the smallest possible working face and thereby limiting the contaminated materials exposed to the air. Common sense precautions such as excavating during cooler weather will also reduce volatilization. The use of volatilization control techniques such as foam supressants can also be used.

Other short-term risks were also considered. The intermingling of the drummed liquids can be limited through the segregation of the drum contents as they are removed. The short-term risks associated with the drum lancing proposal include those associated with the physical puncturing of the drums and of the mixing of the liquids after they are released by the lancing. The risks of lancing can be reduced through the use of controlled lancing. The work would proceed gradually with the removal of liquids released as rapidly as feasible during the lancing. The lancing work could also be done by remote control to protect site workers. The risks of puncturing the drums could be reduced through the use of non-sparking materials on the lance points and through the use of carbon dioxide to eliminate the oxygen supply through the lance hole if needed. It is important to note that there is already extensive mixing of the source area liquids as evidenced by the amount of pooled liquids in the Barrel Mound. This would indicate that the risks from further mixing are less than might otherwise be anticipated.

Of these two alternatives, excavation poses less of a short-term risk. It allows greater control and observation of the hazardous materials that are disturbed.

7.6 Implementability

The majority of all three alternatives use established technologies and could be implemented. Only the lancing of drums has not been attempted at a hazardous waste site. The lancing technique has been demonstrated for the puncturing of buried drums and has been used for other industrial purposes. This one point leads to a slight preference for the EPA excavation alternative and the HSC proposal over lancing for this criteria.

7.7 Cost

Because it is a less extensive remedy, the HSC remedy is cheaper than either of the EPA remedies. It is important to remember that the HSC proposal is not an equally protective remedy when compared to the two EPA proposals. The relative estimated costs for the three alternatives are: HSC \$46 million, EPA with excavation \$63 million, and EPA with lancing \$59 million. An additional consideration is costs associated with remedy failure.

With greater amounts of waste remaining in the source areas for a longer period under the HSC remedy, the potential exists for greater costs should additional remedial work be required.

7.8 State and Community Acceptance

State comment on the proposed plan for remedial action can be found in the transcript for the public meeting held on October 26, 1989 and in their letter of November 13, 1989. Basically the Oklahoma State Department of Health as representative of the State of Oklahoma supports elements of EPA's selected remedy including soil vapor extraction, but disagrees with with the excavation or lancing of the drums in the source areas, and with the use of catalytic oxidation as a thermal treatment.

Public comment expressed at the public meeting showed a preference for quicker action and for more permanent remediation. To quote one of the local residents who spoke at the public meeting,

"... Personally, I think that the way that some of the basic ideas that you have got about addressing the cleanup of this is good. I particularly like the idea of removing the drums. When you start taking these materials out, when you remove them from the site completely, it's the only way that you are going to create any kind of confidence that you have really cleaned it up."

SECTION 8: THE SELECTED REMEDY

Based upon consideration of the requirements of CERCLA as specified in Section 7.0 of this document, the detailed analysis of the alternatives, and State and public comments, EPA has determined that the Partially Revised EPA Remedy involving the excavation of drums for liquids removal, is the most appropriate remedy for the Hardage/Criner site near Criner, Oklahoma. A schematic of the selected remedy is shown in Figure 8-1.

The first element of the selected remedy is the removal and destruction of contaminants in the source areas. Free liquids within the three major source areas, the Barrel Mound, Sludge Mound and Main Pit, would be removed through extraction wells. Organic liquids would be transported offsite for destruction and aqueous liquids treated onsite. Drum concentrations in the Barrel Mound and Main Pit would be excavated. Liquids in the drums would be removed and taken offsite for destruction. Solids would be restored to the three main source areas. Contamination from adjacent areas would be consolidated into the three main source areas. These source areas would be treated through soil vapor extraction (SVE) to remove contaminants. The resulting SVE effluent contaminants would be destroyed onsite using thermal treatment. It is this element of the recovery and destruction of the contamination at its source that is missing from the HSC remedy and which confers the greatest degree of superiority to the selected remedy over that recommended by the HSC. The reduction in the long-term uncertainties associated with leaving large portions of the source areas of contamination unremediated, as in the HSC alternative, is another area in which the superiority of the selected remedy over the HSC alternative is demonstrated.

The second element of the selected remedy would be control of residual contamination. The major source areas would be capped first temporarily during treatment and removal in the source areas, and then permanently with a regulatorily compliant cap following completion of the main treatment and removal phase. Groundwater would be collected through interceptor trenches and treated onsite. Surface water controls would be instituted to minimize contaminated runoff.

Finally, institutional controls would be implemented to prevent use of contaminated groundwater downgradient of the source areas. Alternate water supplies would be continued to replace supplies lost through contamination. The site boundaries would be expanded from the original site to the area indicated in Figure 4-6 to facilitate the implementation of the institutional controls.

The estimated cost for the selected remedy is \$63 million. Table 8-1 gives a breakdown of this estimate and a detailed cost estimate can be found in Appendix G.

8.1 Remediation Goals

The purpose of this action is to protect human health and the environment through control of risks posed by the Hardage/Criner site and minimizing further migration of the site contaminants. Estimates of the risk of cancer from lifetime use of residential water contaminated at the level of the Old Corley well range as high as 0.0007 (seven per ten thousand) to 0.006 (six per thousand) far above the one per hundred thousand risk which is the upper




TABLE 8-1 $\label{eq:cost_summary} \text{Cost summary for the selected remedy}^1$

Liquids Removal and Control Drummed Waste Staging/Consolidation Area		6,449,745
and Storage		2,813,516
Soil Vapor Extraction and Treatment		3,098,052
Removal of Adjacent Wastes		2,168,834
Source Area Capping		3,722,605
Ground Water Extraction and Treatment		5,971,286
Remedy Support Facilities		3,237,290
Surface Water Controls		196,000
Remedial Monitoring		41,250
Institutional controls		608,250
	3	28,306,837
Bid and Scope Contingency		9,907,393
Implementation Costs		10,317,842
Conversion to September 1989 dollars		
Operation and Maintenance for 30 Years		14,309,500
1	TOTAL 3	62,904,655

¹ Source: Remedy Report for the Hardage Industrial Waste Site, Criner, Oklahoma, October 13, 1989.

houndary of acceptable risk set in the National Contingency Plan.

To accomplish this goal, the remedy would permanently and significantly reduce the volume, toxicity, and mobility of contaminants in the source areas. This is accomplished through removal of liquid contaminants quickly and directly through liquid extraction wells and excavation of drum liquids. By following these steps with soil vapor extraction, removal and destruction of the most mobile contaminants, including most of the known and suspected human carcinogens, will be acheived. The goal of soil vapor extraction would be a. 99% reduction of the volatile organic concentrations found at the beginning of soil vapor extraction.

Beyond reduction of the source, the goal of this action is to restore the groundwater to levels below MCLs. This action is particularly directed at the alluvial aquifer associated with North Criner Creek.

The superiority of the selected remedy is demonstrated in the comparison of the alternatives through the use of the nine criteria given in Section 7 of this document. The reduction in the sources of the contamination associated with the selected remedy confers advantage to the selected remedy over the remedy recommended by the HSC. By eliminating the contaminants at their source the selected remedy is more protective of human health and the environment, has greater long-term effectiveness and permanence and provides for greater reduction in the volume, toxicity and mobility of contaminants than provided by the HSC remedy. The selected remedy can be implemented using existing technologies and methods. Its cost is greater than that of the HSC proposal, but the selected remedy through its source control elements provides greater and more efficient levels of remediation. In this regard, the additional costs associated with the selected remedy are reasonable. The selected remedy would also comply with existing ARARs on cap construction, which the HSC alternative would not do, and would attain the standards for drinking water quality in the alluvial aquifer as expressed through the Safe Drinking Water Act MCLs in a shorter period of time than the HSC proposal would. The State of Oklahoma through its representatives has expressed concerns about the short-term effectiveness of the selected alternative, and some short-term risks do exist. However, these risks have been considered, and they can be controlled or eliminated through the application of prudent engineering and safety techniques. Finally, the local community, through the public comment period on the alternatives expressed a preference for removal and destruction of as great an amount of the contamination as possible from the source areas. The selected remedy provides for far greater direct removal of the source area contaminants than does the HSC proposal.

The selected remedy also holds advantage over the other EPA alternative which included lancing. The lancing techniques have not been used at a hazardous waste site before and therefore their implementability is not as well known as the excavition of drums in the selected remedy. There are also greater uncertainties associated with in-place release of the drummed liquids through lancing that will not exist with the selected excavation program with actual physical removal of the drummed liquids.

9.0 STATUTORY DETERMINATIONS

Under its legal authorities, EPA's primary responsibility at Superfund sites is to undertake remedial actions that achieve adequate protection of human health and the environment. In addition, Section 121 of CERCLA establishes several other statutory requirements and preferences. These specify that when complete, the selected remedial action for this site must comply with applicable or relevant and appropriate environmental laws unless a statutory waiver is justified. The selected remedy also must be cost-effective and utilize permanent solutions and alternative treatment technologies or resource recovery technologies to the maximum extent practicable. Finally, the statute expresses a preference for remedies which significantly reduce the volume, toxicity, or mobility of hazardous wastes as their principal element. The following sections discuss how the selected remedy meets these statutory requirements.

9.1 Protection of Human Health and the Environment

The remedy seeks remove liquid contaminants quickly and directly through liquid extraction wells and excavation of drum concentrations. By following this removal with soil vapor extraction, removal and destruction of the most mobile contaminants including most of the known and suspected human carcinogens will be acheived.

Along with effective reduction of contaminant sources, the selected remedy protects human health and the environment through intercepting and treating contaminated groundwater with interceptor trenches. The North Criner Creek alluvial aquifer is the nearest groundwater used as a residential water source. The selected remedy provides better protection of human health and the environment as it will achieve the goals for groundwater cleanup more quickly than the HSC proposal. The selected remedy will eliminate uncertainties associated with the continued presence of toxic and mobile volatile contaminants in the source areas by recovering and eliminating contaminants, unlike the HSC alternative which would allow these contaminants to migrate.

9.2 Compliance with Applicable or Relevant and Appropriate Requirements

The elements of the selected remedy would all comply with applicable or relevant and appropriate requirements (ARARS) established for this site. A more complete examination of ARARS can be found in Appendix A. Key among these ARARS are the Sare Drinking Water Act chemical specific requirements known as MCLs (maximum contaminant limits), and the requirements under the Resource Conservation and Recovery Act (RCRA) which relate to the construction of hazardous waste facilities and their closure.

ARARs include:

- RCRA requirements for landfill closure in 40 CFR 264.111 Subpart G and 264.310 Subpart N which specify cap requirements for landfills;
- RCRA requirements in 40 CFR 264.117 Subpart G dealing with Postclosure;
- Requirements under State of Oklahoma Air Regulations requiring use of Best Developed Available Control Technology for treatment of the air from the SVE system.
- 4) Maximum Contaminant Levels (MCLs) established under the Safe Drinking Water Act;
- State of Oklahoma maximum acceptable ambient concentrations (MAACs) for air contaminants;
- 6) Oklahoma Water Quality Standards for discharge to a surface stream.

None of the alternatives would result in rapid restoration of the ground-water within the site to MCLs. However, the selected remedy would accomplish this goal more rapidly than the HSC remedy through the elimination of contaminant sources. The selected remedy would also meet RCRA requirements for the construction of the cap over the source areas; the proposed HSC alternative does not meet these requirements.

9.3 Cost Effectiveness

The selected remedy is cost effective and would cost an estimated 63 million dollars. It includes some 20 million dollars of cost directly related to contaminant source area reductions, through excavation, soil vapor extraction, and liquids extraction. The HSC remedy does not include these costs. This additional cost is reasonable considering the added long-term protection of human health the environment provided by direct and permanent reductions to the source areas.

9.4 Utilization of Permanent Solutions and Alternative Treatment Technologies.

The selected remedy represents the maximum extent to which permanent solutions and treatment technologies can be utilized in a cost effective manner. The amendment of the 1986 ROD, which called for land filling and stabilizing the source soils and sludges, to the new selected remedy of excavation, liquid extraction, soil vapor extraction and capping provides for a permanent solution through additional recovery and treatment of contaminants.

The emphasis in the selected remedy is on the recovery and permanent destruction of the contaminants at the source. This begins with the recovery of the free liquids and the liquids in the buried drums through excavation and liquid extraction, and the subsequent destruction and treatment of these liquids offsite in a permitted Treatment, Storage, and Disposal facility and in the onsite water treatment system. It also includes soil vapor extraction of the Main Pit, Barrel Mound and Sludge Mound to remove volatile organic compounds.

Another aspect of permanence is the reduction of the mobility, toxicity or volume of the wastes. The selected remedy accomplishes all of these goals through removal of contaminants at the source, unlike the HSC alternative which would allow contaminants to migrate out of the source areas.

Through removal and destruction of contaminants by SVE the amended selected remedy provides permanence, particularly when combined with the groundwater collection and treatment elements of the selected remedy. The groundwater portions of the selected remedy utilize permanent solutions through removal and treatment of contaminated groundwater and the destruction of the organic contaminants removed during treatment.

9.5 Preference for Treatment as a Principal Element

Treatment is central to the selected remedy. Treatment is used extensively to address each of the three primary contaminated media. Free organic liquids from the source areas and organic liquids from the excavated drums will be taken offsite for destruction or treatment at an appropriate, permitted Treatment, Storage and Disposal facility. Contaminated soils and sludges that remain following liquids removal and treatment will be consolidated into the three main source areas for treatment with a soil vapor extraction (SVE) system. The goal of the SVE system will be removal of 99% of the volatile organic contaminants from the contaminated soils and sludges. The air from the soil vapor extraction system, and air effluent streams from other remedy components, will be treated onsite with a thermal treatment system, to treat and destroy the contaminants within the air streams. The third major contaminated media is the aqueous liquids including groundwater,

aqueous liquids from the buried drums, and surface run-off. All of these liquids will be treated in an an onsite water treatment plant. The water treatment plant will be designed to treat the influent liquids to standards for discharge in accordance with Oklahoma Water Quality Standards.

Additional advantages in the treatment in the selected remedy are gained by treatment of the contaminants in a more concentrated form. This is true of the free and contained liquids in the source areas due to the liquid extraction wells and collection of the free liquids and the excavation of the buried drums. The SVE system will also recover the volatile contaminants from the soils and sludges in the three source areas allowing them to be treated in a concentrated air stream rather than diffused through the soils and sludges. Treatment of the contaminants at their source will also improve the effectiveness of the water treatment system through reduction of contaminant migration to groundwater. The contaminants will be treated before they migrate into the groundwater where they would spread and be diluted.

9.6 Documentation of Significant Changes

The Proposed Plan for the Hardage/Criner site was released for public comment on October 13, 1989. The Proposed Plan identified the use of drum lancing as an option for addressing the buried drums. Comments received during the public comment period indicated particularly strong opposition from the State of Oklahoma to retention of this option. While EPA feels that drum lancing could be implemented, the option of drum lancing and associated U-shaped trench has been deleted from the selected remedy and only excavation is part of the selected remedy.

REFERENCES

- Hardage, Royal N., 1987. Deposition.
- EPA, 1985. Field Investigation and Data Summary Report, Royal Hardage Industrial Hazardous Waste Site, $\mathrm{CH}_2\mathrm{M}$ Hill, May 22, 1985.
- EPA, 1985a. Public Health Assessment Manual, EPA, Office of Solid Waste and Emergency Response, November 1985.
- EPA, 1986a. Source Control Feasibility Study, Royal N. Hardage Industrial Waste Site, CH₂M Hill, February 20, 1986.
- EPA, 1989. Remedy Report, CH₂M Hill, October 12, 1989.
- HSC, 1986. Final Conformatory Bedrock Study, ERM-Southwest, December 31, 1986.
- EPA, 1988. Design Report Source Control Remedial Design Hardage Industrial Waste Site Criner Oklahoma, November, 1988.
- HSC, 1988. Mound Characterization Field Study, ERM-Southwest, November 7, 1988.
- ${\sf HSC}$, 1988. The Hardage Steering Committee's Recommended Source Control Remedy.
- HSC, 1989. Second Operable Unit Management of Migration Remedial Investigation Report, ERM-Southwest, May 10, 1989, as amended by EPA Comments.
- HSC, 1989. Second Operable Unit Management of Migration Feasibility Report, ERM-Southwest, May 10, 1989, as amended by EPA Comments.

APPENDIX A

EVALUATION OF APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS

THAT SCHOOLING OF PRINTIAL PEDENAL CHEMICAL-SPECIFIC AMP'S

(Carento		Organic and inorquals rentantants have been detected at the study sies.	Matter are not indecably referrable but are telembed as quidelines for the states.	Wilds are non enforceable requirements.	Specific requirements are listed under discharge requirements		Air offigues from the transment lystemy must ment these atenderes.	The apprific properties of the lite may be staller enough to those regalements to conder then relevant and appropriets.
Applicable/belonged		1	į	ŧ.	ì		:	/44
Processed from		Establishes health-hamed standards for public safer hydron hamium contast- and lovels (WLs).	folditions standards for the modification of public water systems necessary still (MECA);	Fold-links maximum smalminami lossi quels implos of me barra or anticipated adverse health effects.	Objectives are to restore and maintain the chancel, physical, and biological integrity of the antiem's solors.		Pointings of maderial for ambient off quality to protect public hould and collect for both and standards for por- livated and to and leads.	Concrete and MCM transland, always of dispute facilities and facilities and facilities for the person that are designed to the facility person that one designed to ensure that the facilities conducted that the facilities of the
Citation	100 350 (1)	40 CFB 141	5 &	Public La Ro. 90-319 160 Stol. 43	33 WK 1351-1374		40 CTB 90 (4) WC 7401- 74431	8 CB 24.
Prerogalation		Palic mier Spilm	Public Bates System	Public mier Protm	Miers of the Milita States		Containation of air offecting public motth and unifore	Opportunit agailer underlylag o moie management mili bepard ibs paird of campilance
Pr-Pe I seemil	Safe freinking Boter Act	hallend Primery Drinking Baler Standards	Hallphal Securbing p hilling Balof Standards	Realean Contentempt trvt feets	them mater fact (Cmb) mater Quality Criteria	Clean Alt Act (CAA)	Martianal Primary and Cornectory Ambient Aly Quality Standards	Demotr (emotralia) and because he (MDR)

. . If a requirement is applicable, it control also be relevant and appropriate.

1-145125

Neproduced from best available copy.

INITIAL SCREENING OF POPTIFIAL PEDIDIAL LECATION-SPECIFIC ARAB'S

Prepirement	Prorogalsties	Citation	Precription	Applicable/Delegat	
Project Conservation and hecovery Act (MTA)	ACM beigrhous veste, freet- ment, storage, or disposal	40 CTB 344.1884	New treatment, strenge, or disponsi of haistmen maste promibited within 45 meters of a foul displaced in Malacene (see,	*	There are no Enurse faults within 61 porters.
Ť.	MCTA hazardour unate, treat- bent, storage, or dispensi	80 CTF M4. Lett.	treatment, starmer, or dimposal facilities within the IND-post flowd piace main to designed, carrincing, operator, and maintained to present manhame,	Net/	Part of the site lies activis the 100. year flowd glate.
Fraulte Order on	Action that ulli accur in a line plain (i.e., les)ands and relatively flat areas adjaining liland and could asters, and piver (lead-press area)	Esecutive Order 11 MB	Must take action to profit of sinistic potential harm in flood plains, and restors and persons natural and beneficial values.	·· / S &	Part of the size lies within the 100. year fleed plain.
Ţ.	Moncantainvertend or halt tigaid 40 CFB 364.18[c] hazardmus usate	40 CPB X4.18/cl	The placement of any mescentainer- lise or but liquid heardean varie in most dame formation, sall bud termiton, undergramed mine, or care to prohibited.	<u> </u>	There are no toll dame formations, self and formations, undergraund block, or terro ansite, littures in all dame formations, store, or terro to not restruction for this project.
Mattonal Bribanological Attention of and Midelia Proporetion Act setentific, po bistorical, of	Alteration of terrain that threatens aignificant scientific, probletorical, historical, or archamisates deta	(16 89C Section 669) 16 CFB 65	Must take action to recent and preserve artifacts.	ę.	There are he hearn scientific, presis- teric, historic, or archaeological artifacte antilo,
Fish and Widille Crosdination Act	Discreten chammeling or wiber schilly that modifies a birman or river and effects fish or wildlife		Must take action to product fish or elidiffe	/A K	Distribute to Marth Coiner Creek is Blanned as part of the remediation
Srenic Bloos Act	Activities that affect or may affect only of the rivers specified in Section 1796al	Tie MC 1371 Med File 7 (at) of CP 6.303 (a)	Must avoid taking or mainting in metion that will have direct advarse affect on posmic river.	\$	The action planmed at the site will have direct advances affect on a transcriber.

Note: .. . If a requirement to applicable, it teams also be relevant and appropriate.

\$PR154/1-2

I and I have

,	The stands on	No action to dredge material is proposed at the site	No action to dredge material is proposed at the site	There are no landmarts on the Matienal Degister of Materal Landmarks on the site.	No structure or work in surface stream is planned other than monitoring.	The site is not included in or citizen for its citizen for the Poliman Anglists of Aisters.	The site is and a critical habitation and the second species or large leaves and species and second	The sile is not a unitard as defined by Doctof to Date it was, Secretar 2.
Applicatio/Inleased	4 / 4	4	ş	*	No/Yes	§	£	ŧ.
Deprify len	Must countert activities in a manner consistent with approved state management programs.	so CTV, Subpart H. Artion to dispose of dradge naterial into over subers (a prohibited vilbant a persit,	(3) PPC 1331-1374 Artion to dispose of decides 40 CFB 190, 23) material into revon maters to prohibited without a permit	Nest avoid undestruble impacts upon londmarts.	Substative requirements of Section 10 must be and if an elicentative developed busis imples structures or must in an effect manigable valors.	Must take action to persone historic graphs close among or controlled by federal opening. Must plan action to mission harm to Metional Historic landmath.	Must take metion to commerce endampered species or threstowed species.	Nut take action to ministe the desirection, less, or depends ton of vetlands.
Citation	50ct 500 1631	ed Cre, Subpart H		(16 PSC 461-443)	(13 CT 320-330) 33 PSC 403	116 mmC 470 et. sed.) 36 cmm mcO	1331 mt. 1331 mt. 20 cm 200, 30 cm 603	Decretive Order 11990 40 CFF Appendix 6
Prerequisites	Arisities silecting the creatal same including lands liberanchs and adjarent shorelands	Greens and voters of the United States	Oceans and valers of the United States	Esistemes of malusal landmarks. (16 PSC 661-643)	Artivities afferting navigation enters	Property Included (n or eligible for the Mellona) begister for Historic Places	Critical habital upon which endonmered species ar threatened species depends	Delland on defined by Decotive Order 11990, Section 1
Pequiremni	fractal fore	Ciran Mater act (CMA) Section 404	Marine Protection Democrat and Sanctuary Art, Tertion 103	Historic Sites, Buildings, and Antiquilles Act	Sicers and Marbora Act	National Historic Preservation Art, Section 178	Defendenced Species Ref. of 1433	Partition of Bellands

Note: -- - If a requisement is applicable, it connect aims be relevant and appropriate.

\$-176K(448

,

5	
1	
:[
=	
•{	
Bolo: If a requirement	
ļ	
=	
į	
~ ·	
Ξ	
2	
÷	
¥	
carmot also be relevant as	
i	
and appropriate.	

Propriessont	Propriesent Presequisites Citation	Citation	Description	Applicable/Beforent	Control
Wilderness Act	Probatelly named area described 50 CF8 35.1 as a eliderment area	50 CF# 35.1	Area must be administered in such a summer that will leave it uniqualized as wilderness and to preserve its wilderness character.	***	The site is rest a federally remed area described as a ultreinest area.
Hational Wildlife Peluge System	Area designated as past of the -30 CTW Past 37, Wallonal Wildsife Refuge System fis USC 648 d.d.	50 FFR Part 37, 116 UST 668 d.d. et. seg. ?	Only actions that are allowed under the provisions of 16 UST, Section dd(c) may be understated in access that are part of the Hattonal Wildlife Befuge System.	He to	The alto is not designated as part of the Matismai Wildlife Beinge System

ti ont fraud)

INITIAL SCREDNING OF POTTOPTIAL PENSAL ACTION-SPELIFIC MANAGE

Committee		Memorer, the maje stituent pin- visions of 40 CFB Jdgml. one there ritterla.	The madilitations or convoling one moderal saiding requisions, will be used.	My selected and appropriate If any selected as a tength of trademin.	Me released and again, the liquid there is be account sold or liquid resident free free free freetening plant.	Applicable to off-site transport of recovered liquids or if there is hazardous residury from the treatment systems.	Applicable to treatment (p. 11119.	Are referent and appropriate for amilte treatment jurility.	Fredami (acility meds a property developed and implemental	Graditates farmed radedy plant	hee applicable if herrebury sells and liquid resident from trailment plant must be from manied effects	Grambed or amiliaring provisions are relevant and appropriate	Portions of Sufface) of that Acal with post-closure activities are applicable.
Applicable/Belesget			4.	#1/ #	i.	Tes/	·/84/	Ĭ	į	± 5/4	¥**/	# / Ja	740/
Description		Catabilities criticis for use in observable delib soil assis dispussi inclilities and president part a resemble predicting of devices criticis an feetifa of the vestimance out, thereby, creatituse probibilied span demps.	Extensioned precedency and critical for medification or removalion of any practicion in 60 (TP 340-345.	Defines these solid master that are subject to repoletion as hazardaus santes ember 80 CFB 363-265, and 134, 230, and 231,	Catabilibes standards for generalists of hospidams units.	Establishes etambede lind copil to persons transperting thesidess waste establish the U.S. If the transpertition requires a mension; under 60 CTB 343.	Establishes minima matland indicated biometric that deline the exceptible management of histories and particles that itself, afters, or dispuse of histories and indicated waste.	4/8	۷/۵	m/m	4/1	4/k	4/8
Citation	143 ME AWIT-44873	40 C# 33	996 643 940	14 81 00	6 CB 343	(* £) 8	7. E. 9	. Drawn .	Subport C		a Linda	Badgari P	Sabpart G
Prerequisites		Disputal of solid easte	KTA hatardous waste	Solid water	Generation of NCM hazardeas	Constitute of MCM has and vesto villa offsite disposal	RTM hazardway waster	fredment, elerape, or dispersi	Generalism or treatment, storage, or dispusal of WCM heterdoors public mestic	Generalism of treatment, elorage, or disposal of MCMA haisidess maste ensite	Commentation or treatment, plorage, or dispused of MIM haintdean opple and to	Demonto or treatment, plerage, or dispused of KCM halvidum made analle	Generalium of tradement, starmen, or dimposal of MCM haterdour waste mestle
Propilionen!	Solid Marie Dispared	collects for Collection of Collection of Pacifics and Facilies	Hataideus Maste Management System: (erectat	identification and Listing of Noracobus Water	Standards Applicable to Georgestes of Massidons Marte	Standards Applicable to transporters of Marsidoss Maste	Standards Applicable in Company (Special series of in section 1, Standard Printed and Illegeous facilities	o Grantel Pat 11189 Standards	· Proporeduces and Prevention	Dergency Plan and	· Manifest Spates Perceptosying and Paperting	o Polososs (rem Palis Rosto Ambapraent Balto	Clours and Pust.

Role: If a requirement to applicable, it connect also be released and appropriate.

1-100/461443

d from ble copy.

9.1

ì	
ī	
Ū	

		Applicate for any container tenter and and any container of the first tenter to be a second to the first tenter of the first tenter to the first tenter of tenter of tenter of tenter of tenter of tenter of t	State as Subpart 1.	Applicable to surface impoundments constructed to hold hazardous waste.	Moto piles are not being used at	land treatment to mel helme pen-	Closure of lamifiti	The specific proporties of the trice may be thello remays to their requirements to creder them releases and appropriate.	Man are identified at this cite.	Parties of maintenance.	This is not a respilling facility to recover proclims missly.	A case becomes used a land dis- paral facility is not bated pro- parad. Deferenced in period a becomes used in the contra- picted.	No united of equity are non- impliated for disperal.	Permits are and completed for an also are also peritylises at Superfluid
Application for formal	/144	-/*	/*E	Tes/	\$	\$	/69/	/104	\$	\$	\$	\$	ţ	Š
Deve e jat fan	e/a		٧/١	· · · · · · · · · · · · · · · · · · ·	7/11	B/B	Establishmy standards for hazardous wasin Yes/ landitity (including cap requirement)	**		Conditions without matimus. Constitute that define the formation of the f	Establishes requirements that supply to represent answeriet that was rectisized to tercour communically statisficant amounts of precises motals.	Distriction alongum and least 11 and or the define account to 12 and or the define account to 12 and of the seast to 111. 12 and the seast to 111. 13 and the seast to 111. 14 and the seast to 111. 15 been account to 120.	Finishing lead dispensed of specified solved and househous nation and provides special fractionments for handling such sailon.	Establishes providions convince harte Th permitting require- ments.
C11 84 1000	Subpart H	Support	Separe J	S. Separat	Part I.		Subpart N Part 264.310	F	Support B	R E	*# #£	. R E S	I E I	84 cm 118
Perreptation	Generalism or tradpost, alarage, or disposed of PCBA haisthogo saile artifr	Management of MTM hazardess waste in containers	Management of Artic Sacretius	Management of ESA kateridaes saits in series impoundable smalls	Paragraph of RTM Misches	Land transferri of W.M. hater date,	Londition of NCM househor	locineration of M'M boundary	frectural, storage, or dispass!		Deption to recover precious metals	the fifth bales dead made land disposal feelilly	Land Stapesol of NCTA harardown verte mostle or offills	Arms best from easte transmet, strade, and disposal emilia
Printer	n Pinaw lai Brquirearate	o five and Panagement of Containers	į	• Surfer Impuniforts		a Lond Treatment	• Lond(1111	· lar layest at a	· Histollorsom Built	Control of Combactor for the control of the control	Comment of Berlin Response of Berlin Section Types of Residue Berlin Response of Fertilling	Date of Standards for Commercial Special Commercial Special Commercial Special Commercial Special Commercial Special Commercial Special Commercial Special Special Commercial Special Special Commercial Special Speci	Cond States of Particular of P	Regride Male Profit

Balan and It a semidiscent to applicable, it removed also be relevant and appropriateles.

_	
ì	
-	
٤	

	1 1	If a treduced plant is a product production versel.		No injection of liquids is planned at the site.		Perfections of the property of the property of the property of the perfect of the	the ere mearces have been ideal find of the alle.	Mo discharge to a Public Sewage Treatment Plant is planned at the site.	If these contaminants sold sithin the study proc.	Brem damplen mat part ad any proposed alternatives.	Applicable of PCBs are detected in materials before transfer about conspicing of fraction about account to the contraction of transfer about account to the contraction of the contracti	Numb were to rat a statute related		Some portions of 40 CFR 61 would be relevant and appropriate to offiges emissions from the treatment systems.
Application leaded	į	**/***		*		/101	*	ş	/***	4	******	Ę.		5
Perceiption	Extendibles requisitions related to universecond states than 5.	Proposed standard enoid require 1918 consertion of extelling untante entratum from Product Accountation Vessel.		Presides for presention of production of productions of delabling value.		Chapter perults for the dis- chapter of pullstants from any pullstants. Discussed the Mained Mater. Promiss Based an mained unter spainty contents.	Sets technology-based offlowed Italiation for point paper discharges in the Ove History and Destrict bold Source extensey.	Sets standards to control politries; that pass through or fireffer; with tradeound processes in Wills or that may contaminate prouge shadps.	Entablisher of fland of makeds or problem for certain foots polydonis.	bequisies acets bamping.	Latelianes electry and dispusal requirements for NOs.	Entablishes presidents designed to protect the entitlement from the effects of parties rul belief apprentions and, to a first raterly, recent spins.		Date malester expendentless for decimal decimal decimal decimal descriptions, and incorporate
Citation	96 (12)90	5. T 3.	(4) MEC 3004)	86 CPB 146-147	1) 885 1331-1336	8 CT 133, 135	\$ £	(Ca 442) 00	\$ C. E. 3	111 PK 1001-1451	113 mm 2601- 2623- 80 (17 mm)	1301	(4) PEC 1001-74631	\$ E1 8
Protequisites	Undergraums starmen tank	Voluliis erganics selesions		Ambrigatural injection of substitute of substitutes		Discharge of pallotants from any paint powers into vaters of the United States	Point senere discharge into the Ore Ore Miles and Dressing Point Emerce Calegary	beliefate that pass through as interfere with treatment processes in POTEs or that ser- centaminate present studies.	hidrinfalaidrin, Mif, andeln, las aphane, beneidene, Kfb.	Order damping	ţ	Hining operat lane		Accedent of policians
Times John	Undergraum Sturage Tanta (1978)	Property Degulation for Contest of sele- tions of selective espents	Safe Drinding Mater Art.	Undergrand Injection (note: Population) (off)	Clear Seins Act (CM)	Nichota Milantia	efficant Lieitations	National Protections	Tests Pallatand Efficient Standards	Notice Projection Protects and Sanctuaries Act	Parle Subajaness Control As i IPRA	Section Help Carteel and Performance for Francisco Act	Class hir and ICAN	Mariened Delnalem Standard for Maraching Air Politicals

Main If a trapalirement to applicable, it commet also be relevant and appropriate.

(Continued)

Briguty namet	Preregulaties	Citation	Description	Applicable/Delevent and Appropriate	t'nement 4
National Applient Air (Nation Criteria	Various air contaminants		Sets retisted standards for designated air confectants to protect the public health and vollare.	₹ 05/	All proposed alternatives need to provide adequate level of uniters protection during reached inc.
New Source Performance Utanderds	New stationary source		Sele emission standards for cer- tain classes of new stationary sources of ele poliution,	Yes/	if a certain class of new source is proposed as part of treatment plant.
this spational Safety and Health Art (USHA)	Remedial action workers	(29 USC 451-6781	Requistes worker health and solely.	Yes/	Applicable to worker health and safety.
federal Rine Safety and Health Act	Mork in underground aines	30 VSC 801-967	Regulator working conditions in underground since to assure rately and braith of workers.	No/Ho	Study area is not a minimprolated site.
Recordous Materials Transportation Act		144 USC 1801-18131			
Hazerdous Meteriala Transportation Propilations	Transportation of Insurdous materials	40 CFR In?, 171-177	Regulates transportation of hezerdous materials.	T+4/	If any ulternative requires the offsile transportation of her- ardous materials,

Note: -- - II a requirement is applicable, it cannot also be relevant and appropriate.

ped marriculates.	Control of Fugition	Central of Entrals of Notice day and Insid ble Center- insid	Balanes Class Air Act	Projection Measures	Commender Deality Vianderds	becomes tex	Drimary Degraption and incomments	N p Process Voter	Ago tenditora	Primery Worm Mater	Public & Private Mater Surplice	Syrface Major Opelity Standards	Onlohoma Maier Gmalliy Standards (DMCS)	Property and
20 20 20 20 20 20 20 20 20 20 20 20 20 2		•		fresh grandbater		broignated ees by ONQS	Berigaried are by Degg	Designated use by DMTS	beligneted use by Orth.	Designated use by DwGS.	Devignated use by DMTS.			Prezegalulion
Breulation 3.3	Requisition 3.1	Regulation 3.8	63 0.3. Supp. [180] 3.1861 of seq.	F age then	Dw05 498	11' 00(She	11 DOC 10mg	Dw05 300.18	DWG5 300 #	guers 300 7	9493 300 5	Owers, you	82 Q.S. \$466. \$ 486 926 3, 926 6, 5085 2	Citation
Tate reacomphic precoultums to winimize atmospheric pullution.	Comivel eightle pullysigums and perliculators.	Control of participant of hazardous and tasks conteminants.		Protection criteria for ground mater		Surface Maters are to be sentbertcolly rejurable	Mater shall not contain bubiliness in concentrations that are irritating to skin or are laste or couse illusts upon impetion	Quality triterit has water mood for process or coaling purposes.	Surface maters an intelled so that teattly does not shabit continued imposition by livestect or frispation of coops.	Criterio to promote fish and wildlife propagation.	Criteria for water quality.	to provide that we write by distanced the army waters of the State allowed that was a first and a state with waters.	browner & protect as many beneficial total and the assume that deposition be activiting mobility of voters does not decur.	free; ipt les
4 -0	ged	(Besiz yes)		613		***!	yest	\$\$ p\$\l-:	, , , , , , , , , , , , , , , , , , ,	yes/	end you	7111	peti	Applicable/Beloved
		Man share of head down or their the		that a major provided water harra		Both Friene (spek and Smeth Crime (rook are affects) by anythetic stantarts.	Marth (rimer (resh in designated for including budg (smile) refrestion and (rimer (resh bur grimary refrestion)	Both Crimor Creek and Sprik Crimor Creek are designated for the actual process under-	Both Crime Creek and Burth Crime Creek are designated for howeficed use by apriculture.	bath Borth (rear (res) and from Cresh are daily agent for high and middles propagation.	(rimer (res) is decignated as a mobile d private mater supply	See Specific requirements	Application despends on the designated benefited our at the stream	Congres of a

98

Reproduced from best available or py.

∢ •

APPENDIX B

AGENCY FOR TOXIC SUBSTANCES DISEASE REGRISTRY EVALUATION

Health Assessment for

ROYAL HARDAGE INDUSTRIAL HAZARDOUS WASTE LAND DISPOSAL FACILITY

CRINER, OKLAHOMA

DECEMBER 1988

SUMMARY

The Royal Hardage Industrial Hazardous Waste Land Disposal Facility (Hardage/Criner) National Priorities List (NPL) Site is located in Criner, McClain County, Oklahoma. The site is located in an agricultural area. There are volatile organic compounds (VOC's) and several heavy metals present in the groundwater and soil, and VOC's in surface water and sediment. The Record of Decision (ROD) for the first operable unit (source control) signed November 1986, selected several remedial actions which included excavation of the primary source material and separation of the wastes for treatment: solids to be disposed of in an on-site landfill which meets Resource Conservation and Recovery Act (RCRA) requirements, organic liquids to be incinerated, and inorganic liquids to be treated by other means as necessary. This site is currently in the remedial design phase.

BACKGROUND

A. SITE DESCRIPTION

The Hardage/Criner NPL Site is located in McClain County, Oklahoma, on 60 acres. Operations began at the facility in 1972. Several pits were excavated in the early years to receive wastes from barrels and tank trucks. The pits filled rapidly. The wastes were then transferred to temporary ponds. In the west pond, the wastes were slurried with soil and transferred to the south pond. The south pond was eventually filled and the wastes were then stacked to a height of 10 feet above grade. This became known as the sludge mound (see Appendix).

During the mid-1970's, drums were no longer emptied into the pits, instead they were piled at the north end of the main pit. This became known as the drum mound (see Appendix). During the late 1970's monitoring wells were constructed in the southwest corner of the site. These wells indicated the presence of contamination.

The wastes received by the facility included: oil recycling wastes, chlorinated solvents, styrene tar, acids, caustics, paint sludges, lead, chromium, cyanide, arsenic, pesticides, inks, polychlorinated biphenyl's (PCB's) and large quantities of waste from injection wells and other nearby facilities including two NPL sites, Brio and Bio Ecology.

Operations ceased in November 1980. Closure activities continued into 1982. There was an effort made during the closure activities to consolidate the wastes into major source areas. These source areas are identified in the Appendix.

The ROD for the first operable unit signed November 1986, selected several remedial actions which included excavation of the primary source material and separation of the wastes for treatment: solids to be disposed of in an on-site landfill which meets RCRA requirements, organic liquids to be incinerated, and inorganic liquids to be treated by other means as necessary. This is presently in the design phase. A second Remedial Investigation (RI) was begun in February 1988 to determine what type of migration control should be implemented at this site.

B. SITE VISIT

ATSDR has not conducted a site visit at this time.

ENVIRONMENTAL CONTAMINATION AND PHYSICAL HAZARDS

A. ON-SITE CONTAMINATION AND OFF-SITE CONTAMINATION

The project site boundary depicted in the Appendix was the basis for defining on-site and off-site in this Health Assessment. The values recorded in the tables below reflect the data presented in the Field Investigation and Data Summary Report, Volume 1. Although there were other data received by ATSDR, sampling points were not adequately identified, and therefore, were not utilized in the tables.

Page 1

The results for the surface water and sediment sampling recorded in Appendix H of the Field Investigation and Data Summary Report were not provided to ATSDR for review. However, the discussion provided in the text indicated that methylene chloride and bis (2-ethylhexyl) phthalate (DEHP) were detected in the surface water samples and methylene chloride, fluorotrichloromethane, DEHP, and chloroform were detected in the sediment. (These contaminants may be laboratory artifacts and not site-related.)

Table 1
ON-SITE CONTAMINATION

<pre>Contaminants </pre>	Soil (ma/Ka)	Groundwater (ug/L)
Chloroform	ND0006	1 340 1
1,2-Dichloroethane	ND180	ND1,500
1,1-Dichloroethene	ND6.2	1 105,300
Tetrachloroethene	ND16,000	ND1,800
1,1,1-TCA	ND6,000	1 3332,000
1 1,1,2-TCA	ND1,100	ND1,200
Trichloroethene	ND1,500	1 2936,000
trans-1,2-DCE	ND009	1 1046,000
1,2-DCB	ND150	ND4,300
DDT		ND57
Chromium	ND937	ND28
Lead	ND5,470	1 1
Methylene Chloride	ND1,300	1 2449,000
Xylene (total)	ND1,500	i 1
Toxaphene	ND160	1 1
l Aroclor 1260	ND19	

Table 2
OFF-SITE CONTAMINATION

1	Contaminants	Monitoring (ug/	L) Residential	(ug/L)]
1	Chloroform 1	ND1,300	1	1
- 1	1,2-Dichloroethane!	ND140,000	I	1
ł	1,1-Dichloroethenel	ND4,900	ND6.6	}
1	Tetrachloroethene	ND24,000	ND9.2	1
ļ	1,1,1-TCA	ND31,000	ND29	1
1	1,1,2-TCA	ND50,000	ND120	1
1	Trichloroethene	ND8,000	ND63	1
1	trans-1,2-DCE	ND3,600	79 – סא	1
1	1,2-DCB	ND40	!	1
1	Chromium	ND223	J	1
1	Lead	ND23	1 ND23	1

Legend

TCA trichloroethane

DCE dichloroethene

DCB dichlorobenzene

DDT dichlorodiphenyltric loroethane

-- no concentration reported

B. PHYSICAL HAZARDS

There are no reported physical hazards present at this site.

DEMOGRAPHICS OF POPULATION NEAR SITE

The area surrounding the site is used to graze cattle. A chain-link fence was installed in 1987 which eliminated the past problem with cattle grazing on-site. There are two buildings located on-site. One was the former sludge drying building located northeast of the drum mound. The other was a barn located between the sludge mound and the main pit, which was used as an office. The site is located 15 miles southwest of Norman, Oklahoma, and one-half mile east of the community of Criner. The nearest residence is located along the southwest site boundary.

EVALUATION

A. SITE CHARACTERIZATION (DATA NEEDS AND EVALUATION)

1. Environmental Media

The soil contamination has been well defined. The groundwater and surface water, and the interactions between them, will need to be more completely characterized in the future to determine public health implications. This further characterization should be addressed in the second operable unit (migration control) RI. A drinking water survey should be conducted and a map developed which indicate the location and population using the groundwater (public and private wells) or the surface water.

2. Land Use and Demographics

The land use and demographic data provided to ATSDR were incomplete. Additional information on the current use of residential wells near the site would be useful to ATSDR. If this information does not already exist it should be gathered during the second RI.

3. Quality Assurance/Quality Control

Conclusions contained in this Health Assessment are based on the information received by ATSDR. The accuracy of these conclusions is determined by the availability and reliability of the data.

B. ENVIRONMENTAL PATHWAYS

The bulk of the contamination present on-site is located in the subsurface soil. This contamination is the primary source of the contamination in the other media. The first operable unit ROD requires the excavation of all principal source areas and the appropriate treatment and disposal of such materials. This action should help to decrease the migration of the contamination from these source areas. Additional soil sampling during the second operable unit RI should identify any additional areas of soil contamination.

The groundwater at the site is located in two geologic formations near the site. One formation which is the primary source of drinking water in the area, is the alluvium of North Criner Creek, which is 40 to 60 feet deep at mid-valley. The other formation is the Hennesey Formation which is composed of fractured shale, mudstone, and sandstone. The water located in the upper sediments is potable, but deeper it becomes salty and brackish.

The flow of the groundwater has not been well defined at this time. It appears to flow to the southwest and the east. Leachate has been detected up to 50 feet below the bedrock as well as 400 to 2,000 feet laterally in the bedrock. This is a result of the strong downward gradient and the fractured Hennesey Formation. Contamination has also been detected in the alluvium of North Criner Creek 2,000 feet southwest of the site. The plume is estimated to be 1,000 feet long. The mechanism of this transport is unknown and will be the subject of further study during the second operable unit RI.

The North Criner Creek flows from the northwest to the southeast and is located south of the site. Its alluvial valley extends almost to the southwest corner of the site. North Criner Creek joins Criner Creek approximately 1 mile south of the site. There is also a creek located about 400 feet east of the waste disposal areas. This stream was impounded to create 3 small lakes which cover approximately 6 acres, total. There is a 2-acre pond located 1,500 feet west of the drum mound. Surface water and sediment samples were taken at various locations at the site. These samples indicated the presence of contamination. The additional sampling planned for the second operable unit RI should include surface water and sediment samples to better characterize those media.

There was no ambient air sampling conducted at this site. Without any data to the contrary, air must be considered a potential medium of concern.

Potential environmental pathways at this site include migration of contamination from the primary source areas and the soil to the groundwater, surface water and sediment, biota, and air. There is also the potential for the contamination to migrate between the various media.

C. HUMAN EXPOSURE PATHWAYS

The potential human exposure pathways for this site are ingestion of contaminated soils, groundwater, and surface water; inhalation of dusts or vapors from the source areas, the contaminated soil, or the contaminated groundwater; and dermal exposure to contaminated soil, groundwater, surface water, or sediment.

Inhalation of dusts and vapors generated on-site from the soils is a potential exposure pathway for remedial workers and trespassers at the site. People may be exposed to contamination while performing tasks that require disruption of the soil, thereby causing a release of contaminated dust and vapors. This potential exposure will decrease once remedial work requiring excavation of the contaminated oil and construction of the on-site landfill is complete. Off-site there is a potential for exposure

from fugitive dusts and vapors generated by disrupting the soil at the site, and inhalation of vapors generated while using the contaminated groundwater could occur if water from contaminated wells was used for showering, irrigation, washing cars, etc.

Ingestion of contaminated groundwater is a potential public health concern, off-site. The maximum concentration of trichloroethylene (TCE) (63 ug/L), and trans-1,2-DCE (120 ug/L) reported in Table 2 above, were detected in a residential well that was no longer in use at the time of the sampling. However, the maximum concentration of lead (23 ug/L) reported, was detected in a residential well which was still in use. This concentration of lead is of public health concern. According to the Environmental Protection Agency these homes have been provided alternate water. There is no known use of the groundwater on-site. The concentrations of contaminants detected in the groundwater monitoring wells located on-site are of public health concern and the water should not be used for domestic or agricultural purposes.

Ingestion of soil is a potential human exposure pathway on-site. The problem will center around the workplace (people eating lunch with dirty hands, wiping dirt on their face, etc.). Dermal exposure is a potential human exposure pathway from working with the contaminated soils, especially in the locations of the primary source areas. This potential exposure will decrease once the contaminated soils are contained within the landfill.

There is a possibility of incidental ingestion and dermal exposure to surface water and sediments at the site. The surface water features in the area may be used for recreational activities (e.g., wading, fishing, etc.).

Human exposure pathways that are of public health concern are inhalation of fugitive dusts and vapors generated on-site and vapors generated from use of groundwater off-site; ingestion of contaminated soils, surface water, and groundwater; and dermal absorption of contamination from soil, sediments, surface water, and groundwater.

PUBLIC HEALTH IMPLICATIONS

Much of the contamination detected in the various media are VOC's. Some of these VOC's may cause depression of the central nervous system at high concentrations. Also, some VOC's cause liver and kidney toxicity as well as damage to the pulmonary and hematopoietic systems. In addition, there is evidence that some VOC's are carcinogenic in laboratory animals.

TCE given orally in doses of 24 or 240 mg/kg/d for a period of 14 days produced effects including increased liver weight, decreased hematocrit, and depressed cell-mediated immune response (Tucker et al., 1982, Sanders et al., 1982). Based on liver tumor production in mice, the Environmental Protection Agency (EPA) has designated TCE as a potential human carcinogen. It is unknown how long residents may have been drinking or using for domestic purposes the highly contaminated water present in the plume. Long-term exposure to TCE at the maximum contamina ion detected in residential wells could result in a significant, increased risk of

Page 5

1

cancer and other non-carcinogenic toxic effects such as liver damage and depression of immune function. Therefore the use of this groundwater for drinking, bathing, and other domestic uses is not acceptable.

Lead is known to cause neurological effects in gestating fetuses, neonates, and young children. It can also cause peripheral neuropathy in adults. Other adverse health effects caused by lead include: hypertension, growth retardation, and effects on heme synthesis enzymes and the cell membrane. The maximum concentration of lead detected in the soil at this site was 5,470 mg/Kg and in the residential wells, 23 ug/L. Ingestion of lead at these concentrations is of public health concern.

Acute PCB-related health effects typically occur at higher concentrations than those detected on-site. However, for this site, the primary identified potential health effects, resulting from exposure to PCB's through ingestion, inhalation, and dermal contact, are carcinogenic effects. PCB's, have been designated as Group B2--Probable Human Carcinogens (EPA 1987). This designation is based on experiments which demonstrated the induction of hepatocellular carcinomas in laboratory animals fed high doses of PCB's in their diet (Kimbrough et al., 1975; Norback and Weltman, 1985).

The toxicity of chromium is dependent upon the valence of the cation present (Cr VI or Cr III) and the anion to which it is bound. The valance of the chromium detected at the site was not established; therefore, this assessment is based on the potential toxic effects of Cr VI, which is the more toxic form. The cell membrane is penetrated by Cr VI more easily than Cr III. Once inside the cell, Cr VI is converted to Cr III, which then complexes with deoxyribonucleic acid (DNA) providing an opportunity for cell mutation (EPA 1987). Dermal contact with Cr VI may result in dermatitis or skin ulceration. Chromium can also cause kidney and liver damage. The maximum concentration found in the soil was 937 mg/Kg. Ingestion of chromium at this concentration is of public health concern.

CONCLUSIONS AND RECOMMENDATIONS

A. CONCLUSIONS

This site is of potential health concern because of the risk to human health resulting from possible exposure to hazardous substances at concentrations that may result in adverse health effects. As noted in the Environmental Pathways and Human Exposure Pathways Sections, human exposure to contaminated soil, groundwater, surface water, sediment, air, and biota may have occurred in the past or may be occurring now. The actions in the ROD should reduce the potential exposures to the soil and should reduce the potential for the migration of contamination from the source. The second operable unit RI should provide the additional information required to determine what migration controls should be implemented at the site.

Page 6

B. RECOMMENDATIONS

- 1. During remediation, measures should be taken to protect people on-site and off-site from exposure to any dusts or vapors that may be released. Workers on-site should be provided adequate protective equipment and training, in accordance with 29 CFR 1910.120, and should follow appropriate National Institute for Occupational Safety and Health and Occupational Safety and Health Administration guidelines, when involved in activities that may result in an exposure. Workers should implement optimal dust control measures. During working hours, appropriate monitoring should be utilized at the worksite periphery to protect nearby workers and residents.
- 2. The information requested in the Data Needs and Evaluation Section of this Health Assessment should be provided to ATSDR.
- 3. In accordance with the Comprehensive Environmental Response, Compensation, and Liability Act as amended, Hardage/Criner NPL Site has been evaluated for appropriate follow-up with respect to health effects studies. Although there are indications that human exposure to on-site or off-site contamination may have occurred in the past, this site is not being considered for follow-up health studies at this time because the level and extent of possible human exposure to site chemicals has not been defined and it is unclear that current exposure is occurring. However, if data become available suggesting that human exposure to significant levels of hazardous substances is currently occurring or has occurred in the past, ATSDR will reevaluate this site for any indicated follow-up.


PREPARERS OF REPORT

Environmental Reviewer: Susan L. Mueller, Environmental Health Specialist, Health Sciences Branch.

Regional Representative: Carl Hickam, ATSDR Regional Representative, Region VI.

REFERENCES

- 1. Record of Decision, Hardage/Criner, McClain County, Oklahoma, 1986.
- Field Investigation and Data Summary Report, Volume 1, Royal Hardage Industrial Hazardous Waste Site, CH2M Hill, 1985.
- 3. Hardage/Criner Oklahoma Superfund Site, Partial Summary of Data, 1987.
- 4. Final Preliminary Public Health Evaluation, Technical Memorandum, Royal Hardage Industrial Hazardous Waste Site, CH2M Hill, 1986.
- 5. USEPA Drinking Water Criteria Document for Chromium, 1987.
- 6. USEPA Drinking Water Criteria Document for Polychlorinated Biphenyls (PCB's) ECAO-CIN-414, 1987.
- 7. Kimbrough, R.D., Squire, T.A., Linder, R.E., Strandberg, J.D., Montali, R.J., Burse, V.W., JNCI 55: 1453-1459, 1975.
- Norback, D.E. and Weltman, R.H., Environ. Health Perspect. 60: 97-105, 1985
- Tucker A.N., Sanders V.M., Barnes D.W., et al., 1982. Toxicology of trichloroethylene in the mouse. Toxicol Appl Pharmacol; 62:351-357.
- 10. Sanders V.M., Tucker A.N., White K.L., Jr, et al., 1982. Humoral and cell-mediated immune status in mice exposed to trichloroethylene in drinking water. Toxicol Appl Pharmacol; 62:358-368.
- Casarett and Doull's Toxicology, The Basic Science of Poisons, Ed. 3, Curtis D. Klaassen, Ph.D. et al., Macmillan Publishing Company, New York, 1986.
- 12. Environmental and Occupational Medicine, Rom, 1983.
- 13. ATSDR File.



ı

APPENDIX C

ADMINISTRATIVE RECORD INDEX (with Addendum)

administrative Record Ladex not included.

APPENDIX D
STATE OF OKLAHOMA CORRESPONDENCE

8910013 70 10 69

Men K Leavitt M.D. Commusioner

MAZARBOUR LASTE MOME DIV

DEPARTMENT OF HEALTH

Boord of Health Whiter Scott Auton is ICO mores 8 ma

VCERTORY

C M and extend

Den in Feren DO Burger F Green M.D. CH PORTO MEDIU Errer D Mattr. R.M. Law W. Parson November 13, 1989

R.O. BOX STAR 1000 N.E. TENTI CHILAHOMA CITY, OK 7312

AN EQUIL OFFICETUATY BARLONS



Allyn M. Davis, Ph.D (6H) Director Hazardous Waste Management Division **EPA Region VI** 1445 Ross Ave. Dallas TX 75202

Dear Dr. Davis:

I was surprised to receive your letter requesting concurrence on the Hardage/ Criner Proposed Remedia! Action Plan. We were awaiting additional information and we were given only one working day to formulate a reply.

Please be advised that the discussions we have had with representatives of your agency have not served to eliminate several of our concerns regarding your proposed plan. As you are aware, the Oklahoma State Department of Health (OSDH) received the Remedy Report for the Hardage Industrial Waste Site on October 13, 1989 and subsequently requested briefings in order to cain an appreciation of your proposal. During the briefings your staff was unable to answer any of our questions relative to risk analysis, condition of the barrels and amount of liquids in barrels. Additionally, only some of our concerns relative to control of air emissions and other basic information and assumptions upon which the proposed plan is built were answered.

Your staff promised to forward information relative to some of these issues; however, the information received was either unconvincing or not pertinent to these issues. The important question of relative risk has been left unanswered.

OSDH believes that several of the remedial action technologies proposed for site clean up have merit and in the interest of public health should be instituted as soon as practicable.

elements of merit:

Southwest trench or wells - institute immediately V-shaped trench - Institute immediately Liquid extraction wells Vapor extraction wells - If this element is part of a permanent cap with a vapor control component.

OSDH also believes that there are serious problems with everal proposed clean up technologies presented in the Remedy Report and that these coments of the pian have potential for increasing health risks to the public.

elements of disagreement:

Drum lancing - not recommended

Excavation of drums - not recommended

U-shaped trench - not recommended

Catalytic thermal treatment - as presented will not meet CAA requirements or BACT.

The Oklahoma State Department of Health does not agree with significant elements of EPA's Remedial Action plan for the Hardage/Criner Superfund site as presented and explained to us, therefor, OSDH cannot concur with the proposed plan based on the information currently available.

If you have any questions regarding this matter please call me at (405) 271-8056.

Very truly yours,

Mark S. Coleman

Deputy Commissioner

for Environmental Health

Wat I blen -

APPENDIX E

RESPONSIVENESS SUMMARY

Hardage/Criner Site Community Relations Responsiveness Summary

The Community Relations Responsiveness Summary has been prepared to provide written responses to comments submitted regarding the proposed plan at the Hardage/Criner hazardous waste site. The summary is divided into two sections:

Section I: <u>Background of Community Involvement and Concerns</u>. This section provides a brief history of community interest and concerns raised during the remedial planning activities at the Hardage/Criner site.

Section II: Summary of Major Comments Received. The comments (both oral and written) are summarized and EPA's responses are provided.

I. Background of Community Involvement and Concerns

Individual interest or attention to the site has been moderate since the signing of the 1986 Record of Decision for source control. Individual residents are concerned about their health, food chain impacts, as well as the economy of the area. Residents at the public meeting in October of 1989 indicated their desire for more frequent updates on activities and plans for the site, and for credibility of the remediation through the removal of wastes from the site.

II. Summary of Major Comments Received

Public notice announcing the public comment period and opportunity for a public meeting was given on October 1, 1989. The Proposed Plan fact sheet was distributed to the site mailing list on October 12, 1989. Fact sheets were also sent to site repositories on this date, along with documents comprising EPA's Administrative Record for the site. The comment period began on October 13 and ended on November 2, 1989. A public meeting was held on October 26, 1989, at the Grady County Fairgrounds Community Building in Chickasha. The purpose of this meeting was to explain the results of the Remedial Investigation and Feasibility Study for groundwater, and to explain changes in the source control remedy since the 1986 Record of Decision for the site. Approximately 40 people were in attendance, and a number of questions and comments were received. Two letters were received with questions as well.

The comments/ Jestions received during the public comment period concerned the following

- o the timing and exact location of remedial activities
- o the impa t of contaminated groundwater on the food chain and health
- o safety and health concerns during remediation
- o the loca on and announcement of future public meetings.
- o need for the excavation of drums

Comments were received from the following citizens: Marvin Lyles, Edwin Kessley, Royce Smith, Eilene Whitehead, Kay Hixon and George (Buddy) McKinnon. Letters were received from George McKinnon and Lisa Ozment with Progressive Environmental Management, Inc. Comments received are summarized below, along with EPA responses.

Question #1. Will there be any problems with the roads due to movement of equipment?

Response: The majority of the activities at the site during remediation will take place within the site boundaries. There will be some movement of equipment onto the site to perform the work. The only regular movement will be the shipment of the liquids removed from the source areas as they are taken offsite to be destroyed. These liquids will be accumulated until a load is ready for shipment.

Question #2. Why weren't the source areas covered during the time of the investigations to prevent the infiltration of rainwater?

Response: Actions were taken to eliminate immediate threats at the site, such as erosion of the Barrel Mound. From the end of 1982 when the Hardage property became a Superfund site it was not anticipated that it would take as long as it has for clean-up to begin. This is particularly true of the delay for litigation which has taken place since 1986.

Question #3. Why are there differences in the locations shown for the southwest trench locations in the fact sheet and the overhead during the presentation?

Response: Trench or interceptor well locations shown on overheads during the presentation were only approximate locations specified for the purpose of evaluating alternatives for groundwater control. The trench or interceptor well locations specified in the fact sheet are also approximate and based on the current spread of groundwater contamination. The exact location of the proposed interceptor system will be determined during final design stages of the project, and will be based on the following considerations:

- a) the spread of groundwater contamination immediately upgradient of the alluvium;
- b) the hydraulic properties of the bedrock (these dictate the exact design requirements); and
- c) the location of residential structures and property.

EPA will make efforts to install the interceptor system so as to minimize disruption to homeowners who may be impacted by construction and operation and maintenance activities.

Question #4. Did all of the EPA's information come from the Hardage Steering Committee's investigation or did EPA do its own studies.

Response: Much of the information about the Hardage site has come from multiple sources. EPA, the Oklahoma State Department of Health (OSDH), and the Hardage Steering Committee (HSC) have all gathered information about the site. The most recent investigation, that of the area groundwater, was conducted by the Hardage Steering Committee under the terms of a formal agreement with EPA. Among the terms of the agreement were provisions for EPA oversight of the work, split sampling by EPA to check the HSC's sample results, and EPA review and comment upon the investigation reports, and final EPA approval. EPA has its own experts and employees to examine the information gathered and is not dependent upon the interpretations put on the raw information by the HSC.

Question #5. How deep is the underground water in the area of Mrs. Smith's property?

Response: Water level measurements in the alluvium in this area indicate that the groundwater table is about 15 feet below the ground surface.

<u>Question #6.</u> Is there any threat from eating from pecan trees that have roots into the contaminated groundwater?

Response: Wells in the vicinity of the homestead in question (MW-12, 13, and 28, for example) exhibit detectable concentrations of contaminants. Contaminants detected in the alluvium include the following compounds at the concentrations indicated:

Compound	Concentration Range (parts per billion)	Drinking Water Standard (parts per hillion)
Total volatile organics (VOC) 39 - 560	not set
Arsenic	1 - 7	50
Selenium	6 - 52	10

As the table indicates, selenium and VOCs are present at levels which pose a concern for drinking water. Whether these contaminanats are taken-up by pecan tree roots is not known. EPA will search for information on exclusion mechanisms in pecan trees, and further evaluate this question.

Question #7. There were noxious fumes from the site during its operation. What about these fumes?

Response: During the time that the Hardage site was open, much of the waste that was hrought to the site was exposed to the air. There were open ponds containing waste and drums and piles of more solid material were also left uncovered. This allowed the fumes to escape from these sources. The potential for escape of fumes is dependent on the surface area of contaminated material which is exposed. During the selected remedy, the major potential for such exposure is during excavation of the drums from the Barrel Mound and the Main Pit. Three direct actions will be taken to control the formation of fumes. First, the excavation will be done on the smallest practical working face. This means that the area disturbed to remove the drums and any one time will he kept at a minimum so that as little contaminated material will be exposed to the air as possible. The second step will be constant monitoring of the air both around the excavations and at the fence line. The third is would be the use of engineering controls to prevent vapor release problems. This would entail the use of foam supressants to stop the escape of the fumes up to stopping operations and recovering the exposed areas if the fumes cannot he controlled.

Question 8. Is EPA aware of a report by Kirk Brown from Texas A & M saying that contamination is worse than EPA says?

Response: One of the government's experts for the purposes of the upcoming trial on the Hardage site is Dr. Kirk Brown. Mr. Brown is therefore representing the government and EPA is in agreement with his opinions, which involve significant measures to directly reduce contamination in the main source areas.

Question #9. When will a final decision be made on what will be done to clean up the site?

Response: The Record of Decision which was issued at the same time as this Responsiveness Summary completes the EPA's administrative process for selecting the clean-up method for the site. There is also a trial on this issue which is scheduled to begin on November 27, 1989 in Federal District Court in Oklahoma City and which should last no more than twenty days. The Judge will then give his decision on remedy.

Question #10. The notice that appeared in the Daily Oklahoman was not sufficient to notify the local residents about the meeting on the sit2. Notice needs to be provided in papers which the local people use.

Response: The regulations governing the issuing of public notice require that a daily paper he used to give the notice. However, that doesn't prevent the placing of additional notices in other papers. In the future add tional papers will be used including the Purcell Register, Chickasha Star, and the Blanchard News.

Question #11. The meeting should have been held in McClain County where the site is and not in Grady County.

Response: Future meetings will be held at a location in Purcell.

Question #12. Will transcripts of the meeting be available to the public?

Response: Yes. A copy of the meeting transcript will be placed in the public repository for the site in the Purcell Public Library, the offices of OSDH in Oklahoma City, and at EPA's offices in Dallas. In addition, copies will be available on request from either Mr. Underwood or Ms. Price at EPA.

Question #13. There are carcinogenic compounds in the water that has been used by the Whiteheads (including children and infants) over the past 14 years. This contamination is moving to Criner Creek, which in turn runs into the Washita. At what rate is it moving?

The Whiteheads were provided alternate water from the McClain County Rural Water District No. 7 in 1987. Prior to this, domestic water supplies came from wells installed in North Criner Creek. Groundwater contamination has migrated to a location in North Criner Creek which is approximately 1600 feet downstream of the North Criner Creek bridge on Old State Highway 122. Groundwater flow rates for the upper alluvium are estimated to be between 80 and 170 feet per year and that for the lower alluvium between 9 and 19 feet per year.

Question #14. How many years until this contamination is contained?

Response: Groundwater contamination will be removed when the groundwater interceptor system and source control components (soil vapor extraction, drum excavation and liquid extraction wells) are installed. Construction is expected to take some five months from start to finish. Construction will begin as soon as the litigation ends and the trench design is approved by EPA.

Question #15. Do we know how much contamination is present in Criner Creek?

Response: We know there are levels of contaminants in the North Criner Creek alluvium (see answer to Question #6). Low levels of contaminants have also been detected in surface water samples of North Criner Creek. Contaminants, however, have not reached Criner Creek.

Question #16. How much time will be needed from the time a decision is made to the start of the clean-up?

Response: Once a decision has been made (see Response to Question #9) it normally takes about nine months for clean-up to begin. Unlike most sites, much of the preliminary design has been completed for trial, and therefore work could begin within several months of a final remedy decision.

. -

Question 17. Should the Whiteheads continue to farm?

Response: Results of the Public Health and Environmental Endangerment Assessment (PHEEA) conducted during the groundwater investigation indicate that it is safe for the Whiteheads to farm. The PHEEA evaluated exposure scenarios which assumed dermal contact with affected water and injestion of affected water, beef and milk for various age groups. The results of risks associated with exposure scenarios are summarized in the Second Operable Unit Feasibility Study, which indicate risks below EPA's common acceptability range for risks associated with Superfund clean-ups (1 in 1,000,000 risk). Probable scenarios of future land use were developed for exposure calculations Probable exposure scenarios for a child or adult were a few orders of magnitude below EPA's acceptablilty range, however, worst case scenario results showed risks from exposure to be between 10-4 through 10-5.

Question #18. Will appeals be made to the court decision?

Response: We do not know. Certainly all sides in the case have the legal right to do so, but whether or not that right will be exercised will have to be seen after a ruling has been made.

Question #19. Some of the residents near the site have been told they will have to move for the clean-up. What if they do not want to?

Response: It is not and has never been the position of EPA that any of the area residents would have to move. Because of the need to locate some of the portions of the groundwater portion of the clean-up off of what was the original Hardage site, access to some area properties may be needed to implement the clean-up. EPA does not feel that it is necessary to move for the purpose of institutional controls, but cannot rule out the possibility of temporary re-location during remedy construction. If no agreement can be reached on allowing access to property for implementation of the clean up the government could as a last resort obtain such access through the use of emminent domain. However, the need to resort to such a method has been rare.

Question #20. Is there water contamination to the north? My grandfather drilled three wells in an area of North Criner Creek north of the area of contamination shown in the fact sheet.

Response: Data collect for and by EPA does not indicate that contamination has migrated to this area. To be on the safe side, however, the Oklahoma State Department of Health (OSDH) has sampled the wells in question. The has indicated that results were sent to residents, which showed no detectable contamination.

Question #21. Has all of the seismigraphic work in the area fractured the bedrock?

Response: Geologic studies at the site have revealed details regarding the stratigraphy and structure of the site area. While fractures were noted in the local bedrock, there is no reason to believe these have been caused by seismic testing in the area.

Question #22. Are there faults in the area?

Response: Studies reported in the literature have provided evidence for deep, complex faulting in the Criner region. Depths of over 5000 feet are suggested for such complex faulting. No evidence has been found in the literature to suggest that these faults extend up into the younger (less than about 1000 feet deep) bedrock in the vicinity of the site.

Question #23. Something needs to be done quickly to remedy the site problems.

Response: EPA agrees with this statement. Fortunately the upcoming trial is set for November 27, 1989.

Question #24. The reputation of the area has been devastated and property values depressed. These things aren't being addressed. The only way to restore confidence is to remove the drums from the site completely and highly publicize the event.

Response: The selected remedy calls for the removal and destruction of contaminants contained in the source areas through liquid extraction, excavation, and soil vapor extraction. The rapid and permanent destruction of contaminants is one of the primary benefits of the selected remedy over other options that have been proposed or considered.

Question #25. Once remediation of the Hardage/Criner Site is complete and for some unforeseen reason the selected means of remediation does not prove to be sufficient, will the PRP's be financially responsible for an extended remediation?

Response: Responsibility remains even after remediation. Should additional activity beyond that selected in this Record of Decision be needed the same parties would still be liable for remediation. Such determinations are made on the basis of the 5 year Superfund review process and though re-openers in consent agreements, which provide for continuing liability if additional work becomes necessary.

Question #26. If material from the site is transported offsite to another disposal facility and this facility later becomes a Superfund site will the PRP's be financially responsible for the material transported to the site from Hardage/Criner?

Response: The generators of the material would still be responsible for it. This scenario is not expected to occur as the materials taken offsite should be destroyed in compliance with EPA regulations.

Question #27. Can the land he put back like it was?

Response: No. The best that can be done is to remove and destroy as much of the contamination as is possible and to reduce the threat posed by what contamination remains by limiting its mobility and by careful maintenance and monitoring of the site. Because of the need to maintain a cap on the site, the land will very likely lay fallow.

Question #28. (OSDH) The objective of Superfund is the protection of public health and the environment. Any release of contamination into the water or air resulting from the remedial action at the site is inappropriate and runs counter to this objective.

Response: The objective of Superfund is the protection of human health and the environment. This objective includes protection from both long-term and short-term risks. The short-term risks posed by excavation of the drums from the source areas exist, but can be controlled as described in the Response to Question #7 for releases to air. The excavation of buried drums is an established technique which has been successful at similar hazardous waste sites. Experience at such sites has shown the precautions which need to be taken to minimize any short-term risks to the site workers or to the public.

The long-term risks associated with the Hardage site are a grave concern. Ultimately this concern can only be minimized by the recovery and destruction of the contaminants. No one can predict what will occur over time as the drums buried in the source areas corrode and continue to release their contamination to escape into the environment. As these wastes mix and migrate the risks they pose will continue. These risks include chronic, long-term risks posed by carcinogenic compounds. With no known time limit for the release of the contamination from the source areas a choice is apparent between rapid removal and destruction of contaminants using pre-planned engineering and safety controls successful in other similar excavtions. The alternative is attempts, with many uncertainties, to achieve long-term containment of hazardous and carcinogenic contaminants which are mobile and subject to continued release into the environment under conditions that are neither known or controlled.

Question #29. (OSDH) The data provided does not support the volume or condition of the drummed waste that was used to justify the removal component of the proposed plan.

Response: It is true that assumptions have been made about how many of the buried drums still contain liquid waste. Faced with the choice of hoping that perhaps all or most of the drums are empty or making the more conservative assumption that they are not, EPA assumes that they continue to pose a threat. Given the stakes, the health of local residents and the environment, we would rather take the precaution of making this assumption and then discover that the drums are empty than gamble that they are empty and later be tragically proven wrong.

Question #30. Can we be confident that all areas relating to soil vapor extraction have been addressed? Can we be confident in the catalytic oxidation process and that this in itself would not contaminate the air?

Response: Once EPA selects the final remedy for the site, a detailed remedy design will be prepared and approved. This design will necessarily address all areas of concern during remediation, including refining the areas of contamination, evaluation in detail the performance of soil vapor extraction, and covering details of health and safety during remedial activities. As far a catalytic oxidation is concerned, EPA is required to utilize the Best Available Control Technology (BACT) for the destruction of contaminated vapors resulting from soil vapor extraction. This is a requirement of the Clean

Air Act and State regulations. If catalytic oxidation does not meet BACT, then an alternate thermal destruction technology will be used. Air monitoring onsite and at site boundaries will be instituted to assure air quality remains below action levels desiged to protect human health.

Question #31. The rural water system should be extended to those concerned about possible domestic groundwater contamination.

Response: There are currently no plans to further extend the rural water system through Superfund. Conditions which would warrent such an extension, such as threatened or impacted groundwater in drainages outside North Criner Creek, do not exist. Questions about potential groundwater contamination from the site have been evaluated and indicates that groundwater plumes are migrating primarily into the alluvium of North Criner Creek where alternate water has been supplied. Planned actions in the alluvium would assure that contamination in the alluvium is geographically controlled and concentrations reduced.

Question #32. A park or recreation area should be set up with information about the site.

Response: EPA has established a repository at the Purcell Public Library which contains all such information.

EPA responses to revisions of the Second Operable Unit reports prepared by ERM-Southwest are found on the following three pages. These revisions were submitted to EPA during the public comment period and are treated since EPA approved the Second Operable Unit RI/FS prior to this time.

TECHNICAL REVIEW COMMENTS AMENDMENT NO. 1

SECOND OPERABLE UNIT REMEDIAL INVESTIGATION REPORT REVISION NO. 1 HARDAGE SUPERFUND SITE CRINER, OKLAHOMA

The United States Environmental Protection Agency (EPA) conducted a technical review of the Revision No. 1, dated October 10, 1989, to the Second Operable Unit (OU) Remedial Investigation Report (RI) prepared by ERM-Southwest, Inc. Users of the RI should be aware that EPA has a number of comments and technical concerns regarding the report and its Revision No. 1.

Previous EPA review comments were organized to align with the Summary and Conclusions Section (Chapter 6) of the RI report. Individual responses were presented for each of 54 conclusions in Chapter 6. These responses addressed the major areas of concern that EPA has with the RI.

This amendment addresses the October 10, 1989 major revisions to the Summary and Conclusions section (Chapter 6) of the RI report. The revised conclusion is noted and the new response is presented beneath it. Comments could be raised for each of the revised technical sections and subsections of the report.

Users of the RI should therefore consider EPA's broad responses and noted data limitations as needed when reviewing the individual technical sections or appendixes contained within the RI.

Revised Conclusion Chapter 6--Introductory Paragraphs

EPA disagrees that Stratum II is relatively impermeable; while it may be of lower overall permeability than overlying or underlying units, Stratum II contains fractures and sandstone lenses. The source mounds are also not entirely within the bounds of Stratum II. Excavation of the source mounds into Stratum I sandstones is also suspected.

The presence of !rummed solids and liquids in other portions of the Main Pit besides the west side) is also expected.

Data developed by the HSC expert panel investigation was sponsored by the HSC for their ongoing litigation purposes. This study, as part of litigation, has not been endorsed by EPA.

Revised Conclusion No. 11

EPA does not agree with the characterization of Stratum II as a low permeability unit.

The hydraulic head measurements alone do not yield information on the vertical rate of groundwater movement through Stratum II. Hydraulic conductivity and porosity values are also necessary.

EPA does not agree with ERM's revised groundwater velocities for Stratum I and Stratum III. ERM's values were calculated using median hydraulic conductivity values and the lowest hydraulic gradient observed during the study. Recalculating the velocities using the range of measured hydraulic conductivities and hydraulic gradients reveals that Stratum I velocities could range from 1/2 to 1,000 feet per year and Stratum III velocities could range from 0.003 to 250 feet per year.

Revised Conclusion No. 15

No comment.

Revised Conclusion No. 21

EPA desires to state that the period of record, while revised to include a longer period, is still relatively short and may therefore not be fully representative of the range of flows that may be encountered in the creek.

Revised Conclusion No. 26

The peak flow measured for the south pond may not be relevant since it is controlled by discharge through a pipe rather than site hydrology.

It should be noted that the period of record, while revised to include a longer period, is still relatively short and may therefore not be fully representative of the range of flow from the south pond or the alluvium.

Revised Conclusion No. 43

The modeling performed by SSPA was not conducted as an approved task under the second OU work plan. This modeling is being performed as a result of the HSC litigation effort and will be evaluated separately.

As stated in previous responses, EPA does not agree that the contamination found in the alluvial system is predominantly the result of surfical transport.

Revised Conclusion No. 45

See Revised Conclusion No. 43 response.

Revised Conclusion Nos. 54 and 55

The PHEEA does not address the exposure pathway that led to the provision of an alternative drinking water supply to the residents previously dependent on well water from the North Criner Creek alluvium. The PHEEA also ignores the potential exposure of humans via the ingestion of aquatic organisms, at an annual consumption of about 5 pounds per year, which is possible under a recreational scenario for North Criner Creek. This is very important since the 10⁴ carcinogencic risk criteria for some volatile organic compounds, (such as 1,1-Dichloroethene at 1.85 ug/1) relative to the consumption of aquatic life, is less than CLP contract detection limits.

The PHEEA also does not address a "no action" alternative that action alternative risk reductions can be compared to.

The range of risks developed in the PHEEA are applicable only to the exposure scenarios evaluated and are lacking in that the ingestion of ground water and/or aquatic life potential exposure scenarios are conspicuously absent.

The PHEEA also does not use reference doses, Rfds, nor does it follow the more recent EPA guidance for the preparation of Human Health Evaluations 9285.701A dated July 1989.

APPENDIX F

1986 RECORD OF DECISION FOR SOURCE CONTROL

RECORD OF DECISION

(ENFORCEMENT DECISION DOCUMENT)

Site

Hardage/Criner located in McClain County, Oklahoma

Documents Reviewed

I am basing my decision on the following documents which describe the cost-effectiveness of source control remedial alternatives for the Hardage/Criner Site:

- Field Investigation and Data Summary Report, Royal Hardage Industrial-Hazardous Waste Site near Criner, Oklahoma, by CH2M Hill, dated May 1984.
- Source Control Feasibility Study, Royal Hardage Industrial Hazardous Waste Site near Criner, Oklahoma, by CH₂M Hill, dated February 1985.
- Preliminary Public Health Assessment for Groundwater Ingestion for the Hardage/Criner site by CH₂M Hill, dated August 1985.
- * Summary of Remedial Alternative Selection, November 1986.
- Data gathered prior to and during enforcement actions in 1982 as described in Appendix A to the Summary of Remedial Alternatives.
- August 1986 memo, Bill Langley to Bob Davis describing review and confirmation of 1984 data from sludge mound sampling.
- Public comments received March 10 April 15, 1986 on the Source Control Feasibility Study.
- Community Relations Responsiveness Summary, November 1986.
- Staff summaries and recommendations.
- Reference materials for the documents listed above.

Description Of Recommended Final Source Control Remedy

Excavate the principal source areas (drum mound, main pit, and sludge mound) to bedrock and separate wastes for treatment as follows:

 Solids - treatment and disposal in an on-site landfill cell constructed and operated in compliance with the Resource Conservation and Recovery Act of 1976, as amended (RCRA).

- * Organic liquids will be incinerated.
- Inorganic liquids will be treated and disposed by other means, as appropriate.

Temporarily close areas of residual contamination at the former source areas until remedial action is selected under the second operable unit.

Decision

Consistent with the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA) and the National Dil and Hazardous Substances Contingency Plan (40 CFR Part 300), I select the remedy described above (alternative number seven from the Source Control Feasibility Study) for the Hardage/Criner site. I have determined that this remedy is cost-effective and is protective of public health and welfare and the environment. The action will require operation and maintenance to maintain the effectiveness of the remedy. Since wastes will be left on-site, the remedial action will be reviewed every five years to assure that the remedy is still protecting public health and the environment. The State of Oklahoma has been consulted on the remedy. I have considered Section 121 of the Superfund Amendments and Reauthorization Act of 1986 (SARA), including the cleanup standards thereof, and certify that the portion of the remedial action covered by this Record of Decision (ROD) complies to the maximum extent practicable with Section 121 of CERCLA (as amended by Section 121 of SARA).

If negotiations are successful, potentially responsible parties (PRPs) will enter into a Consent Decree with EPA authorizing the PRPs to implement the remedial action. In the event that negotiations are unsuccessful, on-going litigation will be pursued by EPA and the Department of Justice in an effort to secure performance of the remedial actions.

11/14/86 Date

-Frances E. Phillips

Acting Regional Administrator

HARDAGE/CRINER RECORD OF DECISION CONCURRENCE

ally mais

Allyn M. Davis, Director Hazardous Waste Management Division

Robert E. Hannesschlager, Chief Superfund Enforcement Branch

Larry D. Wright, Chief Superfund Enforcement Section Paul Seals Regional Counsel

Bennett Stokes, Chief Solid Waste and Emergency Response Branch, Office of Regional Counsel

SUMMARY OF REMEDIAL ALTERNATIVES SELECTION

FOR SOURCE CONTROL

HARDAGE/CRINER SUPERFUND SITE
MCCLAIN COUNTY, OKLAHOMA

NOVEMBER 14, 1986

SUMMARY OF REMEDIAL ALTERNATIVE SELECTION HARDAGE/CRINER MCCLAIN COUNTY, DKLAHOMA

	1.0	Site Location and Description
_	2.0	Operating History
	3.0	Current Site Status
T i	4.0	Risk to Public Health and Welfare and the Environment
E	5.0	Alternative Development and Screening
1	6.0	Selected Alternative
Ħ	7.0	Compliance of Remedial Action with Applicable or Relevant and Appropriate Requirements
L	8.0	Operation and Maintenance of the Remedy
	9.0	Compliance of Source Control Remedy with Section 121 of the Superfund Amendments and Reauthorization Act of 1986 (SARA) to the Maximum Extent Practicable
l	10.0	Other Operable Units
<u>ئ</u> ا	11.0	Enforcement
	12.0	Community Involvement
	13.0	References
	APPE	NDICES:
1.		A) Chronology of EPA Site Investigations Prior to 1984
		B) List of Potentially Responsible Parties Identified for the Hardage/Criner Site
		C) Community Relations Responsiveness Summary on the Source Control Feasibility Study

SUMMARY OF REMEDIAL ALTERNATIVE SELECTION HARDAGE/CRINER MCCLAIN COUNTY, OKLAHOMA NOVEMBER - 1986

1.0) SITE LOCATION AND DESCRIPTION


The Hardage/Criner site is located in McClain County, Oklahoma, roughly 15 miles southwest of Norman, Oklahoma and 1/2 mile east of the community of Criner (Fig. 1). The area is agricultural with land on all sides of the site used for grazing cattle. Oklahoma Highway 24 forms the southern boundary of the site and a gravel road runs along the east side of the site (Fig. 2).

2.0) OPERATING HISTORY

The Royal Hardage Industrial - Hazardous Waste Land Disposal Facility was issued an operating permit by the Oklahoma State Department of Health (OSDH) in September 1972 and commenced construction immediately. Two pits were excavated, the main pit and the south pit. Originally, liquids and sludges from drums and tank trucks were discharged directly to these unlined pits. The methods of liquid disposal were evaporation and infiltration; however, the main pit filled to capacity rapidly. Waste from the pit was transferred to temporary ponds, the "west pond" area, where liquids were slurried with soil, transfered on to the south pit and disposed concurrently with styrene tar and oil recycling residues. The south pit was eventually filled in and waste piled to a height of about 10 feet above grade, forming the "sludge mound". After the first years operation, drums were no longer emptied, but rather piled at the north end of the main pit beginning the "drum mound". The mound was extended southward and built to a height of about thirty feet. In all, roughly 18 to 20 million gallons of waste were disposed at the site during its operation. The sequence of operations has been compiled from OSDH inspection reports and a deposition and hearing testimony of the facility owner/operator. In 1978, the State of Oklahoma filed complaints against the facility for suspected lead poisoning of air around the site. In September 1979, OSDH began proceedings to revoke the facility permit for operating unpermitted pits, failure to seal permeable lenses in the pits, improper closure of pits, failure to retain runoff, and improper storage of wastes. In September 1980, the U.S. Department of Justice (DOJ) filed suit on behalf of the Environmental Protection Agency (EPA) against the facility under Section 7003 of the Resource Conservation and Recovery Act (RCRA). Operations ceased in November 1980 prior to the effective date of RCRA interim status requirements. Royal Hardage then undertook site decontamination and closure efforts which extended into 1982. These efforts consisted of mixing fluids in the pits with soil, excavating visibly contaminated soils from mixing areas and temporary ponds and capping the source areas with a layer of soil. During closure, an effort was made to consolidate wastes in the source areas (sludge mound, main pit, and drum mound).

AR0001851

Ţ





3.1) Site Investigations:

The site was inspected frequently by OSDH during its operation. Inspectors reported widely varying conditions, with problems initially centered around pits filled to capacity and the potential for overflow. In 1976 OSDH requested that Hardage installed groundwater monitoring wells in the southwest drainage. Eventually, thirteen monitoring wells were installed by the operator. These have been periodically sampled ever since, showing uniformly high levels of contamination. Some Hardage wells may have become contaminated by surface runoff entering the well bore during and immediately after construction. However, repeated purging of these wells has not lowered the levels of contaminants.

EPA first inspected the site in July 1979 due to asbestos disposal. EPA contractor Ecology & Environment (FIT) collected samples at the site in August 1979, August and October 1980, and in March and August 1982. In 1984, work was begun by EPA contractor CH₂M Hill to gather supplemental data to allow preparation of a Feasibility Study (FS) for permanent remedial actions on the site. This supplemental data was compiled and field work was documented in a Data Summary Report (DSR) completed in May 1985. A chronology of EPA sampling efforts prior to 1984 is given Appendix in A.

3.2) Contaminants:

The site was permitted to accept all types of industrial and hazardous wastes except radioactive materials (OSDH-1972). A total 18 to 20 million gallons of waste was logged into the site. The resulting mixture contains virtually every type of waste produced by industries operating in the States of Oklahoma and Texas from 1972 through 1980. The general types of waste accepted at the site included: oil recycling wastes, chlorinated solvents, styrene tars, acids, caustics, paint sludges, lead, chromium, cyanide, arsenic, pesticides, inks, PCBs, and large quantities of waste of unknown content from injection wells and other facilities including what became the Brio and Bio Ecology Superfund sites (Hardage 1972-1980, Eltex 1985). Under each of these broad waste types are numerous specific wastes streams produced from perhaps hundreds of different industrial processes, each waste having it's own unique characteristics, impurities, and inherent hazardous and toxic properties.

Some of the contaminants which pose an immediate threat through groundwater are chlorinated solvents, including: 1,2-dichloroethane, 1,1,2-trichloroethane, 1,1-dichloroethene, tetrachloroethene, and trichloroethene (CH2M Hill 1986a). Other compounds such as lead, chromium, PCB, and toxaphene are present on the site and will pose long term or permanent hazards due to their persistence in the environment. This is by no means an exhaustive list of either the wastes sent to the site or the contaminants of concern; further information is contained in the source control FS.

250001851

3.3) Remaining Features:

Source areas include the main pit, drum mound, and sludge mound (Figure 2). The slude mound covers 1.5 acres to a thickness of from 15 to 20 feet above and within the former south pit.

The main pit covers about two acres with a 15 to 20 foot thickness of waste having been slurried with soil and backfilled into the pit, bringing it to the grade of surrounding land on the east and forming a steep berm 10 to 20 feet high on the west. A high concentration of drums is located along the west side of the pit and in the barrel mound which covers about 0.8 acres to a thickness of 30 to 40 feet. Estimates of the number of unemptied drums remaining in the source areas ranges from 10,000 to over 20,000, with knowledge of site operations and history favoring the latter (Hardage 1972-80).

Other areas of the site were used as temporary holding and mixing ponds or may have been incidentally contaminated during site operations. These areas are the west ponds, east ponds, north pit, and the southwest drzinage (Figure 2).

Two buildings are still on-site. A former sludge drying building used during the last year of operations is located northeast of the drum mound. A barn, used as the office, is between the sludge mound and main pit.

3.4) Hydrology:

North Criner Creek runs in a northwest to southeast direction south of the site with the alluvial valley extending nearly to the southwest corner of the site. This stream is perennial and joins Criner Creek roughly one mile south of the site. Criner Creek empties into the Washita River thirteen miles south of the site.

A stream runs along the east side of the site, about 400 feet east of the waste areas. This stream has been impounded to form a chain of three small lakes totalling about 6 acres. Another two acre pond lies about 1500 feet west of the drum mound.

3.5) Geology:

The site lies in what are commonly referred to as "redbed" sediments. This is a thick sequence of shales, mudstone, and sandstones which grile back and forth over the space of tens to hundreds of feet. The geology was originally described as consisting of the Bison shale overlying the Purcell sandstone. Site investigations indicated the units are not differentiated at the site; so shallow bedrock is referred to collectively as the Hennesey formation (CH₂M Hill 1985).

Beds generally dip to the south and southwest at less than 5° . No major faults are believed to underlie the site. However, a well defined regional joint system is present with joint sets observed at N 20° W, N 20° E, and N 50° W (Kent 1982).

The alluvium of North Criner Creek is 40 to 60 feet deep at mid valley and made up of decomposed bedrock from adjacent uplands.

3.6) Geohydrology:

The groundwater table beneath the site generally follows topography and flows are to the southwest and east. Adjacent monitoring wells completed at different depths strongly indicate a vertical (downward) flow component exists. Shales and mudstones underlying the site are fractured and provide a secondary permeability which, coupled with horizontal sandstone beds, has allowed migration of leachate from 400 to as much 2000 feet laterally through the bedrock and over 50 feet beneath the bedrock surface. Questions exist on the method of transport to the southwest, where waste has migrated over 2000 feet by unconfirmed pathways to enter the alluvium of North Criner Creek and apparently form a plume over 1000 feet long in the alluvial aquifer. Further evidence of the bedrock's inadequacy as a barrier to migration is provided by consideration of contamination in two of the CHpM Hill - 1984 wells (BW-4, GTW-3) and in a series of four FIT - 1982 wells (EW-3, EW-5, EW-6, and EW-7) located to the east and southeast of the sludge mound. These wells are in areas where no site operations occurred and where runoff would not be channeled by topography. The observed 400 feet of migration into these wells over the twelve years between 1984 and 1972 indicates a rate of transport greater than 33 feet per year.

3.7) Areal Groundwater Supplies:

Where possible, residents of the area have drilled water supply wells into the shallow alluvium of streams such as North Criner Creek. However, farms not located in alluvial valleys and without access to these supplies can and have drilled producing wells into the Hennesey formation within one mile of the site. Although not formally classified, both the Criner and North Criner Creek alluvial aquifers and the Hennesey formation would generally be categorized as Class IIb under the EPA Groundwater Protection Strategy.

Fresh water in this area is generally contained in the upper sediments, with water becoming progressively more salty or brackish with depth as indicated in Figure 3 (USGS -1966).




FIGURE 3:
Regional hydrogeology

E0001156

3.8) Extent of Contamination:

Groundwater has been contaminated beneath and adjacent to the source areas, in the southwestern drainage, and to the east and southeast of the source areas to depths greater than 50 feet. The alluvium of North Criner Creek has been contaminated, as evidenced by the presence of from 100 to 300 ppb of volatile organic chemicals in three separate wells, which indicates a plume over 1000 feet long (Figure 4). The relative contribution of surface and subsurface pathways to alluvial contamination is unknown. However, transport rates observed on other parts of the site indicate the source areas will, over time, continue or begin to introduce contaminants to the alluvial aquifer through surface and subsurface migration routes.

Soils may be contaminated over several tens of acres as a result of indiscriminant operations and closure. Evidence of this is provided by both visible surface contamination and stressed vegatation. Determination of the extent of surface contamination will require a significant sampling effort during the second unit RI to adequately define the areas requiring remedial measures.


4.0) RISK TO PUBLIC HEALTH AND WELFARE AND THE ENVIRONMENT

Many of the compounds present at the Hardage site are either known or suspected carcinogens. Other compounds either are or are believed to be acutely toxic or capable of causing damage to specific organs. Some of these compounds also bio-accumulate in plant, animal, and human tissues.

The principal routes of exposure for humans are: Groundwater ingestion, direct contact, ingestion resulting from contamination of the food chain and possibly exposure to airborne contaminants.

The alluvial aquifer of North Criner Creek represents the most readily available source of drinking water in the vicinity of the site. This aquifer is contaminated with varying amounts of several chlorinated solvents, as evidenced by sampling of water from the abandoned Corley well and three alluvial monitoring wells. Since several of the compounds detected in these samples are either known or suspected of inducing cancer and/or damage to specific organs of the body, chronic consumption of this groundwater would pose unacceptable health risks.

The Smith and Atkinson/Bearden wells a : located 200 and 700 feet respectively from contaminated monitoring wells. Domestic use of water from the abandoned Corley well or the EPA monitoring well AW-S03 would pose lifetime cancer risks in excess of 10-4. Use of groundwater from on-site would pose an excess lifetime cancer risk averaging 2% and up to 60% (CH₂M Hill, 1986a).



Direct contact with wastes on the surface of the site also poses hazards; however, the health risk has not been quantified. Determination of acceptable levels of surface contamination will be a primary concern in the second unit FS. Current human traffic on the site is minimal; but cattle do occasionally graze on the site. Contamination of the food-chain by lead, chromium, pesticides, and PCBs, on the surface of the site poses long-term hazards. This concern has prompted construction of a fence to keep cattle off of the source areas; however, there is evidence of continued intrusion by cattle, giving rise to concerns of food chain contamination. Certain compounds such as pesticides and PCBs have the ability to bioconcentrate through successively higher levels of the food chain (EPA 1985a).

Inhalation of volatiles and contaminated airborne particulates on and possibly adjacent to the site may also pose long term hazards; however, this has not been confirmed.

5.0) ALTERNATIVE DEVELOPMENT AND SCREENING

In accordance with Section 300.68(f) of the NCP and EPA guidance documents (EPA 1985b), several alternatives were developed for source control remedial actions at the Hardage/Criner site. Scoping of general alternatives and objectives for remedial action was first discussed in a 1983 meeting between EPA, OSDH, and EPA contractors. After reconsidering these objectives and alternatives in light of the decision to proceed with a source control operable unit, eleven alternatives were developed (Table 1), as documented in the FS. Of these alternatives, four were retained after screening and developed in further detail (see Section 5.2-5.5 below). Estimated cost ranges for the four alternatives retained are shown in Figure 5.

5.1) Alternatives eliminated in screening:


The most notable result of alternative screening was the elimination of those plans for containing the wastes in place. Several methods of isolating the wastes and reducing or eliminating their release were considered. After screening of technologies, several in-situ containment plans were developed. Of these, capping in conjunction with vertical trenches to intercept shallow groundwater (Alternative #5) would be expected to be the most effective. While this plan may be the most effective in-situ containment plan, it can by no means be considered as an adequate remedy on that basis alone. Consideration of this alternative did, however, serve as a test of whether or not any form of capping-in-place remedy would sufficiently contain the source areas. Technologies such as slurry walls and groundwater injection/withdrawl were eliminated due to the presence of fractured bedrock, observed vertical migration of contaminants, and the absence of any continuous horizontal bedrock layer at

TABLE 1 - Source Control Remedial Alternatives

E

Ŀ

- Alternative No. 1 No Action: no site remedial action taken.
- Alternative No. 2 Limited Action: remedial action consists of grading, revegetation, fencing and institutional restrictions for the site.
- > Alternative No. 3 Capping: both source areas would be left in place and covered with a multi-layered cap.
- Alternative No. 4 Oppradient Drains: the source areas would be left in place, covered with a multi-layer cap and upgradient groundwater drains constructed.
- Alternative No. 5 Perimeter Drains: source areas would be left in place, covered with a sulti-layer cap and appradient and downgradient groundwater drains constructed.
- Alternative No. 6 Partial Memoval: a cap and perimeter drains would be constructed around the sludge mound, the main pit and barral mound would be excavated, the wastes treated, as needed, and disposed of in an on-site compliant NOW landfill.
- Alternative No. 7 On-site Disposal: both source areas would be excavated, the wastes treated, as needed, and disposed of in an onsite RCRA compliant landfill.
- Alternative No. 8 On-site Incineration and Disposal: both source areas would be excavated, the wastes incinerated on-site and disposed of in an on-site RCRA compliant landfill.
- Alternative No. 9 On-site Incineration/Off-site Disposal: source areas would be excavated, the wastes incinerated on site and disposed of in an off-site RCRA compliant landfill.
- > Alternative No. 10 Off-site Disposal: both source areas would be excavated, the wastes treated on-site to meet landfill criteria and transported to an off-site RCPA compliant landfill.
- Alternative No. 11 Off-site Incineration: both source areas would be excevated and the amjority of the wastes transported to an offsite incinerator for incineration and disposal.
- Off-site incineration was assumed in some cases for cost-estimating purposes. This does not reflect a final decision to use off-site disposal facilities for any waste from the Hardage site.



ypper mumber represents upper-bound condition, biddle number represents babe condition, Lower mumber represents Lower-round condition.

145

FIGURE 5: AR0001865

Costs and sensitivity ranges for source control remedial alternatives

{Hardane/Cetee- no-

reasonable depth with sufficient integrity to provide a natural base to any engineered containment system. Further discussion of these capping-in-place or in-situ containment technologies and the rationale for their rejection is presented in both the Source Control FS and the Responsiveness Summary (Appendix C).

Consideration of the cap and drain alternative revealed the presence of the same flaws as existed in other plans for containing wastes. The drains were first considered to a depth of five feet below the present groundwater surface. However, migration has been observed to over thirty feet below the water table, indicating that interception substantially deeper than five feet would be necessary to provide meaningful reductions in the releases now occuring. In addition, free liquids present in the landfill and in drums which will continue to deteriorate and burst would be released and allowed to migrate vertically until the source was exhausted. The plan involving shallow (five foot) trenches was estimated to cost \$35-40 million. Extensive and continous operation and maintanence (O & M) for the indefinite future would be necessary to maintain the collection system. It was estimated that for collection rates greater than 0.5 gallons per minute, economics would indicate construction of an on-site treatment plant. The problems associated with operating such a system for the indefinite future, meeting discharge requirements and handling occasional peak flows could be significant. In addition, there is no method for assuring the longterm operation of such a treatment system.

The continued release of hazardous wastes and hazardous substances with only negligible lateral interception and no vertical interception, the need for indefinite 0 å M when such cannot be assured, the potential for continued off-site impacts, and the entire "band-aid" type of approach that this, the most viable in-situ containment alternative entails is wholly inadequate to meet the objective of CERCLA and the directive of the NCP to provide a permanent remedy meeting or exceeding applicable or relevant and appropriate Federal public health and environmental requiremnts.

-As a result, closure in place was rejected as being incapable of containing wastes in the immediate vicinity of the site and unacceptable as a permanent source control remedy.

5.2) Alternative 7 - On Site Disposal:

The source areas (drum mound, main pit, and sludge mound) would be excavated. Solids would be treated and disposed in a landfill cell constructed on-site. Liquids would generally be incinerated. After completion, the landfill would be closed with a multi-layer cap and gas venting system. The Remedial Action (RA) would require about 18 months to complete at a present worth cost of \$70 million (Table 2).

TABLE 2: ALTERNATIVE NO. 7--ON-SITE DISPOSAL

ITEM GENERAL	COST \$ 1,800,000
EXCAVATION, SEPARATION, SAMPLING	\$12,979,000
TREAT AND TRANSPORT DRUMMED WASTES	\$ 5,450,000
. DN-SITE DISPOSAL	\$12,789,000
SITE RESTORATION	\$ 196,000
EVAPORATION/COLLECTION POND FOR SURFACE WATER	\$ 280,000
SURFACE WATER TRANSPORTATION, TREATMENT AND DISPOSAL	\$ 5,403,000
OTHER PROVISIONS	\$ 249,000
Construction Subtotal	\$39,146,000
Bid Contingencies (15%)	\$ 5,872,000
Scope Contingencies (20%)	\$ 7,829,000
Construction Total	\$52,847,000
Permitting and Legal (7%)	\$ 3,699,000
Services During Construction (10%) Total Implementation Costs	\$ 5,285,000 \$61,831,000
Engineering Design Costs (10%)	\$ 6,183,000
TOTAL CAPITAL COSTS	\$68,014,000
OPERATION AND MAINTENANCE (Present Worth)	\$ 1,690,000
Bid Contingencies for Operation and Maintenance (15%)	\$ 254,000
Scope Contingencies for Operation and Maintenance (20%)	\$ 338,000
TOTAL OPERATION AND MAINTENANCE (PRESENT WORTH)	\$ 2,282,000
TOTAL PRESENT WORTH	\$70,296,000
 Off-site incineration was assumed for cost-estimating purposes. This does not reflect a final decision to use off-site disposal facilities for any waste from the Hardage site. 	/ * 0 0 0 1 × 0

150001867

5.3) Alternative 8 - On Site Incineration and Disposal:

The source areas would be excavated. Wastes would be incinerated in a kiln constructed on-site. Ash would still contain metals and, until proven otherwise through de-listing, would require disposal as a hazardous waste. Disposal would be in a landfill cell constructed on-site. This alternative would require four to eight years to implement at an estimated present worth cost of \$326 million (Table 3).

5.4) Alternative 9 - On Site Incineration and Off Site Disposal:

The source areas would be excavated and wastes incinerated as above. The difference between this and Alternative 8 would be the off-site disposal of incinerator ash. This alternative would require four to eight years to implement at a cost of \$374 million (Table 4). Future 0 & M for this source control remedy would be non-existent.

5.5) Alternative 10 - Off Site Disposal:

The source areas would be excavated; and wastes would be transported off-site to existing Treatment Storage and Disposal (TSD) facilities for landfilling, incineration, reuse/recycling, or other treatment as appropriate. This alternative could be implemented in about 2 years at an estimated present worth cost of \$133 million (Table 5). As with alternative 9, 0 & M would be non-existent.

6.0) SELECTED ALTERNATIVE:

Alternative 7 (On-Site Disposal) is selected as the appropriate remedy for source control at the Hardage/Criner site. The process by which this alternative was chosen over the other three under consideration is outlined below.

6.1) Remedial alternative selection procedure:

EPA is required by Section 300.68(i) of the NCP to determine the appropriate extent of remedy by, "Selection of a cost-effective remedial alternative that effectively mitigates and minimizes threats to and provides adequate protection of public health and welfare and the environment". The NCP goes on to state that the selected remedy will attain or exceed applicable or relevant and appropriate Federal environmental and public health requirements. EPA has a sidered the cost, technology, reliability, administrative and other concerns in selecting Alternative 7 as the appropriate remedy, as documented below. These considerations have only been applied to alternatives meeting or exceeding the above noted requirements.

TABLE 3:

ALTERNATIVE NO. 8--ON-SITE INCINERATION AND DISPOSA

l	ITEM GENERAL	COST \$ 7,352,000
	EXCAVATION, SEPARATION, SAMPLING	\$ 12,979,000
e .	ON-SITE INCINERATION OF WASTE FILL	\$130,500,000
8	TREAT AND TRANSPORT DRUMMED WASTES	\$ 2,916,000
E	ON-SITE DISPOSAL	\$ 10,175,000
_	SITE RESTORATION	\$ 196,000
	EVAPORATION/COLLECTION POND FOR SURFACE WATER	\$ 310,000
	SURFACE WATER TRANSPORTATION, TREATMENT AND DISPOSAL	\$ 21,611,000
	OTHER PROVISIONS Construction Subtotal	\$ 249,000 \$186,288,000
{	Bid Contingencies (15%) Scope Contingencies (20%)	\$ 27,943,000 \$ 37,258,000
(Construction Total Permitting and Legal (7%) Services During Construction (10%) Total Implementation Costs	\$251,489,000 \$ 17,604,000 \$ 25,149,000 \$294,242,000
F.	Engineering Design Costs (10%) TOTAL CAPITAL COSTS	\$ 29,424,000 \$323,666,000
	OPERATION AND MAINTENANCE (Present Worth)	\$ 1,384,000
	Bid Contingencies for Operation and Maintenance (15%)	\$ 208,000
L	Scope Contingencies for Operation and Maintenance (20%)	\$ 277,000
<u>-</u>	TOTAL OPERATION FID MAINTENANCE COSTS (PRESENT WORTE)	\$ 1,869,000
i	TOTAL PRESENT WOP"H	\$325,535,000
i		

Off-site incineration was assumed or cost-estimating purposes.

This does not reflect a final deci ion to use off-site disposal facilities for any waste from the ardage site.

TABLE 4:

ALTERNATIVE NO. 9--ON-SITE INCINERATION/OFF-SITE DIS

ITEM	COST
GENERAL	\$ 7,928,00
EXCAVATION, SEPARATION, SAMPLING	\$ 12,979,000
ON-SITE INCINERATION OF WASTE FILL Design, Construction and Operation	\$130,500,000
TREAT AND TRANSPORT DRUMMED WASTES	\$ 3,788,000
WASTE FILL REMOVAL TO OFF-SITE LANDFILL	\$ 16,958,00C
OFF-SITE LANDFILL DISPOSAL CHARGES	\$ 20,850,000
SITE RESTORATION	\$ 196,000
EVAPORATION/COLLECTION POND FOR SURFACE WATER	\$ 310,000
SURFACE WATER TRANSPORTATION, TREATMENT AND DISPOSAL Construction Subtotal	\$ 21,611,000 \$215,120,000
Bid Contingencies (15%)	\$ 32,268,000
Scope Contingencies (20%)	\$ 43,024,000
Construction Total Permitting and Legal (7%) Services During Construction (10%) Total Implementation Costs Engineering Design Costs (10%) TOTAL CAPITAL COSTS	\$290,412,000 \$20,329,000 \$29,041,000 \$339,782,000 \$33,978,000 \$373,760,000
OPERATION AND MAINTENANCE	\$ 0
(Present Worth) Bid Contingencies for Operation and Maintenance (15%) Scope Contingencies for Operation and Maintenance (20%) TOTAL OPERATION AND MAINTENANCE COSTS (PRESENT WORTH)	\$0 \$0 \$0
TOTAL PRESENT WORTH	\$373,760,000

TABLE 5:

ALTERNATIVE NO. 10--OFF-SITE DISPOSAL

ITEM GENERAL	COST \$ 2,538,00
EXCAVATION, SEPARATION, SAMPLING	\$ 12,979,0C
TREAT AND TRANSPORT DRUMMED WASTES	\$ 7,584,00
WASTE FILL REMOVAL TO OFF-SITE LANDFILL	\$ 21,228,00
OFF-SITE LANDFILL DISPOSAL CHARGES	\$ 26,100,00
SITE RESTORATION	\$ 196,000
EVAPORATION/COLLECTION POND FOR SURFACE WATER	\$ 280,00C
SURFACE WATER TRANSPORTATION, TREATMENT AND DISPOSAL Construction Subtotal	\$ 5,403,000 \$ 76,308,000
Bid Contingencies (15%) Scope Contingencies (20%) Construction Total Permitting and Legal (7%) Services During Construction (10%) Total Implementation Costs	\$ 11,446,000 \$ 15,262,000 \$103,016,000 \$ 7,211,000 \$ 10,302,000 \$120,529,000
Engineering Design Costs (10%) TOTAL CAPITAL COSTS OPERATION AND MAINTENANCE (Present Worth)	\$ 12,053,000 \$132,582,000 \$0
Bid Contingencies for Operation and Maintenance (15%)	\$ 0
Scope Contingencies for Operation and Maintenance (20%)	\$0
TOTAL OPERATION AND MAINTENANCE COSTS (PRESENT WORTH)	\$0
TOTAL PRESENT WORTH	\$132,582,000

6.1.1) Comparison of on-site versus off-site remedial action alternatives:

Two alternatives, 7 and 8, involve on-site disposal of wastes excavated from source areas. Alternatives 9 and 10 entail complete off-site disposal of wastes. The alternatives 7 and 10 involve essentially the same operations (i.e. excavation with limited incineration and landfilling for the bulk of wastes), except that they are on and off-site variations of basically the same alternative. Similarly, alternatives 8 and 9 are basically on and off-site disposal options for residue from the on-site incinerator. Based on this point, the analysis below compares on-site to off-site disposal.

Cost: The cost of off-site landfilling and incineration alternatives exceed their on-site counterparts by 90% (\$63 million) and 15% (\$48 million) respectively.

Technology: The on and off-site options will be virtually identical in the treatment and disposal technologies employed. Control of the quality of work done under the on-site alternatives may be somewhat superior in this respect however, since these actions would be conducted under EPA oversight and off-site treatment or disposal would not.

Reliability: The off-site disposal options will provide reliability in preventing releases from this site, simply because wastes would not remain on-site. However, off-site disposal has the potential to increase health risks at other sites. It is not certain that any significant advantage exists in reliability of off-site over on-site disposal locations. The Hardage/Criner facility is in compliance with the siting requirements currently governing location of commercial disposal facilities. For this reason, any particular vulnerabilities which are present on the Hardage site would not necessarily be absent at off-site facilities.

Administrative: Each alternative will comply with RCRA Part 264 requirements, long-term objectives of CERCLA as amended, and all applicable or relevant and appropriate requirements for protection of public health and welfare and the environment. Since wastes will be left on-site, the remedial action will be reviewed every five years after it's completion, as required by the Superfund Amendments and Reauthorization Act of 1986 (SARA), to assure that the remedy is still protecting public health and the environment.

Other concerns: (Safety during implementation) Both on and off-site alternatives carry inherent risks during excavation. As discussed later, these impacts can be controlled. The primary difference between the on and off-site alternatives with respect to safety during implementation is the potential for accidents

or spills during off-site transport of the wastes. For example, an estimated 11,000 loads would be required to transport the entire 180,000 cubic yards of waste off-site. For the 400 to 800 mile transport distance assumed in the FS, trucks carrying waste from the Hardage site would be on the road from four to eight million miles.

Consideration of the components of the four remedial action alternatives evaluated shows that the key difference is the presence of an on-site landfill under the two on-site alternatives. Information collected to date indicates that an adequate landfill cell could be constructed on-site and successfully maintained. The site meets RCRA Section 264.1B siting requirements for seismic stability and flooding potential. Due to the hazards and costs arising from off-site disposal and transport, clear and significant benefits should be present before off-site disposal is selected. Those benefits are not significant or certain in this case. While such benefits may exist in the off-site treatment of small to moderate quantities of specific wastes, organic liquids may be an example, off-site disposal for the entire waste quantity is not preferred over on-site management of wastes in this case. Therefore, the off-site alternatives are eliminated from consideration, and the on-site disposal alternatives (7 - On-site disposal; 8 - On-site incineration and disposal) will be carried on for further evaluation.

6.1.2) Comparison of the two on-site alternatives:

Cost: Alternative 7 would cost \$39-109 million to implement, with the most likely cost being \$70 million. Alternative 8 would cost \$171-495 million, the likely figure being \$326 million. Therefore, the benefits to be derived from incineration of all waste would come at a cost of 470% (\$256 million) greater than landfilling.

Technology: Incineration is a key component of both alternatives 7 and 8. Since some wastes are liquids which cannot be landfilled, the decision to incinerate organic liquids is appropriate.

Incineration of all wastes will have the net benefit of destroying virtually all organic materials. Even with incineration however, heavy metals will still be present in the residue. These materials simply cannot be destroyed. The mobility can be reduced by treating the waste to reduce it's acidity; this would be done under either alternative.

Reliability: By incineration, virtually all organics are destroyed, leaving an ash with varying contents of heavy metals requiring stabilization and disposal as a "characteristic" hazardous waste. The landfilling alternative, with limited incineration, removes only the free organic liquids with the greatest potential for penetrating a landfill liner and moving into the environment.

Landfilling and incineration of liquids are established technologies, with a demonstrated ability to perform under similar conditions. Incineration of soils contaminated by a heterogenous mixture of wastes, while feasible, has not yet been attempted on a scale such as would be required for complete incineration at the Hardage site.

Administrative: Both alternatives would meet all aplicable or relevant and appropriate requirements for protection of public health and welfare and the environment. Since wastes would be left on-site, the remedial actions would have to be reviewed every five years as required under Section 121 of SARA.

Other concerns: (time to implement) Landfilling can be accomplished in 12 to 18 months. Incineration will take four to eight years.


Based on the factors considered above, Alternative 7 (On-site landfill with liquids incineration) is selected as the appropriate remedy for the Hardage/Criner site. This alternative will provide a degree of protection to public health and welfare and the environment similar to that which could be achieved with complete incineration. This remedy can also be carried out in a shorter time using proven technologies which are currently in wide-spread application.

6.2) Detailed Description of the Recommended Alternative:

The following is a general sequence of operations and construction activities required to implement on-site disposal for a source control remedy at the Hardage/Criner site. The timing and specifications will be developed in detail during the Remedial Design (RD) phase of response.

A landfill cell will be constructed to meet the minimum technology requirements for hazardous waste landfills as set forth in RCRA Section 264.301. The key feature of such a landfill cell is a double liner system with interior leachate monitoring and collection (Figure 6). The landfill will be constructed above grade on the high ground west and north of the present source areas, as indicated in the FS. If at all possible, construction of the landfill cell over significant residual contamination will be avoided. The exact siting of the landfill cell will be based on the results of surface soil sampling during the second unit RI, consideration of topography and hydrology of the site, and possibly additional geotechnical data collected during the RD. Sufficient land is available on which to site a landfill cell.

The sludge mound, main pit, and drum mound will be excavated. This represents a volume of approximately 180,000 cubic yards, and includes in excess of 10,000 to 20,000 unemptied drums. For this operable unit, the vertical extent of waste excavation will be to the upper surface of undisturbed bedrock (see Section 6.3 - Clean-up levels).



After waste excavation, treatment, and disposal (described below), the empty waste pits and bedrock now underlying the waste piles will still remain. This upper bedrock surface is believed to be saturated with waste seepage to an unknown depth. Such residual contamination will generally not be removed during the source control remedial action, since the appropriate extent of vertical excavation cannot yet be defined. In order to prevent contamination of surface runoff waters and to eliminate direct contact exposure hazards from open areas of residual waste, it will be necessary to construct a protective temporary cap over the former source areas. This temporary cap will serve the dual purposes of preventing direct rainfall from leaching the contaminated bedrock and eliminating direct contact hazards. The cap will be constructed so as to achieve these goals and at the same time be of a design to allow upgrading to meet relevant and appropriate RCRA closure standards should it be determined by the second operable unit RI/FS that closure in-place is an appropriate permanent remedy for residual contamination beneath the former source areas. Considering the relative times required for design of the source control remedy and conduct of the management of migration RI/FS, it is possible that final clean-up levels will have been developed for the site prior to waste excavation. If such clean-up levels are available, the interim cap would be unnecessary and remedial action for residual contamination in the bedrock beneath the former source areas can proceed directly from excavation of the source areas.

Since wastes excavated in the source areas will range in consistency from dry solids to relatively pure liquids, and since the appropriate means of waste treatment and disposal is in large part determined by the physical consistency of the material, it is clear that criteria will have to be developed during the RD which allow segregation of: liquids for incineration or other treatment, solids whose moisture content is appropriate for landfilling, and solids requiring moisture reduction prior to landfilling.

Liquids will be defined by the relevant and appropriate RCRA testing procedures (currently the Paint Filter Test) which are effective at the time the remedial design is approved. Liquds will be segragated based on their chemical make-up (i.e. organic versus inorganic as described in the FS). The RD will develop criteria for making this distinction.

Solids, as defined by testing procedures noted in the above paragraph, will be randled in a manner based on decisions made in a moisture content valuation, described below under Section 6.2.3. Based on the criteria developed there, wastes will have to have to fall below an upper limit on moisture content, after treatment, before they can be disposed in the landfill, provided other requirements, such as land

disposal bans, do not preclude their placement in the landfill. Based on the determinations and criteria from the RD, the wastes will be treated and disposed as indicated in the general schematic shown in Figure 7. Discussion of waste treatment and disposal is provided below.

Treatment of organic liquids: These liquids will be incinerated. Based on the economics of the volume of materials encountered, this would be done either at an off-site facility or on-site with a portable or modular incinerator.


Treatment of inorganic liquids: Based on the economics of the volume and character of the liquids encountered, treatment and disposal may be done either on or off-site. On site treatment would generally be through physiochemical methods capable of removing both organics and metals, to allow discharge under an NPDES permit or transport to a publicly owned treatment works. If off-site treatment is selected, either deep well injection or treatment at a commercial facility would be available.

Treatment of Solids: Solids will ultimately be placed in the landfill cell constructed on-site. Prior to disposal, the wastes will be subjected to treatment aimed at reducing their toxicity and mobility. Since a large volume of contaminated soil is present, significant volume reduction would not be possible. Such treatment may include addition of materials to stabilize the fill or physiochemical treatment designed to remove or alter specific hazardous constituents or classes of compounds. Treatment technologies identified are:

- ° chemical neutralization (pH adjustment),
- * solidification by addition of lime, cement, fly ash, or other proprietary agents,
- ° reduction of liquid content,
- ° chemical oxidation or reduction, and
- ° air stripping to remove volatiles.

Other a ternative treatment technologies identified during the remedial design will also be considered for application, and those technologies showing promise for the specific wastes and situations at the randage site will be evaluated further through bench tests or pilot studies as appropriate

During the remedial design, an evaluation including bench testing will be conducted to determine an appropriate upper limit on the moisture content of fill which could be placed in the on-site land-fill. This evaluation will consider the potential composition of pore file ds in the waste, the reaction of various soil/fluid combinations and the type of triaxial stresses to be expected within the



landfill, the potential for long and short-term leachate generation, and the effects of such leachate on various liner systems proposed for the landfill cell. Based on the results of this evaluation, an upper limit will be imposed on the moisture content of wastes which can be disposed in the landfill. Wastes placed in the landfill will in no case be of the type which:

- a) would be classified as "liquids" by applicable or relevant and appropriate testing procedures pursuant to the RCRA prohibition on the disposal of liquids in landfills; or
- b) are the subject of any land disposal bans under the Hazardous and Solid Waste Amendments to RCRA or the Toxic Substances Control Act which are determined to be applicable or relevant and appropriate.

Treatment technologies will be further refined during the RD phase; and additional design data may be required. The variability of wastes present in the source areas precludes any extensive characterization of wastes prior to excavation. For this reason, final determinations on appropriate treatment will in some cases have to be made during the RA itself.

6.3) Clean-up Levels for the Source Control Operable Unit:

Selection of clean-up levels will be a concern of the second operable unit (Management of Migration). Ultimately, clean-up levels will have to be selected for the base of the pits and for surface soils on-site. In the pit areas, the criteria will generally include potential for migration of metals and organics which have already migrated out of the pits. The surface soil criteria will focus on metals, PCBs, and pesticides due to their persistence in the environment, direct contact exposure hazards, and potential to contaminate surface runoff.

The Source Control operable unit deals exclusively with the concentrated pits and piles of wastes. In this case, selections of compounds of concern and selection of clean-up levels based on soil concentrations of these compounds is not appropriate. The criteria to be used for determining the extent of clean-up will be the surface of undisturbed bedrock. If, at that point in the RA, additional data from the second operable unit RI/FS or the Source Control RD has allowed determination of a first clean-up level, then excavation, in-situ treatment, or permanent capping may be implemented for the residual contaminants. If such data is not available, a temporary cap will be installed over the excavated areas pending second operable unit remedy definination.

6.4) Health and Safety Concerns During Implementation

Excavation of the waste piles and pits will pose hazards to workers via air and direct contact in addition to the physical hazards normally associated with such construction. In many cases the waste excavation and handling will have to be conducted under Level B protection (containerized air and protective clothing) to mimize hazards to the workers. Air release of volatile organics will likely increase during waste excavation. Continuous monitoring of air around working areas, at the site perimeter, and near offsite homes will allow identification of health threats to off-site residents and prevent problems from going undetected. Dust and vapor suppression measures, maintenance of a small working face of exposed waste, and possible use of a temporary structure over the excavation will help to minimize air releases.

Runoff retention structures and emergency holding ponds will be used to prevent chronic or sudden releases during construction.

7.0) COMPLIANCE OF REMEDIAL ACTION WITH APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS FOR PROTECTION OF PUBLIC HEALTH AND THE ENVIRONMENT

Section 300.68(i) of the NCP directs that EPA will, except in narrow cases such as "fund-balancing", select a remedy that "attains or exceeds applicable or relevant and appropriate Federal public health and environmental requirements that have been identified for the specific site." These applicable or relevant and appropriate requirements (hereinafter "Requirements") are discussed in an October 2, 1985 memorandum from Winston Porter, Assistant Administrator for EPA's Office of Solid Waste and Emergency Response, "CERCLA Compliance with Other Environmental Statutes", which is set forth in the preamble to the NCP at 50 Fed. Reg. 47912, 47946 (November 20, 1985).

The principal requirements and policies to be considered during conduct of the RA will be as follows:

7.1) RCRA Subtitle C Permit Requirements, 40 CFR Part 264:

E

While not deemed applicable to the site since it closed prior to November 19, 1980, these requirements are considered to be relevant and appropriate to this CERCLA response action to the extent indicated below. Leaving engineering considerations aside, the Part 264 permit requirements are considered appropriate rather than the Part 265 interim status requirements. The facility closed prior to the effective date of interim status, rather than attempt to comply with these standards. Royal Hardage notified EPA of hazarchus waste activity under RCRA in August 1980, but withdrew the notification in November 1980 and did not file Part A of the RCRA permit application, most likely because the site could not have me those

standards without bankrupting the facility. As indicated previously, wastes were disposed haphazardly in unlined pits and the treatment, storage, and disposal of hazardous wastes at the facility as far below the standards required for interim status facilities. Indeed, EPA filed a lawsuit seeking clean up and closure of the facility under RCRA, Section 7003 in U.S. District Court in Oklahoma City on September 8, 1980. EPA has conclusive and demonstrable evidence of releases of hazardous wastes and hazardous substances from the disposal units of the Hardage site. Given this situation, the most appropriate Federal environmental requirements to apply to the source control action, which is consistent with and forms a substantial increment of a permanent site remedy, would be the Part 264 requirements, applicable to new facilities, along with their more stringent closure requirements.

Additionally, EPA-believes that the physical nature of the site, it's hydrology, and underlying geologic conditions dictate that the waste materials not be left in-place. Accordingly, it is clear that the Part 264 permitting and closure requirements should be applied to the construction and closure of new disposal units necessary for this facility.

Finally, it should be noted that, as the preamble to the NCP states, "... although the Subtitle C regulations differ as to whether a hazardous waste facility has a RCRA permit (40 CFR Part 264) or is operating under interim status (40 CFR Part 265), remedies will generally have to be consistent with the more stringent Part 264 standards, even though a permitted facility is not involved. The Part 264 standards represent the ultimate RCRA compliance standards and are consistent with CERCLA's goals of long term protection of public health and welfare and environment." 50 Fed Reg at 47918.

7.1.1) Subpart B - Siting Requirements:

This will govern placement of the landfill cell on-site. The principal concerns stated in this subpart are seismic stability and flooding potential. Neither factor appears to be a major concern at the Hardage site; therefore, compliance does not seem to pose problems.

7.1.2) Subpart F - Groundwater:

This subpart will determine the extent to which the on-site landfill will be monitored. It will have a much wider application under the second operable unit.

7.1.3) Subpart G - Closure and Post-Closure:

These standards will apply to closure of the landfill cell(s) after completion of the source control RA. The remedy will comply with this subpart.

7.1.4) Subpart K - Surface Impoundments:

This will apply to any temporary impoundments constructed during the RA that treat, store, or dispose hazardous wastes. Impoundments will be lined, opearted, closed, and if necessary monitored in compliance with this subpart.

7.1.5) Subpart N - Landfills:

This subpart will govern construction and operation of the landfill cell. The landfill will meet requirements set forth for new landfills.

7.2) Toxic Substances Control Act:

This would come into application if PCBs are encountered at levels greater than 50 ppm, since such materials are banned from land disposal. In that case, alternative treatment would be required and implemented in order to comply with the Act.

7.3) EPA CERCLA Off-Site Policy (memorandum dated May 5, 1985; "Procedures for Planning and Implementing Off-site Response Actions"):

This policy will determine which TSD facilities are eligible for receipt of hazardous substances from the site. The policy generally requires a facility to be permitted and have no significant RCRA violations or conditions affecting it's satisfactory operation. Prior to disposing or authorizing disposal of wastes from this site the Region will contact the State in which the facility is located, review the facility's record of operation, and if appropriate contact other Regional offices of EPA where the facilities may be located to evaluate compliance with this policy. No wastes will be disposed at any site not meeting the criteria set forth in the policy.

7.4) Occupational Safety and Health Standards (29 CFR Part 1910):

These standards will be applied during remedial actions to protect workers from exposure to hazardous substances and other physical hazards associated with implementation of the RA. Methods for assuring the safety of workers involved in the RA will be devloped and described in a "Site Safety Plan" developed as part of the Remedial Design.

7.4) Hazardous and Solid Waste Amendments to RCRA of 1984:

The Hazardous and Solid Waste Amendments to RCRA of November 1984 (HSWA), 42 U.S.C. 6901 et seq. contain provisions setting several statutory dates for banning land disposal of hazardous wastes The provisions discussed here are RCRA Section 3004 (d)(e) and (g), due to the possible intersection of their statutory deadlines with the construction schedule for a source control remedy at the Hardage site.

The HSWA land disposal amendments are in fact not yet applicable or effective Federal requirements with respect to CERCLA Section 104 or 106 response actions, since their implementation dates are still some time off in the future. The bans found in subsection (g) are to be implemented during three periods over 21 months for 1/3, 2/3, and finally all of the RCRA subtitle C "listed" hazardous wastes commencing August 8, 1988, as determined by EPA. Those determinations will be made by rulemaking. See 50 Fed. Reg. 19300 (May 28, 1986) for the list of wastes to be considered.

The statutory ban on the "California List" wastes and solvents in subsections (d) and (e) and the prospective bans laws of subsection (g) are not considered relevant and appropriate at this time, since their applicability to CERCLA waste disposal is in the future. The effect of the bans in subsection (g) on the remedy is speculative at best, since EPA is required to engage in rulemaking for methods of land disposal and pretreatment for such disposal, 42 U.S.C. 6924 (g)(5) and (m). Futhermore, it must be emphasized that CERCLA requires the selection of cost-effective remedies and does not require EPA to implement standards that are not in effect.

During the course of remedial action and construction, EPA intends to further review the effect of land disposal bans on waste disposal at the site and the issues of how such laws will be implemented should they intersect the construction schedule. Additionally, bench tests and/or pilot studies may be performed with respect to pre-treatment methods for solvents and other organics potentially impacted by such bans.

8.0) OPERATION AND MAINTENANCE

1

The on-site landfill will require little routine operation and maintenance (0 & M). Monitoring of the interior leachate detection system will be required, as will periodic inspections of the cap and monitoring of gases leaving the venting system. Development and routine sampling of a groundwater monitoring network will also be necessary for 30 years, at which time the need for additional monitoring will be reevaluated.

To provide a contingency in project cost estimates, it was assumed that at 30 years after construction replacement of the landfill liner and cap might be necessary. The cost is reflected in the present worth cost estimate of \$70 million. Operation and maintanence costs on a present worth basis are estimated as \$2,282,000 in 1985 dollars.

- 9.0) COMPLIANCE OF SOURCE CONTROL REMEDIAL ACTION WITH SECTION 121 OF THE SUPERFUND AMENDMENTS AND REAUTHORIZATION ACT OF 1986 (SARA) TO THE MAXIMUM EXTENT PRACTICABLE
- 9.1) Basic Certification:

The selected remedy will comply with Section 121 of the Comprehensive Environmental Response, Compensation and Liability Act of 1980 (CERCLA), as amended by SARA, including the cleanup standards thereof, to the maximum extent practicable. The selected remedy is considered to be cost effective and protective of human health and the environment as well, in accordance with the NCP.

9.2) Permanent Solutions and Technologies

In selecting this remedy, EPA has considered a full range of alternatives and solutions and alternative treatment technologies that will result in a permanent and significant decrease in toxicity, mobility, or volume of the hazardous substances present. In conducting its assessments of remedial alternatives and treatment technologies, EPA has considered:

- 1) The long term uncertainties of land disposal;
- 2) goals and requirements of the Solid Waste Disposal Act ("RCRA");
- 3) persistence, toxicity, mobility and bioaccumulation potential of the wastes:
- 4) short and long term potential for adverse human health effects;
- 5) long term maintenance costs of the remedy;
- 6) potential for future remedial actions costs if the remedy fails;
- potential threat to human health and the environment from the excavation, transportation, and redisposal, or containment of hazardous substances.
- 9.3) Remedy Analysis:

The selected remedy is a remedy for the first operable unit of remediation - source control. It is a significant part of overall remediation at the Hardage site and is consistent with a permanent remedy for the site. The second operable unit, "management of migration", is now under development.

This remedy will employ treatment through incineration of all free liquid organics in the estimated 175,000 cubic yards of waste fill, as well as the more than 18,000 estimated drums of waste buried on-site. Remaining waste fill and inorganic solid drum contents will be treated through stabilization measures prior to redisposal in a double lined on-site RCRA compliant landfill cell. In carrying out these measures, EPA will be permanently and significantly reducing the volume, toxicity, and mobility of the hazardous substances present at the Hardage site. Further, EPA will avoid in large measure the potential dangers and uncertainties of transport and disposal off-site, with its on-site approach for the bulk of wastes. EPA requires that this source control remedy be reviewed not less than every five years to assure that human health and the environment are being protected.

As noted previousTy, in Section 7 herein, EPA has scrupulously considered the applicable or relevant and appropriate federal requirements for protection of public health and the environment in accordance with the NCP. EPA has also looked into the issue of applicable or relevant and appropriate state environmental laws and has determined that the "RCRA analogous" regulatory requirements of the Oklahoma Controlled Industrial Waste Disposal Act, as amended, authorized by EPA under RCRA to operate in lieu of the EPA regulations, are met or exceeded by the selected remedy. In a nutshell, EPA has complied with the SARA Section 121 cleanup standards to the maximum extent practicable.

10.0) OTHER OPERABLE UNITS

EPA's response actions on the Hardage/Criner have been divided into two operable units: Source Control (the remedy discussed in this document) and Management of Migration (also referred to as the groundwater/off-site operable unit).

The source control response is limited to the source areas of the site (sludge mound, main pit, and drum mound). The bases of the main pit and southern pit (beneath the sludge mound) at approximate elevations of 1109 and 1093 feet MSL respectively form the lower bound of the source areas. The lateral bounds of the source areas are described by the base of the slopes on the north, south, and west faces of the waste piles and pits, and as the lateral extent of the excavated pits on those sides of the source areas where wastes and cover have been backfilled to ground level.

The management of migration RI/FS will include the following:

- Definition of the extent and levels of contamination present in soils and rock outside the source area;
- determination of the extent and fate of groundwater contamination in the alluvium of North Criner Creek and the feasibility and need for remedial actions in the alluvial valley;

determination of permanent surface clean-up levels on-site to prevent or minimize further degradation of potential surface and ground water supplies, direct contact hazards to the public, and other long term hazards.

11.0) ENFORCEMENT

11.1) Hardage 1:

In 1979, EPA inspections of the site indicated poor waste management practices posing potential threats to public health and welfare and the environment. In September 1980, the U.S. Department of Justice (DOJ) filed a complaint on behalf of EPA in U.S. District Court in Oklahoma City, Oklahoma. The complaint alleged violations of Section 7003 of RCRA and sought proper cleanup and closure of the site. The facility had ceased operations in early November 1980, before RCRA Interim Status Standards came into effect.

In 1982, DOJ and EPA amended the existing complaint against the facility owner and operator Royal Hardage. The complaint was changed to include allegations and requested relief under Sections 106 and 107 of the Comprehensive Environmental Response Compensation and Liability Act (CERCLA). In December 1982, the Court found that the site posed an imminent and substantial endangerment to public health and welfare and the environment as defined by CERCLA Section 106 and RCRA Section 7003. In August 1983, the Court granted a partial judgment for over \$211,000 in response costs, which EPA had incurred through 1982, against Royal Hardage.

Hardage filed for Dankruptcy in 1983 and again in 1985, and EPA has never recovered its partial judgment.

11.2) Hardage II

EPA compiled available records from the sites operations including daily and monthly site logs of wastes received, waste manifests, and disposal plans and records filed with the State of Oklahoma by generators and transporters of waste to the site.

As a result numerous Potentially Responsible Parties (PRPs) were identified. In December 1984, EPA mailed letters to 289 of these PRPs requesting information about their waste disposal at the Hardage site of authority of Section 104(e) of CERCLA and Section 3007 of RCRA of inotifying the PRPs of their potential liability for site clear p. As further information was gained, information request and notice letters were sent to additional PRPs identified. At the presenting, over 400 PRPs have been identified. Various PRPs have gondut of business or cannot be located; therefore, approximately to have been contacted. A number of these parties, not the Hardage Steering Committee (HSC). The HSC has met with 1 and OSDH on numerous occasions since EPA's first PRP meeting concerting the site in January 1985.

457100034

Since the FS was on going at the time the PRPs were notified and CERCLA progam policy previously did not allow PRP conduct of R1/FS studies without a signed agreement to also implement the EPA selected remedy, the PRPs were not involved in preparation of the FS. In May 1985, EPA released the DSR documenting 1984 site investigations; and HSC also obtained all EPA files on the site. The HSC has retained Dames & Moore and more recently ERM-Southwest to provide technical support in their dealings with EPA.

In July 1985 the Court administratively closed the 1980 case against Hardage, providing that the U.S. could re-open the case for the purpose of seeking appropriate relief until April 1, 1986, at which time the case would otherwise be dismissed. DOJ, on behalf of EPA, filed a motion on March 27, 1986, to amend the existing complaint and add generators and transporters to the existing case. The Court ultimately denied the motion and dismissed the case, providing that Royal Hardage could be named for limited purposes in a subsequent case.

On June 25, 1986, DOJ filed a new complaint naming 36 generators and transporters of waste at the site. The complaint asks for performance of the EPA selected source control remedy, maintenance of site security, conduct of a RI/FS for the management of migration operable unit and any subsequent EPA selected remedy, and recovery of EPAs' past and future response costs. A status conference was held on September 3, 1986, and a second status conference has been set for January 7, 1987.

12.0) COMMUNITY INVOLVEMENT

Due to the large number of PRPs for this site, the majority of meetings, comments on the FS, and other external communication has been with these parties, However, attention has been given to the concerns of near site residents and other interested parties.

When the draft FS was completed on February 20, 1986, a press release was issued announcing this fact, copies of the FS were placed in repositories, and a copy was provided directly to the Hardage Steering Committee. The public comment period was from March 10-April 15, 1986. A public meeting was held in Chickasha, Oklahoma to answer questions and receive comments on the FS on March 20. The response to questions, comments, and concerns raised during this period is contained in the Responsiveness Summary, Appendix C.

13.0 REFERENCES

- CH₂M Hill 1985
 Field Investigation and Data Summary Report, Royal Hardage
 Industrial Hazardous Waste Site, CH₂M Hill, May 22, 1985
- CH₂M Hill 1986a

 <u>Preliminary Public Health Assessment</u>, CH₂M Hill, August 1986
- CH_ZM Hill 1986b
 Source Control Feasibility Study, Royal Hardage Industrial
 Hazardous Waste Site, CH₂M Hill, February 20, 1986
- EPA 1985a

 Public Health Assessment Manual, EPA Office of Solid Waste and Emergency Response, November 1985
- EPA 1985b
 Guidance on Feasibility Studies Under CERCLA, EPA, June 1985
- EPA 1986

 Superfund Remedial Design and Remedial Action Guidance, EPA,
 June 1986
- Eltex 1985
 Letter from Eltex Chemical and Supply (Houston, Texas) to Stephen Phillips (EPA-Dallas), August 1985
- Hardage 1972-80
 Monthly waste site log of materials received at the Hardage site
- Kent 1982

 Evaluation of Hydrogeology at Royal Hardage Industrial Waste Site; Criner, Oklahoma, Douglas C. Kent, May 1983
- OSDH 1972
 Industrial-Hazardous waste landfill permit issued September 12, 1972 to Royal HJartdage by OSDH
- USGS 1966

 Base of Fresh Groundwater in Southern Oklahoma, D.L. Hart,
 United States Geological Survey Hydrologic Atlas 223, 1974

. - -

APPENDIX A

CHRONOLOGY OF EPA SITE INVESTIGATIONS
PRIOR TO 1984

AR0001355

A XICHAPPA

EPA Sampling and Inspections of Hardage/Criner prior to 1984:

June 27, 1979

Inspector:

Ralph Hawkins (EPA-Ada Branch) accompanied by Oklahoma

State and County Health Department personnel

Purpose:

NESHAPS inspection due to asbestos disposal

Result:

Recommended Sampling of site

Documentation:

7/3/79 memo, Hawkins to Charles Gazda (EPA-Dallas)

August 15, 1979

Inspector:

5.C. Yin (EPA - Ada Branch) with other EPA and State

Health Department personnel

Purpose:

Obtain samples and inspect site

Result:

Nine soil, water, and waste samples taken, analyzed for

metals and organics; photos taken

Documentation:

9/10/79 memo, Yin to Charles Gazda (EPA-Dallas)

10/26/79 memo William Langley (EPA-Houston Lab) to Oscar

Ramirez (EPA-Dallas) transmitting analytical results.

August 14, 1980

Inspector:

Thomas Smith of Ecology & Environment (FIT) for EPA

Purpose:

Off-Site sampling

Result:

Three samples taken from off-site drainage pathways;

analyzed for metals and organis; photos taken

Documentation:

8/21/80 memo T. Smith to Charles Gazda (EPA-Dallas); 9/23/80 memo William Langley (EPA-Houston Lab) to William

Librizzi (EPA-Dallas) transmitting analytical results

October 1, 1980

Inspector:

S.C. Yin (EPA-Ada Branch) with FIT personnel

∢ *

Purpose:

Off-site sampling

Result:

Thirteen (13) samples taken from off-site drainage and

domestic water wells, analysis for metals and organics,

photos taken

Documentation: 10/23/80 memo, Yin to William Librizzi (EPA-Dallas):

10/15/80 memo William Langley (EPA-Houston Lab) to

Librizzi transmitting analytical results

March 23 - April 8, 1982

Inspector: Imre Sekelyhidi (FIT) personnel and other FIT employees

for EPA

Purpose: Detailed on and off-site sampling of the site

Result:

3/23-24/82, 29 samples collected; 3/30-4/1/82, 6 domestic wells sampled 3/30-4/2/82, 10 monitoring wells drilled, by Shepard Testing and Engineering Co., Inc. of Norman, Oklahoma at locations directed by Jerry Thornhill (Hydrogeologist,

EPA-Ada Branch)

soil borings and monitoring well samples collected from

each new monitoring well

August 16, 1982

Ecology & Environment (FIT) for EPA Inspector:

Second sampling round for the wells drilled by FIT Purpose:

in March 1982

10 groundwater samples collected Result:

APPENDIX B

LIST OF POTENTIALLY RESPONSIBLE PARTIES

1DENTIFIED FOR THE HARDAGE/CRINER SITE

AL0001592

```
.... ......
       710 A BETTER SANITATION
       711 ABLE UNIFORM RENTAL
        712 ACME FENCE
       713 ADVANCE PACKAGING
       714
            AGLAND, INCORPORATED
            ALTEC SOUND PRODUCTS DIVISION
       715
       716
            AMERICAN AIRLINES, INCORPORATED
       717
             AMERICAN DISPOSAL SERVICE
            ATERICAN FARM LINES, INCORPORATED
       718
       719 AMERICAN FURNITURE STRIPPING
       720 AMERICAN TRAILERS, INCORPORATED
       721
            AMOCO PRODUCTION COMPANY & RESEARCH
       722 A-DNE BIT & TOOL COMPANY
       723 . ATLANTIC RICHFIELD COMPANY
       724 ARKANSAS BEST CORPORATION
       725 ARROW TANK TRUCK, INCORPORATED
       726 ARTHUR G. MCGEE AND COMPANY
       727 ASHLAND CHEMICAL COMPANY
       728 BALDN CORPORATION
       729 BEAUTY CRAFT TILE OF THE SOUTHWEST. INC.
       731 BINNEY I. STITH, INCORPORATED
       732 BOB MODRE DILWELL SERVICE
       733 BORDEN CHEMICAL DIVISION
       734 BRITTAIN BROTHERS (NAPA)
735 BROADWAY MACHINE & MOTOR SUPPLY
F
       736 BROWN AND ROOT, INCORPORATED
737 BROWNING-FERRIS INDUSTRIES, INCORPORATED
738 B.S. & S. ENGINEERING COMPANY
       739
            CAPITOL GREASE COMPANY
       740 CATO DIL & GREASE
            C. E. NATCO
       741
       742 CHARLES MACHINE WORKS, INCORPORATED
       743 CHROM ALLOY DIVISION
       744 CHROMIUM PLATING COMPANY
       745 CIMARRON MANUFACTURING COMPANY
       746 CITIES SERVICE DIL COMPANY
       747 CITY SERVICE
       748 CITY OF NORMAN
       749 CLAYTON PLATING COMPANY
       750 CLYDE'S CARFURETOR SERVICE
       751
            CMI CORPORATION
       752 COMPETITION AUTOMOTIVE
       753 CONDCO. INCORPORATED
       754 CONSOLIDATED CLEANING BERVICE COMPANY 755 CONTAINER CORPORATION OF AMERICA
       756 CORE LABORATORIES
        757 COUNTY HOME MEAT COMPANY
       758 CRANE CARRIER CORPORATION
       759 GROSBY GROUP, McKISSICK PRODUCTS DIV. 760 CROWL MACHINE & HEAT TREATING
        761 CROWN TRANSPORT COMPANY
        762 DAL-WORTH INDUSTRY, INCORPORATED
        7£3
            DAYTON TIRE & RUBBER COMPANY
            DEL PAINT MANUFACTURING
        764
            DELTA FAUCET COMPANY
        765
        766 DELTA TRANSMISSION
```

THIS LIST REPRESENTS EPA'S PRELIMINARY FINDINGS ON THE IDENTITIES OF POTENTIALLY RESPONSIBLE PARTIES. INCLUSION ON THIS LIST DOES NOT CONSTITUTE A FINAL DETEMINATION CONCERNING THE LIABILITY OF ANY PARTY FOR THE HAZARD OR CONTAMINATION AT THE HARDAGE SITE

AR0001993

```
DESCIP, INCURRURMIED
       789 DESOTA, INCORPORATED
       770 DOUBLE EAGLE REFINING LUBRICANTS, INC.
           DOVER CORPORATION
       771
       ファミ
            DON CHEMICAL COMPANY
       773 DOWNTOWN AIRPARK, INCORPORATED 774 DRILLERS ENGINE & SUPPLY
       774
       775 DURA-CHROME INDUSTRY
       776
           ERSON & SMITH, WASTE HAULERS
       777
           EASON ENTERPRISES
       778
          EASON DIL
       779 E. I. DUPONT DE NEMOURS
       780 ELTEX CHEMICAL AND SUPPLY COMPANY
       781
           ENGINEERING ENTERPRISES
       782 EQUIPMENT RENEWAL COMPANY
       783 ERNEST ST. CLAIR
       784
           EUREKA TOOL COMPANY
       785
           EVAN'S ELECTRIC SERVICE CENTER
           FAR AERONAUTICAL CENTER
       78£
       787
           FIBERCAST CORPORATION
           FINE CANDY COMPANY
       788
       783
           FIRST NATIONAL MANAGEMENT CORPORATION
       790
           FLINT STEEL CORPORATION
           FORD GLASS PLANT
       791
      792
           FOSTER FEED & SEED
       793
           FOSTER SEPTIC TANK CLEANING
       794
           FRED JONES MANUFACTURING
       795
           FREUHAUF CORPORATION
           GARDNER-DENVER COMPANY
       79€
       797
            GENERAL ELECTRIC
       798
          GENERAL ELECTRIC
       793
           GENERAL TIRE & RUFFER
       BOO GEDPHYSICAL RESEARCH
       801 GLIDDEN COATINGS & RESING COMPANY
       BOR GLOW-LITE DIVISION OF DUTCH BOY, INC.
       BO3 GODDYEAR TIRE & RUBBER COYPANY
       804
           GOVERNAIR CORPORATION
       805
            GROENDYKE TRANSPORT, INCORPORATED
       806
           HALLIBURTON SERVICES
       807
            ROYAL M. HARDAGE
           HART INDUSTRIAL DISPOSAL
       808
       803
           HATHAWAY INDUSTRIES
       810
           HELM & WEAVER
       811
           HERMETIC SWITCH, INCORPORATED
       812
           HOLLEY CARBURETOR
       813
           INDUSTRIAL UNIFORM
            INDUSTRIAL DISPOSAL SUPPLY, INCORPORATED
       814
           INTERNATIONAL CRYSTAL MANUFACTURING
       815
            JOHN ZINK COMPANY
       816
JONES-BLAIR PAINT COMPANY
       817
           KELSEY-HAYES
       818
       819 KELTRONICS CORPORATION
       820
           KERR MCGEE, PRESIDENT
       821
            KIMEALL CHEMICAL COMPANY
           KOBE INCORPORATED
       953
            KDCD TV
       823
            LAHT I PLATING COMPANY
       824
       825 LEAF HEGLER, INCORPORATED
      THIS LIST F RESENTS EPA'S PRELIMINARY FINDINGS ON THE IDENTITIES OF
```

THIS LIST & RESENTS EPA'S PRELIMINARY FINDINGS ON THE IDENTITIES OF
POTENTIALLY ESPONSIBLE PARTIES. INCLUSION ON THIS LIST DOES NOT
CONSTITUTE FINAL DETERMINATION CONCERNING THE LIABILITY OF ANY PARTY AROUND 189
FOR THE HAZ D OR CONTAMINATION, AT THE HARDAGE SITE

```
L. & S. BEARING COMPANY
BEE
     LEEWAY MOTOR FREIGHT (C. L. MOTOR FREIGHT)
827
823
     MAREMONT CERPORATION
830
     MASTER MOTORS
     MATERIALS RECOVERY ENTERPRISES
831
832
     McDONNELL DOUGLAS
     McKESSON CHEMICAL COMPANY
823
     MANUFACTURING MERCURY MARINE
834
835
     METROPLEX SANITATION
83£
     MIKE MONRONEY AERONAUTICAL
837
     MOBIL CHEMICAL COMPANY
828
     NAMEPLATES, INCORPORATED
839
     NATIONAL CAN CORPORATION
840
     NATIONAL PACKAGING COMPANY
841
     NELSON ELECTRIC COMPANY
     NEWSPAPER PRINTING CORPORATION
842
B43
     NICKLES MACHINE CORPORATION
844
     NORDHAM, INCORPORATED
545
     NORTHROP WORLDWIDE GIRCROFT SERVICE INC.
54€
    NU CHROME PLATING
A47
     D'ERIEN PAINT CORPORATION
848
     OCCIDENTAL CHETICAL
     OKLAHOMP CITY DISPOSAL
843
650
     DKLAHOMA GAS & ELECTRIC
85:
     DKLAHOMA CITY COUNTY HEALTH DEPARTMENT
85E
     OKLAHOMA DEPARTMENT OF AGRICULTURE
     DKLAHONA DEPARTMENT OF CORRECTION
853
     OKLA-DMA STATE DEPARTMENT OF HEALTH
654
855
     D.K. PUFLISHING COMPANY
85E
     DKLAHOYA MACHINE MANUFACTURING
857
     D.K. NATIONAL STOCKYARDS COMPANY
838
     D. K. NATURAL GAS COMPANY
853
     D.K. TANK SERVICE, INCORPORATED
    D. K. TRANSPORTATION COMPANY
BEO
8E1
     GRAL ROBERTS UNIVERSITY
E££
     PAGE INDUSTRIES
     PATTERSON SARGENT
863
864
     PHARYASEAL LAES
BES
     PHILLIPS CHEMICAL
BEE
     PHILLIPS PETROLEUM
     POWELL SANITATION SERVICE
6E7
838
     POWELL SERVICE COMPANY
     PRESEYTERIAN HOSPITAL
869
    PRESTOLITE CORPORATION
870
     PRYOR FOUNDRY, INCORPORATED
871
     PUBLIC SERVICE COMPANY
872
     RA NAU CIRCUITS, INCORPORATED
873
     RANDY PLLID
874
     REAGENT CHEMICAL & RESEARCH, INC.
875
     RED PALL MOTOR FREIGHT
876
     ROCKWELL INTERNATIONAL
877
     ROCKH 'LL INTERNATIONAL CORPORATION
878
     RODCO INCORPORATED
879
     NOITARDEPOS KETCA
880
881
     BT. A THONY HOSPITAL
882
     S. &S. PLATING COMPANY
     BANTA FE RAILROAD
883
```

THIS LIST RE ESENTS EPA'S PRELIMINARY FINDINGS ON THE IDENTITIES OF POTENTIALLY SPONSIBLE PARTIES. INCLUSION ON THIS LIST DOES NOT CONSTITUTE A INAL DETEMINATION CONCERNING THE LIABILITY OF ANY PARTY OR CONTAMINATION AT THE HARDAGE SITE

AR0001895

```
SCA SERVICES
004
    SERRS AUTO CENTER
BAS
€3€
    SENTRY MANUFACTURING
     SERMETEL, INCORPORATED
897
336
    SERVICE PRINT MANUFACTURING COMPANY
    SHAKUEE CORPORATION
698
    SHERLIN-WILLIAM COMPANY
890
85:
     EKY WITCH
    SCLVENT MANUFACTURING COMPANY, INC.
BSE
E93 SOONER FORD
    SUDNER DIL PATCH SERVICES, INCORPORATED
834
895 SOUTHERN HILLS COUNTRY CLUB
896 SOUTH PRAIRIE CONSTRUCTION
897 SOUTHWEST ELECTRIC COMPANY
896 SCUTHWESTERN STEEL ROLLING DOOR COMPANY
899 SOUTHWEST UNITED INDUSTRIES
900 SPERRY VICKER COMPANY
901
    STAN RAMSEY COMPANY, INCORPORATED
902
    STANDARD CHEMICAL COMPANY
903
    STAR MANUFACTURING COMPANY
    STEELCRAFT, INCORPORATED
304
905 STORM PLASTICS, INCORPORATED
    SUPLETT & ASSOCIATES
90E
907
    BUN GAS
    TEXACO, INCORPORATED
908
909 TEXAS INSTRUMENTS
910 TEX PRODUCTS, INCORPORATED
911
    THE BUCKET SHOP, INCORPORATED
912 SAMUEL RUFERTS NOBLE FOUNDATION, INC.
913 THOMAS & BETTS
    THOMPSON HAYWARD CHEMICAL COMPANY
914
915 UNITED STATES AIR FORCE
916 TRIBONETICS COMPANY
    TOY EROWN'S OPTICAL
9:7
9:8
    TOX
9:9
    TRIES DRILLING
930 TUFTS & SON OF DKLAHOMA
921 UNARED COMMERCIAL PRODUCT
922 UNIRDYAL TIRE COMPANY
923 UNIT PARTS, BORG-WARNER COMPANY
924 UNITED FOAM
925 UNITED PLATING WORKS, INCORPORATED
926 UNIVERSAL DIL PRODUCTS
927
    UNIVERSITY OF DKLAHOMA
928 UNIVERSITY OF DALAHOMA
929 UNIV. OF DKLAHOMA HEALTH SCIENCE CENTER
930 UNIVERSITY OF OKLAHOMA
931 COLONEL MARY FELTS
932 U.S. CORPS OF ENGINEERS
933
    U.S. DEPARTMENT OF ENERGY
934
    U.S. POLLUTION CONTROL
    U.S. POLLUTION CONTROL
935
    VETERANS ADMINIST ATION
936
    WAYNE CIRCUIT
937
    WELCH DIL COMPANY
938
    WESTERN ELECTRIC ( )MPANY
939
940 WESTERN EXTRACT MERUFACTURING COMPANY
```

THIS LIST REPRESENTS EPA'S PRE IMINARY FINDINGS ON THE IDENTITIES OF POTENTIALLY RESPONSIBLE PARTIE . INCLUSION ON THIS LIST DOES NOT CONSTITUTE A FINAL DETEMINATIC CONCERNING THE LIABILITY OF ANY PARTY FOR THE HAZARD OR CONTAMINATIC AT THE HARDAGE SITE

AK000139

```
94:
     WESTING-DUSE ELECTRIC CORPORATION
94£
    WEYERHAEUSER COMPINAY
943
    WILSON DOWNHOLE SERVICES
544
    W. J. LAMBERTON
    WC_VERINE PIPE
945
945
     IDECEN INDUSTRIES
947
     DKLAHOYA GRAPHICS
948
    U.S. SMALL BUSINESS ADMINISTRATION
949
    GENERAL MOTORS
950
    SUPERIOR LINEN
95:
     O.K. MEMORIAL HOSPITAL
952
    JIM'S SEPTIC SERVICES
953
    A-A EMERGENCY PLUMBING
954
     RIVERSIDE INDUSTRIES
955
    WASTE MANAGEMENT
956
     INTERNATIONAL SYSTEM & CONTROL
     P.A. INDUSTRIES-POLAR MANUFACTURING
957
     AMAX, INCORPORATÉD
958
959
     WASTE MANAGEMENT, INCORPORATED
960
     SANDTRAP SERVICE
961
     FOSTER FEED & SEED COMPANY
963
     JOD DIL EXPLORATION COMPANY, INC.
963
     ALLIED PAINT CORPORATION
     BORG-WARNER CORPORATION
954
965
    CLIFTCO, INCORPORATED
966
    HOVEYMELL COMPANY
9£7
     COOK PAINT AND VARNISH COMPANY
968 CHEMICAL LEAMAN TANK LINES, INCORPORATED
9£9
    YMARYOD THIAR CACHAID
970 EXXUN CHEMICAL COMPANY
     W. R. GRACE & COMPANY
971
972
     GULF STATES PAINT COMPANY
972
     RALPH LOWE
     MAGNA CORPORATION
974
975
    NALEO CHEMICAL COMPANY
     THE O'BRIEN CORPORATION
97E
977
     P. P. G. INDUSTRIES
978
     RELIANCE UNIVERSAL, INCORPORATED
573
     ROPM AND HAAS TEXAS, INCORPORATED
     WITCO CHEMICAL COMPANY
980
981
     TRIANGLE ENGINEERING COMPANY
```

THIS LIST REPRESENTS EPA'S PRELIMINARY FINDINGS A THE IDENTITIES OF POTENTIALLY RESPONSIBLE PARTIES. INCLUSION ON THE LIST DOES NOT CONSTITUTE A FINAL DETEMINATION CONCERNING THE LABILITY OF ANY PARTY FOR THE HAZARD OR CONTAMINATION TAT THE HARDAGE!

AR000181

APPENDIX C

COMMUNITY RELATIONS RESPONSIVNESS SUMMARY
ON THE SOURCE CONTROL FEASIBILITY STUDY

AR0001595

- COMMUNITY RELATIONS RESPONSIVENESS SUMMARY

ON THE SOURCE CONTROL FEASIBILITY STUDY

HARDAGE/CRINER SUPERFUND SITE MCCLAIN COUNTY, OKLAHOMA

NOVEMBER 1986

COMMUNITY RELATIONS RESPONSIVENESS SUMMARY ON THE SOURCE CONTROL FEASIBILITY STUDY

HARDAGE/CRINER SITE MCCLAIN COUNTY, OKLAHOMA

This document summarizes public comments and Environmental Protection Agency (EPA) responses to questions and concerns raised during the public comment period. The responsiveness summary is divided into four sections:

- I. Overview
- II. Activities to illicit input and address concerns
- III. Summary of public comments and EPA response, and
- IV. Remaining concerns

I. OVERVIEW

At this time, the Environmental Protection Agency (EPA) is presenting its response to comments on the Source Control Feasibility Study (FS) prepared for the Hardage/Criner site. EPA has not yet selected its preferred remedy but has developed four remedial alternatives which it believes to be cost-effective plans, meeting all applicable or relevant and appropriate Federal requirements for protection of public health and welfare and the environment.

This site is being managed through the EPA enforcement program. As such, EPA will make a decision on the "baseline" remedy which it feels to be acceptable. EPA will then negotiate with private parties believed liable for the site in an effort to achieve voluntary cleanup of the site. In a parallel manner, EPA is pursuing direct enforcement action under Section 106 of the Comprehensive Environmental Response Compensation and Liability Act of 1980 (CERCLA) and under Section 7003 of the Resource Conservation and Recovery Act of 1976 as amended (RCRA).

When a remedy is proposed, EPA will be seeking public comment. Only after this comment period will EPA make it's final remedy selection.

AR00001901

II. BACKGROUND ON COMMUNITY INVOLVEMENT AND CONCERNS

Major Concerns and Issues

One of the major concerns at the Hardage (Criner) hazardous waste site is evidence from monitoring wells of migration of contaminants from the site and contamination of residential wells offsite. The North Criner Creek alluvium is the primary aquifer of concern.

Deteriorating conditions at the site (i.e., continuous seepage from the pits, exposed barrels from the mound, etc.) and inadequate barriers to retard migration, have given rise to concern for potential surface and groundwater contamination.

Activities to Elicit Public Input and Address Concerns

EPA has kept members of Congress, as well as other elected officials and citizens informed of meetings, plans, and alternatives under consideration. Elected officials and citizens were notified prior to start of the Remedial Investigation and Feasibility Study (RI/FS) process.

Ten families live in the immediate vicinity of the site. Each family was interviewed by representatives of the Oklahoma State Department of Health (OSDH) and the EPA to ascertain their concerns and feelings about the site. Primarily, these citizens' concerns centered around contamination of the groundwater, which was originally discovered in the mid 1970s by the State of Oklahoma in onsite monitoring wells. Since that time, EPA and OSDH have expended considerable joint effort and resources to determine the nature and extent of the contamination. Royal N. Hardage, owner and operator of the site, was sued by the United States in September 1980, seeking investigation and clean up of the site. Although the United States established it's case and won a partial judgement against Royal Hardage, it was unsuccessful in obtaining site clean up, in large part due to Mr. Hardage's bankruptcy. The U.S. Government filed suit in June 1986 against 36 companies believed to be responsible for public health threats posed by the site, seeking performance of remedial actions and further studies as directed by EPA as well as reimbursement of all Superfund costs incurred, which is more than \$1.4 million.

A press release announcing the end of the Feasibility Study, start of the public comment period, and a public meeting, was issued by EPA on February 24, 1986. Copies of all formal documents concerning the site were placed in five strategic repositories for the public to review preparatory to making their comments. Preceding the public meeting held on March 20, 1986, EPA briefed the mayors and other city officials of both Chickasha, Oklahoma and Purcell, Oklahoma. At this briefing, EPA reviewed past actions and ongoing and future planned site activities.

SUMMARY OF PUBLIC COMMENTS RECEIVED DURING THE COMMENT PERIOD AND EPA RESPONSE

The public comment period on this FS was from March 10 through April 15, 1986. The FS was placed in repositories and provided to the Hardage Steering Committee (HSC) on February 25, the day after a press release announced the end of FS activities. A March 20, 1986, public meeting was attended by approximately seventy people, nine of whom made statements. Fourteen sets of written comments were received, consisting of over 200 pages. These comments were received from:

1) B&F Engineering - for Weyerhauser

 Gardere & Wynne - for L&S Bearings, Rotex, and Tribonetics
 Hardage Steering Committee - a PRP group representing 135 parties, submitted their own comments as well as those of three consulting firms retained by the HSC: Dames & Moore, ERM-Southwest, and MDK Consultants

4) Hildebrandt Tank Service

5) Hill & Robbins - representing U.S. Pollution Control, Inc.

6) The Hardy Horton Family

7) Hunton & Williams - representing Oklahoma Gas & Electric, comments endorsed by AT&T

Kerr McGee 8)

9) League of Women Voters

10) Rajeanna Mayo

11) Oklahoma Center for Veterans Rights

12) Pat Shepherd

13) Thompson & Knight - representing firestone

14) Glenn Webb

Comments were also received during the public meeting from the following parties: Glenn Webb, Kinnan Goleman (for HSC), Neal Garrett, Tom Smith, Roberta Olefield, Linda Wall, Faith Hurley, Ben Kalas (for KWCL news) and Mark Fox.

After analysis of the comments, it was decided to organize the responsiveness summary into seven sections, each dealing with comments on a specific subject. These seven categories are:

- A) Adequacy of data,
- B) Operable unit approach,
- C) Compliance with the NCP.
- D) Feasibility Study process,
- E) Opportunity for public participation,
- F) Recommendation for additional study or interim remedial measures; and
- G) Other comments

A) ADEQUACY OF EXISTING DATA ON THE HARDAGE/CRINER SITE

Several commenters suggested that existing data is inadequate to fully characterize the site and develope a permanent and cost effective remedy. Based on the volume of comments, it appears that either the consultants which these individuals employed are not fully aware of the amount of existing data or that a substantial difference of opinion exists between EPA and the Hardage Steering Committee (HSC) as to what would constitute "adequate data". EPAs "Guidance on Remedial Investigation under CERCLA" indicates in Section 7.2.3 that the extent of investigation should not be more than is "necessary and sufficient" to satisfy site-specific objectives. Such objectives were defined early by EPA and are documented in the November 1983 work plan prepared by CH₂M Hill. In the case of a source control action data must be, and in this case is, adequate to establish the degree of containment of the waste materials with reasonable certainty. The data must also allow development of feasible alternatives for remediation of the site, screening of these alternatives, and ultimately selection of an appropriate cost-effective alternative for remedial action. As in any engineering or scientific study, 100% of the available data could never be gathered. As more and more is learned about the site, further data gathering efforts will become less productive and of less value in providing new information and more duplicative of previous studies. At this point, the Agency believes that sufficient knowledge of the source areas of waste and their current state of containment does exist to allow decisions based on fact and sound engineering principles (not on assumptions or conjecture) to be made as to the appropriateness, feasibility, and cost effectiveness of a range of source control remedial alternatives as required by the National Oil and Hazardous Substances Contingency Plan (NCP), 50 Fed. Reg. 47950, November 20, 1985.

The level of data gathering suggested by some commenters indicates confusion about the purpose of an FS and the preceding investigative efforts. The data gathered prior to remedy selection on a Superfund site is not intended to be so complete as to allow preparation of detailed design for each remedial alternative or even for the remedy selected. For example, it would make no sense to collect the extensive data required to design four remedies when only one will be selected. The data only needs to be sufficient to determine the most cost-effective feasible remedy protective of public health and welfare and the environment, not inconsistent with the NCP.

Several commenters pointed out what they believed to be data gaps in EPA's characterization of groundwater hydraulics and other contamination outside the source areas. Since a separate RI/FS is planned to specifically address this, the second operable unit, the comments are noted for future reference in development of the workplan for the second operable unit (Management of Migration) RI/FS.

Response to specific questions and comments regarding the adequacy of data is provided below:

Comment:

Certain data indicate that the bedrock may be fairly impermeable and caple of preventing waste migration, specifically: the yield of water from interceptor wells installed by the operator are low, as reported in the FS; the packer permeability tests conducted by EPA contractors in 1984 indicate the permeability of bedrock is very low, less than 10-7 cm/sec.

Response:

It should be noted that the packer tests indicated permeabilities were less than 8 x 10-7 cm/sec. Packer tests, when conducted properly and under favorable conditions, can provide an indication of the permeability around the well bore. This does not necessarily reflect overall permeability of the bedrock or the ability of seepage to move rapidly through joints. The intact bedrock, especially shales, at this site may have hydraulic conductivities on the order of 10-7 cm/sec. or less. However, EPA believes secondary permeability (fractures/ joints) rather than porosity, characteristics have allowed existing contaminant transport. As stated in the FS, the results of site packer permeability tests would not have been significantly affected by thin, occasional layers with hydraulic conductivities on the order of 10-1 to 10-3 cm/sec or an occasional thin fracture. This statement is based on estimations of the water loss through a thin pervious layer within the packer test sections. Based on the tests conducted at the site, such a layer would not result in sufficient water loss during the test to result in an overall hydraulic conductivity of greater than 10-7 cm/sec, but would allow contaminant migration at relatively high velocities in these secondary channels.

As discussed in the FS, difficulties are inherent in monitoring groundwater quality in a fractured aquifer. The absence of contamination in a single well, for example, cannot be taken with any confidence to mean that contaminants have not reached that general area. This is apparent when one considers the relatively minor area intersected by a well bore as compared to the areal and vertical extent of the aquifer which this well would be intended to monitor (a six inch well bore with a twenty foot long screened-sampling-section might be placed hundreds to thousands of feet from other wells and represent the only data on this section of the aquifer). When groundwater flow occurs through preferential channels, as at Hardage, the

interception of contaminated flow pathways is largely reduced to a matter of chance. The consistent presence of contamination in the majority of wells spaced over a wide area carries great weight in proving the aquifer to be contaminated; and such a situation is correctly taken to represent contamination of the entire area monitored by the contaminated wells.

The yield of the Hardage Wells was reported incorrectly in the FS as one barrel per day. The yield, as stated by Royal Hardage in a 1980 deposition was in fact 25 barrels per day for each of two wells.

Comment:

The groundwater contour map presented in the FS was developed with data from different zones. This is not a correct procedure since deeper bedrock may be hydraulically confined or vertical gradients may exist, making contours developed in this manner deceiving.

Response:

The Bison and Purcell Formations are undifferentiated at the site, comprising a single unconfined hydrogeologic unit; and present data indicates the bedrock is hydraulically connected in the vertical direction and in communication with the alluvium. Therefore, the use of all water level measurements at the site in preparing the ground-water contour map presented in the FS is only subject to errors caused by vertical gradients. Vertical gradients in ground-water do exist and do influence the phreatic surface obtained from monitoring wells installed to various depths. During the investigation for the second operable unit, nested wells will likely be installed to further evaluate vertical gradients at the site. Based on this information, a refined contour map may be developed. Overall, this only has an impact on the second (management of migration) operable unit.

Comment:

Data from waste characterization holes drilled through the sludge mound and main pit suggest that vertical barriers to seepage exist beneath these areas.

Response:

Some data, when analyzed in a cursory manner, could indicate barriers to seepage exist below source areas. However, the observed vertical migration of contaminants and their lateral spread into areas where no other pathway could exist but through groundwater transport overwhelmingly indicates that vertical barriers do not prevent susbstantial releases of contaminants from the shallow to the deeper groundwater.

Comment:

The vertical extent of contaminant migration has not been defined, neither have the vertical flow gradients that would induce such migration. Such information is needed to fully characterize site hydrogeology and adequately develope and evaluate remedies.

Response:

Vertical migration of contaminants through the bedrock to depths greater than 40 feet has been documented to the east, southwest. and directly beneath the source areas. The information obtained from the waste characterization (WT) holes does indicate vertical contaminant migration beneath the source areas, as discussed in the response to latter comments. In addition, ground-water contamination found in wells EW-01, BW-01, BW-04 and GTW-03 indicates contaminants in ground water at depth. In each of these wells, the well screen interval was placed beneath the phreatic surface measured at the well location, thus contamination found at these well locations are beneath the surface of the ground-water table and confirm vertical migration. In addition, several wells and exploratory boring locations were installed adjacent to deeper wells. Although these were not specifically intended to constitute nested wells, information obtained from these locations indicates a gradient from shallow to deep groundwater.

Comment:

Piezometric levels of groundwater were measured in January and aren't representative of the entire year due to seasonal fluctuations. This limited data cannot indicate to what degree wastes in the source areas are beneath the water table.

Response:

EPA agrees that the levels may represent a low as compared to the rest of the year. However, relative levels and the shape of groundwater contours and flow directions likely represent an annual average and are consistent with those developed by earlier investigators (Baker & Burns, 1980; Kent, 1982). Seasonal fluctuations could be better defined in further studies.

Comment:

Geologic cross-sections were not compiled. Such sections could aid in analyzing site geohydrology, and are a tool commonly used to perform such analyses.

Response:

The bedrock consists of shales, mudstones, and sandstones which are deposited in discontinuous layers. These layers grade gradually back and forth from one rock type to another. Since this gradation occurs in three dimensions, the classical concept of a well defined sequence of horizontal or consistently dipping beds which allows tracing individual layers of the

sequence from one borehole to the next is not applicable. As a result of this graded lithology, EPA could make only limited interpretations and would have had virtually no confidence in cross-sections compiled with data from these or any other bedrock borings. For this reason, cross-sections were not refined or published.

Comment:

The site may not be suitable for locating a landfill cell in compliance with RCRA Part 264 regulations; and data is inadequate to make this determination. This should have been considered before retaining the On-site Disposal Alternative through final screening.

Response:

EPA believes the existing data indicates that the site is suitable for placement of a RCRA vault; and further study will be conducted for design should this alternative be selected. Due to the widespread contamination on-site, low levels of residual contamination will remain in the soils over which the landfill would be constructed. A questions was raised by one commenter as to the potential problems of monitoring for leaks from the landfill cells, that is, if contamination were seen in monitoring wells questions could arise as to whether it is coming from trace landfill's liner systems. It is EPA belief that monitoring in a possibly contaminated environment will not present insurmountable technical problems since: (1) The vault will have an interior detection system capable of detecting any leaks before they enter a contaminated zone; (2) the vault will be above the groundwater table, eliminating potential up-flow of contaminants into the interior detection system; (3) regular monitoring will likely be required for any remedy, and long term water quality trends could be established, allowing significant leaks from the exterior liner to be detected. The site is located over several thousand feet of sediments and is not prone to earthquakes. The area of the site considered for locating a landfill cell is far above the 100 year flood and also above the probable maximum flood. Thus, the site meets the requirements set forth in 40 CFR Section 264.18.

Comment:

The geometry of waste fill is not defined. Without such data, it is not possible to adequately evaluate any alternatives or determine either the Feaibility in in-situ containment or the need for excavation of the source areas.

150001302

Ţ

Response:

The base of pits excavated during site operations and later backfilled is defined by depositions of the operator Royal Hardage and confirmed by test holes in these source areas. The borings show bedrock at consistent elevations of about 1109 and 1093 feet mean sea level (MSL) beneath the main pit and sludge mound respectively, thus defining the base of the pits. Magnetometer surveys have located substantial drum concentrations in the drum mound and along the west side of the main pit, also confirming early site inspections and the Hardage depositions.

Comment:

A Quality Assurance plan was not prepared in accordance with the NCP. As such, the accuracy of the data and the methods of data collection are questionable.

Response:

The Quality Assurance Project Plan (QAPP) is included as Appendix A to the May 1985 Data Summary Report. This QAPP meets all the requirements of the NCP (1982 edition), including concurrence on the plan by the Regional QA officer.

Comment:

Sampling from three test holes in the sludge mound failed EPA's requirements for QA/QC. This lack of data prevents EPA from making decisions on the disposition of the materials since it can make no judgement on it's potential threats.

Response:

After completion of the Feasibility Study, EPA's Houston Lab was asked to review the data. The principal problem was that lab reporting sheets indicated the units to be parts per million (ppm). Summing the various constituents indicated certain samples with a sum greater than a million ppm, indicating an obvious error. The Houston Lab's review showed that the units were incorrectly reported and in reality should have been parts per billion (ppb) rather than ppm. This has corrected virtually all problems with this data set. The Houston Lab review is documented in an August 1986 letter from Bill Langley (EPA-Houston) to Bob Davis (CH₂M Hill-Dallas).

Data also exists from previous sampling of the sludge mound and in some cases for wastes disposed there. In addition, the types of wastes disposed in the sludge mound are known for the most part to be: styrene tars; drummed aresenic and cyanide; PCB contaminated equipment; and sludges from oil recycling, the analysis of which showed extremely high levels of lead and phenol as well as over 50 ppm of PCBs; and a composite of all other wastes disposed at the site as a result of clean-out of the main pit. Samples taken in 1982

from the surface of the sludge mound indicated PCB-1260, lead, chromium, anthracene/phenanthrene, dichloropheonol, and other heavy metals and synthetic organics.

Comment:

Poor well drilling techniques may have resulted in cross-contamination of some monitoring wells and waste characterization holes; thus the results may not indicate deep contamination of soil and/on groundwater.

Responses

Discussion is made regarding the contamination found in the waste characterization holes (WT) beneath the source areas. It is suggested by the commenter that only trace levels of contaminants were detected in bedrock samples beneath the pits and that they are "probably associated with inadequate sampler decontamination... or laboratory contaminants". As presented in the Data Summary Report, EPA (1985), rinsate samples taken from the sampler after decontamination did indicate a few contaminants at parts per billion levels in addition to laboratory contaminants. The contention by some commenters is that bedrock contamination beneath source areas was mainly the result of sampler and laboratory contamination; however, this is not substantiated by overall sample analyses. Consistently, compounds other than those found in the rinsate and laboratory blank samples were found in bedrock samples beneath the sources. In many instances, these compounds had concentrations in the parts per million range (orders of maynitude higher than that shown in blanks). In addition, in several holes, compounds were found in the underlying bedrock samples which were not found in samples taken within the source area nor in rinsate or laboratory blank samples. These compounds are however components of wastes known to have been disposed at the site. The obvious conclusion here is that the wastes were not, as the commenter suggested. carried down the borehole by careless sampling procedures. nor were the compounds introducted at the lab or at any time after the samples were collected; rather the contaminants are in fact, as EPA has previously stated, at depth beneath the source areas and represent the result of actual waste migration vertically out of the waste pits and into underlying sediments. In waste characterization hole (WT-006), the results of the analysis of the composite sample comprised of samples from 28,33 and 38 feet showed very few volatile compounds; however, the sample taken at 43 feet showed many more volatile compounds present. EPA believes this pattern of contamination is more indicative of vertical migration through the bedrock along secondary permeability features than the result of trace

contamination on sampling tools. Well GTW-03 showed contamination in groundwater as did the nearby BW-04 well; however, analysis of borings taken from GTW-03 showed no contamination of the overburden, thus precluding contamination of this well during construction.

(For further discussion, refer to a previous comment on vertical migration of waste page C-8).

Comment: No data exists to support EPA's contention that a hazard exists from air on the site.

Response: EPA recently sent its Emergency Response Branch (ERB) to the site for purposes other than air monitoring; however, this was also done while on-site, sampling with a photoionization unit showed readings less than 1 ppm in air. It has been observed that odors are much worse on-site in wet weather than dry wheather-when ERB visited the site. At this time, EPA must reply that it has no data which indicates an air hazard from organic vapors exists on-site at this time. It is entirely possible however, that deteriorating site conditions could pose threats by this exposure pathway.

Comment: Use of area groundwater is not adequately assessed to determine the need for remedial actions.

Response: Those groundwater supplies with the potential to be immediately affected have been considered. Other supplies which could ultimately be impacted as wastes migrate farther from the site will be assessed in detail during groundwater/off-site studies.

Comment:

Response:

The groundwater pathway of contamination transport off-site has not been sufficiently defined. The potential for groundwater contamination has been cited as one factor requiring remedial action, yet it's potential impact have not been adequately assessed.

Pathways of groundwater contamination transport were only considered insofar as they indicate a general inability of the bedrock to provide a reasonable degree of containment of wastes in the source areas. The presence of contamination in the alluvial aquifer of North Criner Creek and the route of transportation from the source areas are by and large irrelevant to the question of the adequacy of barriers beneath these

source areas several thousand feet away. EPA still believes that contamination of this aquifer has resulted from combined runoff and sub-surface transport. The question of which pathway has contributed what to current contamination is of only academic importance, since significant subsurface migration has occurred in this and other directions, and contamination of the alluvium by this method will continue or began to occur until the sources are exhausted.

Comment:

Source areas may exist which have not yet been identified. If this is the case, then the source control FS is incomplete.

Response:

Sufficient information on the operating history of the site is available from Oklahoma State Department of Health (OSDH) inspections from 1972-1980 and from the operators depositions to confirm that Mr. Hardage made efforts to consolidate wastes in the main pit/drum mound and sludge mound. Site samplings and recent inspections give no reason to doubt the belief that the major concentrations of solids, sludges, and drummed wastes are located in the three principal source areas addressed by EPA in its FS.

Even if other major source areas did exist, it would not preclude EPA from addressing the drummond, main pit, and sludge mound as a single operable unit. The NCP provides no such constrainst on what must be included in an operable unit or on how many operable units a site may be divided into.

Comment:

Background quality of groundwater has not been determined. Without knowledge of background concentrations of chemicals or elements, it is impossible to determine if the site is contributing the compounds or if the levels are naturally elevated and unrelated to the site.

Response:

The background levels of synthetic organics (such as solvents) in this rural area is essentially zero with the possible exception of pesticides from agricultural application, and trace levels of natural phenol in groundwater. The background levels of inorganics will be fully addressed in the Management of Migration RI.

Comment:

The extent of groundwater contamination has not been adequately defined; and no plume has been shown to emanate from the source areas. As a result, it is premature to determine that groundwater contamination requires any remedial action.

Response:

Great difficulties exist in monitoring a fractured aquifer where migration is along preferential channels, and where a heavily contaminated zone might lie within a few feet of an apparently clean monitoring well. This characteristic makes the classical concept of a contaminant "plume" misleading and inappropriate for describing migration patterns at this site. In future studies, EPA will undertake to delineate the plume present in alluvium of North Criner Creek, further define the lateral extent of groundwater contamination in the bedrock, and evaluate the potential for contaminants to migrate beneath stream drainage divides near the site. Such investigative activities properly fall within the scope of the second operable unit.

Comment:

Trends show water quality is improving with time. This could indicate that the situation is not worsening, but rather that the groundwater system is recovering by natural processes.

Response:

The historical water quality data is indicative of the presence of off-site contamination. It is not felt that trends in contaminant concentrations can be drawn from the information, since the samples were taken by various parties using widely varying sampling procedures. Specifically, some samples were obtained from taps at the residences rather than directly from the well, thus subjecting the water to aeration during pumping and stripping of some volatiles.

If off-site sampling results from various sources were comparable, the well with the largest historical data base (the old Corley well), does not show any trend whatsoever. Contamination is similar to the levels first seen in late 1982, two years after the site closed.

B) EPA's OPERABLE UNIT APPROACH TO THE HARDAGE/CRINER SITE

Comments were received which questioned the technical and legal justification for EPA's decision to divide the site remediation of groundwater/off-site contamination as discrete and separable problems.

EPA has addressed a substantial number of NPL sites, including several in Region 6 (Bayou Bonfuca, Gurley Pit, Vertac, Motco, Highlands Acid Pits, Odessa Chromium 1, and Odessa Chromium II), by dividing the response into operable units. These divisions are made based on technical information for the site and the criteria presented in the NCP. As noted in the FS. EPA believed at the time the division was made, and continues to believe, that a substantial quantity of wastes remain in or near their original location and are not contained by adequate barriers and that a remedy for source control will be cost-effective and consistent with a premanent overall remedy for the site, thus meeting criteria set forth in the NCP for operable unit remedial response. The best engineering judgement of the Remedial Site Project Officer (RSPO), EPA Regional and Headquarters managers, and EPA contractors was that the vast majority of releases of hazardous substances to the environment could be abated by controlling these source areas which comprise less than 10% of the site area. Strategies for cleanup of existing groundwater contamination or knowledge of the necessity of such actions is not necessary in order to determine the best method of containing the wastes. Source control and management of migration are in this case clearly seperable; therefore, further delays are unnecessary and would be inconsistent with provision of a timely response to a situation posing an imminent and substantial endangerment to public health and welfare and the environment.

Response is provided below to specific comments on the operable unit approach taken on the Hardage site.

Comment: No technical justification exists for an operable unit approach to the Hardage site; the decision to address the site in this manner was driven by budgetary problems and previous delays in completion of the FS.

Response: The technical justification for splitting the site into operable units is strong, as discussed above. The questions about pathways of contaminant transport to offsite alluvium and the extent of surface contamination away from the source areas are not mandatory considerations in the question of source control and the existence of barriers to migration. Since all proposed source control alternatives involve waste excavation and stabilization, which remedy is finally selected is not a concern in relation to the Management of Migration operable unit, therefore delays to determine the groundwater/offsite remedy are unnecessary. The criteria set forth in the NCP for use of operable units has been met; and no strong justification exists for not using the approach and further postponing cleanup of the site. The comment hat EPA employed operable units due to budgetary problems is unfoursed; the cost of the DSR/FS project was slightly over \$800,000 less than is sometimes spent or far less complicated sites.

Comment: EPA has worked on the site for three to five years; so expediting the remedy makes no sense at this point. Further studies should be conducted and a new FS prepared to address the site as a whole rather than as operable units.

Response: EPA first inspected the Hardage site in July 1979; and a complaint was filed against the operator in September 1980 under Section 7003 of RCRA. While EPA has been involved with the Hardage site for nearly seven years now, active Superfund involvement did no begin until 1984. Field work was commenced by EPA in July 1984 and the FS was released in February 1986, twenty months later; the normal period of time in which EPA attempts to complete its investigations and FS on Superfund sites is eighteen months. Delays on this site under Superfund have not been exceptional; and any delays which have occurred do not provide a justification for further unnecessary delays.

Comment: A cost effective remedy can't be selected without knowing the final remedy for other parts of the site.

Response: The situation at Hardage is such that excavation and treatment of the waste piles and pits is required (FS. pages 3-22 through 3-36). Therefore, the cost-effectiveness consideration is reduced to a comparison of various treatment technologies and their relative feasibility, benefits, and permanence. Cost-effectiveness considerations are only to be applied in comparisons between acceptable remedies in accordance with Section 300.68 of the NCP.

Comment: A remedy for source control should not have to meet applicable or relevant and appropriate requirements since it is not the final remedy [(NCP, Section 300.68 (i)(5)(i)].

ET

Response: The remedies which EPA has developed and evaluated, while not addressing the entire site, are permanent for the source control operable unit. As such, response actions must be in accordance with these requirements just as if this remedy were for all aspects of the site. The passage cited in the NCP refers to interim remedial measures (such as a temporary cap) which may be implemented while further study or planning is conducted for the permanent remedy.

Comment: The lack of data needed to complete a FS for the entire site prompted EPA to divide the site into operable units; and these same data gaps also plague the source control FS. This prevents EPA from determining the nature and extent of the threat posed or evaluating proposed remedies.

Response: The "data gaps" are of a quite different nature than the commentor has implied. Data indicates that releases from the site are uncontrolled; and knowledge to site conditions indicates the situation will worsen.

Data is inadequate to determine the appropriate remedy for contaminants that have already left the site or the extent of cleanup required for surface mixing areas which may remain contaminated. However, it is EPAs opinion that the existing data is adequate to allow development of a source control Feasibility Study. The blanket statement that these inadequacies plague the FS was not supported with examples by the commentor. And in the conduct of the FS, EPA has certainly not felt itself to be "plagued" by this or any other lack of information.

AR0001916

C) EPA COMPLIANCE WITH THE NATIONAL OIL AND HAZARDOUS SUBSTANCES POLLUTION CONTINGENCY PLAN (NCP), 40 CFR PART 300*

Several commenters questioned EPAs compliance with the NCP during conduct of response action at Hardage. The comments ranged over many points of the NCP, but were centered on Subpart F - Hazardous Substances Response.

General comments were that EPA had not adequately characterized the site; the screening of remedial alternatives was flawed or biased; an operable unit approach is not valid for Hardage; applicable or relevant and appropriate requirements for protection of public health or welfare or the environment were incorrectly applied or should not have been applied at all; EPA should have further considered waivers provided in the NCP and further evaluated those alternatives providing less than adequate protection of public health and welfare and the environment; and cost-effectiveness was not given adequate consideration.

One important purpose served by the NCP is to provide consistency in application of CERCLA from one site to another and from one Regional program to another; and deviations from the NCP could possibly reduce this consistency. The current NCP was followed at all points through the FS process; and compliance with the NCP was a major factor in review of drafts of the FS. Where formal guidance documents and memos covering compliance with the NCP existed, the material was used. As a result, EPA believes that the FS is entirely consistent with the NCP.

Response to specific comments is given below.

6

Comment: EPAs failure to perform a formal RI is inconsistent with the NCP since: 1) the NCP does not suggest EPA may decide not to conduct an RI when one is clearly appropriate; and 2) the data collected does not serve the purpose of a RI.

Response: The NCP directs that EPA shall "as appropriate" perform an RI/FS. This passage does not bind EOA to do an RI if it is not appropriate. EPA determined that a discrete RI was not appropriate in light of the already extensive data compiled on the site. The purpose of an RI/FS, as explained in the nature and extent of the threat presented by the release and to evaluate proposed remedies (50 Fed Reg). This purpose has been met.

*The NCP was promulgated, and is periodically revised, as required by CERCLA, Section 105. The NCP sets forth the approach to be used in implementing CERCLA. The most recent revision of the NCP was February 18, 1986 (50 Fed. Reg. 47912-47968.

On the other hand, EPA believes that the aggregate of prior studies and data on the site, when combined with its "Field Investigation and Data Summary Report", would in fact constitute a record of substantial equivalence to a discrete RI. Therefore, the decision was made to move directly to the FS.

EPA must make decisions on how to proceed in cases such as this based on the best judgement of the RSPO and EPA managers, and it has acted in a manner not inconsistent with the NCP in deciding against the additional investment in time and effort an RI would have involved. The commenter does not elaborate on why a descrete RI was "clearly appropriate" on this site.

Comment: The FS is not the functional equivalent of an Environmental Impact Statement (EIS) as required by the National Environmental Policy Act of 1969 since the FS does not contain a cost/benefit analysis.

Response: Conduct of a cost-benefit analysis is not required under CERCLA; this is confirmed by the Act's legislative history (136 Cong. Rec. §16427 (1980).) Furthermore, the public comment period on the FS serves the opportunity for comments required under NEPA prior to expenditure of public funds.

Comment: The five waivers applying to remedy selection as set forth in the NCP Section 300.68 (i)(5) should be applied and a remedy selected which does not meet or exceed applicable or relevant and appropriate requirements for protection of public health or welfare or the environment, due to the high cost of remedial actions meeting these requirements or due to other circumstances set out in the NCP.

Response: The five waivers are stated below along with the reasons they cannot be applied to the Hardage site.

1) Remedy will become part of a more comprehensive remedy - This is the final remedy for source control.

1

- 2) Fund-Balancing This test is normally applied where there is a fundfinanced response. This is an enforcement lead site; but there is nothing to indicate fund balancing would be involved even if this were a fund-financed response.
- 3) Technical Inpracticality Remedies meeting requirements are technically feasible and can be implemented.
- 4) Unacceptable Environmental Impacts This is not anticipated since the impacts of continued release out weigh those associated with remedial action.

Enforcement action where the fund is not available, public desire for cleanup is strong, and litigation would probably not result in a better remedy - EPA believes that, if necessary, litigation will produce the desired result and fund may be available. It should be noted that Hardage/Criner is a National Priority List (NPL) site, so the Superfund may be applied to remedy the site if the Agency chooses.

For the above reasons, the waivers will not be applied; and the selected emedy will comply with all applicable or relevant and appropriate requirements.

Comment: Consideration of incineration as a disposal option violates the cost-effectiveness requirement of the NCP.

Response: Incineration was retained for consideration since the environmental benefits of organics destruction compared to waste treatment and landfilling are significant. EPA believes consideration of waste destruction alternatives, such as incineration, is warranted and that the failure to consider waste destruction would be contrary to the Agencies commitment to consider permanent remedies including those which exceed applicable or relevant and appropriate requirement

Comment: Scoping of response actions was not conducted in accordance with Section 300.68(e) of the NCP.

Response: EPA believes that it in fact has properly considered all of the scoping factors required by Section 300.68 of the current and former NCP, as appropriate. Other comments on compliance of the FS with the NCP are addressed in the following section.

D) The FEASIBILITY STUDY (FS) PROCESS

Comments were received to the effect that the technology screening, alternative development and screening, and other components of the Feasibility Study process were flawed due to a lack of data or non-compliance with the NCP.

While it is true that a lack of adequate data could bias the results of the FS by forcing the preparers into unwarranted assumptions, the discussion provided in Section A of this summary regarding what constitutes "adequate data" is referenced. And, as in response to comments in that previous section, it is again stated that EPA believes the data is adequate for the purpose of a FS on Source Control. The data may not be adequate for detailed design; but that is not the present objective. The purpose of this FS is merely to present analysis and discussion sufficient for selection of a permanent remedy for source control.

Comment:

"(EPA) has rejected alternatives found to be protective of public health and welfare and cost-effective at numerous other Superfund sites". This commenter expressed the opinion that EPA had inappropriately rejected inplace containment alternatives. The commenter went on to cite 15 Superfund sites in other Regions which they felt were in conflict with the remedies considered at Hardage. These sites are:

Region #1	Beacon Heights Lanfill, Connecticut; McKin County (Landfill), Maine;
Region #2	Love Canal, New York; GEMS Landfill, New Jersey; Sinclair Refinery, New York; Helen Kramer Landfill, New Jersey
Region #3	Heleva Landfill, Pennsylvania; Lackawana Refuse, Pennsylvania; Taylor Borough Dump, Pennsylvania Douglasville Disposal, Pennsylvania
Region #4	White House Waste Oil Pits, Florida
Region #5	Wanconda Sand & Gravel, Illinois New Lyme Landfill, Ohio
Region #10	Ponders Corner, Washington South Tacoma Channel, Washington

(No sites were referenced in Region #6, where Hardage/Criner is located.)

Response:

At this time, there are hundreds of sites on the Superfund National Priority List. These sites present unique combinations of factors involving geology and hydrology, as well as the age, quantity, and chemistry of contaminants, among other things. For this and other reason, neither Congress nor EPA has ever taken the position that consistency between or among Superfund sites is the measure of the appropriateness of Superfund remedial action at any given site. The specific test upon which basis Superfund remedial actions are judged is their consistency with the NCP. In numerous policy promulgations. EPA has attempted to further clarify those principles which guide Superfund response efforts. The policy and guidance documents have changed during the past six years of Superfund implementation; and they will continue to evolve and expand their scope in the future, reflecting a predicted increase in the body of knowledge concerning contaminant chemistry, health and environmental effects, contaminant fate and transport, and waste control, treatment, and destruction technology, among other things. As addressed elsewhere within this responsiveness summary, as well as within the FS itself, EPA believes that its remedial action proposals are not inconsistent with the NCP as discussed in the previous section of this Responsiveness Summary.

For informational purposes, a brief summary of characteristics, differences, and similarities of the 15 indicated sites vis-a-vis the Hardage site is presented below, along with a summary comparison of their respective remedies. As the information presented suggests, the commentator's point is at best overly simplistic and factually inaccurate. Review of these sites readily shows why capping may be an acceptable component of the remedies (just as capping may be included in the second operable unit at Hardage). The 15 sites referenced can generally be broken into four categories as discussed below:

Contaminated Municipal Landfills:

Beacons Heights, Heleva, Lackawana, Taylor Borough, New Lyme, and Wauconda fall into this category. Such sites are characterized by relatively minor amounts of hazardous materials co-mingled with large volumes of municipal trash. In this type of situation, wastes are of a far different nature than the highly concentrated wastes at Hardage.

261

Capping of wastes in-places was used only on two sites, Beacon and New Lyme. At New Lyme, little or no groundwater contamination has occured or is likely due to hydrogeology. At Beacon Heights, contaminants are dispersed and removal is not feasible. Two other sites, Lackawana and Taylor, utilized capping only after partial waste removal. In both cases, well defined concentrations of drums were present and were removed; the wastes capped were almost exclusively municipal in nature. One site, Wauconda, used a cap as an interim measure. The purpose of the cap was to control surface seepage to a stream.

Waste, Oil Recycling/Refining Operations:

The McKin, Sinclair, Douglasville, White House, and South Tacoma sites fall into this category. At such sites, the principal concerns are open pits of liquid waste and waste spills. Spills represent dispersed waste for which removal would rarely be a feasible option. Pits are drained on most such sites, resulting in almost total source removal. At all five sites noted above, emergency or remedial actions included partial or complete source removal followed by capping of contaminated soils in former source areas. This is analogous to the proposed removal of source areas and possible capping of the former pits at Hardage.

Hazardous Waste Landfills:

 \cdot

The Love Canal, GEMS, and Helen Kramer sites are in this category. Hardage is similar to these sites only in the respect that similar waste types were disposed. At Helen Kramer and Love Canal, barriers to vertical migration exist. The layers make slurry wall cut-off feasible; sands overlying the aquitards lend themselves to easy construction of the wall and simple and effective groundwater management. At the GEMS site, no shallow layer is present; however, a thick sand layer allows effective groundwater management. In addition, drummed liquids are not present as they are at Hardage.

Presented below is a brief summary of site characteristics, differences and similarities between the site and Hardage.

Beacon Heights Landfill Region #1 #203 on NPL

Beacon Falls, Connecticut

- municipal/industrial waste landfill operated 1920-78
- little drummed or other waste remains; most waste was burned as it was received and only its residues remain
- groundwater is contaminated in fractured bedrock

Remedy-Upgrade cap; groundwater decisions deferred

Comparison to Hardage:

Similarities - fractured bedrock underlies both sites

Differences - The majority of waste once disposed at Beacon Heights is municipal. Little waste remains in its original location, most has been burned or already released to the groundwater system.

Remedial Elements:

The sites are not comparable since a well-defined source is present at Hardage; and the sources at Beacon Heights are dispersed, making source control inappropriate.

McKin County (landfill) Region #1 #33 on NPL

Gray, Maine

- waste oil recycling site operated in the late 1970s
- soils are heavily contaminated by spills of solvents
- all surface tanks and druns have been removed;

Remedy:

Soil contaminated above the clean-up level (11,000 cubic yards) will be excavated; soil will be aerated and the off-gas burned; capping will be over areas below the clean-up level

Comparison to Hardage:

Similarities - solvents contaminate both sites

Differences - McKin was a recycling as opposed to disposal facility; no drummed wastes remain on-site

Consistency with removal at Hardage:

In both cases wastes will be excavated and properly disposed. McKin is farther along in remedial process (cleanup levels selected already) but the remedies appear entirely consistent.

. . .

GEMS Landfill

Region #2

#12 on NPL

Gloucester Township, New Jersey

- industrial waste landfill operated from 1970 to 1974
- solid and liquid waste was mixed in pits; few or no drums were disposed
- 6 million cubic yards of contaminated fill present
- 150 feet of permeable sands underlie site, making groundwater recovery feasibile

Remedy:

Cap site; pump and treat groundwater to remove leachate and lower water table below wastes

Comparison to Hardage:

Similarities - similar wastes present

Differences - No drums are in the fill at GEMS. Geology makes groundwater management a feasible and effective method for intercepting seepage near the source, unlike at Hardage.

Remedial Elements:

At Hardage, drummed liquids are present in the fill and the underlying interbeded and fractured bedrock does not lend itself to groundwater management. These complicating factors make the remedy used at GEMS inappropriate for Hardage.

Helen Kramer Landfill

Region #2

#4 on NPL

Mantua Township, New Jersey

- industrial waste landfill operated from 1970 to 1980
- 2 million cubic yards of waste
- all types of waste are present including drummed wastes
- * the site is underlain by a shallow sand aquifer and a deeper aquitard.

201

45000192

Remedy:

Cap the fill; install a slurry wall upgradient and a collection trench downgradient, both with their base tied into the aquitard.

Comparison to Hardage:

Similarities - drummed and bulk wastes in industrial type fill

Differences Containment of the wastes directly beneath the site is feasible due to the presence of a barrier to vertical migration at Helen Kramer.

Remedial Elements:

The lack of a barrier to vertical migration at Hardage prevents effective containment in place as is possible at Helen Kramer.

Ponders Corner

Region #10

Tacoma, Washington

- dry cleaner dumped sludges on the companies property
- solvents have contaminated groundwater
- sludge piles (sources) were previously removed by the State of Washington

Remedy:

Air stripping towers are in-place on municipal wells and are serving the dual purposes of groundwater collection and treatment; limited excavation with off-site is disposal planned for the most heavily contaminated soils.

Comparison to Hardage:

Similarities - solvent contaminated groundwater

Differences - Little of the source remains, most is dispersed into groundwater system or previously removed; collection and treatment of groundwater is feasible;

Remedial Elements:

h

The contaminant source at Ponders Corner has dispersed from it's original location, making source control inappropriate. For this reason the sites are not comparable.

Love Canal

Region #2

#136 on NPL

Niagra Falls, New York

- * abandoned canal was backfilled with industrial wastes and closed in 1952; 21,0 tons of wastes including drums are in the fill
- low-level contamination is present in several media
- canal excavated in sand overlying plastic clay and till; situation allows containment in place

Remedy:

Cap was upgraded; slurry walls installed, tied into clay layer; groundwater collection and on-site treatment system in-place; further studies are under way due to concern over vertical migration of leachate to bedrock and the possible inadequacy of in-situ containment.

Comparison to Hardage:

Similarites - drums in fill: similar contaminants

Differences - low-level contamination outside the canal as compared to Hardage; containment is feasible due to geology

Remedial Elements:

The shallow clay layer beneath Love Canal is thought to allow waster to be contained beneath their original location; however, the adequacy of this layer is still being evaluated. The lack of such a layer at Hardage prevents consideration of such containment.

Sinclair Refinery

Region #2

< + ~

#117 on NPL

Wellsville, New York

- * former refinery operation with two on-site landfills; soil was contaminated by spills
- fill contains principally bulk wastes
- * small fill area (2 acres and 10-15 feet thick) is adjacent to a river and is being eroded; larger fill has a clay liner
- groundwater contamination is present but believed to result from spills on the site rather than releases from the landfills

AR000191

Remedy:

Excavate the small fill areas, consolidate with the larger landfills and cap; groundwater will be addressed in other operable units

Comparison to Hardage:

Similarities - Removal is part of the EPA remedy on both sites.

Differences - Groundwater contamination is primarily from spills and already dispersed contaminants rather than the fill or concentrated source areas.

Remedial Elements:

The landfills at Sinclair are not leaking; at Hardage they are. For this reason, source control at Sinclair only needs to stabilize wastes against flooding and erosion. If necessary, groundwater management would likely be feasible in the river aquifer.

Heleva Landfill

Region #3

#162 on NPL

North Whitehall Township, Pennsylvania

- low level solvents comingled with sanitary waste
- "source" of off-site contamination appears to be contaminated groundwater beneath the landfill itself
- little or no drummed waste is believed present

Comparison to Hardage:

Similarities - Similar contaminants observed off-site

Differences - Little free liquid appears present in the fill at Heleva, while a large source is present at Hardage.

Since contaminants have generally left the Heleva fill.

Source control is not appropriate

Remedy:

Capping with groundwater pumping and treatment

Remedial Elements:

At Heleva, the "source" of contamination has generally entered the groundwater system. This type of situation is best remedied by removing the contaminated groundwater. Since a large volume of free liquids is not present in the fill at Helelva, capping was assumed adequate to prevent further contamination of the groundwater. Such a system is not adequate at Hardage due to the physical differences between the sites noted above.

207

Lackawana Refuse

Region #3

#453 on NPL

Old Forge Borough, Pennsylvania

- sanitary landfill operated through 1976; fill was in old coal pits
- * 10,000 drums dumped in one pit over 4 months in 1976
- geology makes the groundwater contamination threat to the public miminal

Remedy:

Remove all drums from pit and dispose off-site; cap former pit area Comparison to Hardage:

Similarities - drummed wastes present; removal is part of the EPA remedy Differences - groundwater contamination is less extensive than at Hardage

Remedial Elements:

Hazardous materials will be removed from both sites; at Lackawana the municipal wastes will be capped. The remedies are consistent since, in both cases, the wastes will be excavated and properly disposed.

Taylor Borough Dump

Region 3

#635 on NPL

Taylor Borough, Pennsylvania

- municipal/industrial landfill
- site consists of six distinct areas with varying degrees of contamination
- drums are present in some parts of the fill
- the decision on groundwater issues has been deferred to a later operable unit

Remedy:

Remove all drums; cap areas of surface contamination and municipal fill Comparison to Hardage:

Similarities - drummed waste present; removal is part of the EPA remedy

Differences - surface contamination will be capped at Taylor, while its disposition at Hardage has not yet been determined.

Remedial Elements:

Concentrated areas of source materials have been or will be removed on both sites. The hazardous wastes at Hardage will be dealt with in the same general manner as were similar wastes at Taylor. For this reason, the remedies at both sites appears consistent.

Wauconda Sand & Gravel

Region #5

#126 on NPL

Wauconda, Illinois

- municipal landfill operated from 1940s to 1979
- * less than 3% of the 5 million cubic yards of waste is hazardous/industrial
- * fill is in abandoned sand and gravel pit
- * groundwater contamination is negligible

Remedy:

Interim remedy is a cap to prevent surface seepage into a nearby stream. Further study will be done on the groundwater operable unit.

Comparison to Hardage:

Similarities - Both sites have been split into operable units.

Differences - Hardage accepted almost exclusively industrial and hazardous wastes; Wauconda has only a very small percentage of this type waste. Groundwater has been contaminated at Hardage, unlike Wanconda.

Remedial Elements:

Factors making waste excavation necessary at Hardage are not present at Wauconda. Specifically, Hardage contains a large volume of hazardous substances which have been and continue to be released and extensive groundwater contamination is not a driving force behind remedial action at Wauconda. Source control and the cap are prinicpally directed at controlling surface seepage. Such differences make comparison of the sites difficult.

New Lyme Landfill

Region #5

#626 on MPL

Ashtabula County, Ohio

- municipal landfill which accepted industrial waste
- little is known on volume or types of waste
- * little groundwater contamination
- if necessary, groundwater management is probably feasible

203

VF0001938

 groundwater discharge (up-flow) controls local hydrogeology and protects groundwater below fill

Remedy:

Construction of a RCRA compliant cap over the fill.

Comparison to Hardage:

Similarities - Relatively small amounts of some wastes disposed at Hardage are present at New Lyme

Diffences - Little groundwater contamination compared to Hardage site.

No significant amounts of industrial waste was disposed at
New Lyme.

Remedial Elements:

The groundwater flow system at New Lyme acts to prevent seepage out of the landfill. Since such a natural system is present, groundwater is not extensively contaminated and a large liquid/sludge source or contaminants is not present, source control is relatively straightforward. If necessary, groundwater management would likely be feasible unlike at Hardage. The sites are generally not comparable.

White House Waste Oil Pits

Region #4 #132 on NPL

Whitehouse, Florida

- waste oil recycling facility
- Emergency Response cleaned out pits and capped the pit areas
- * groundwater contamination present

Remedy:

Repair caps; install slurry wall and pump and treat groundwater.

Comparison to Hardage:

Similarities - groundwater contamination; waste removal was integral to remedy

Differences - waste source areas have already been removed at White House; and geology makes groundwater management feasible

R medial Elements:

I : site remedies are quite similar. In both cases, the source areas were rowed. The capping and slurry wall at White House are similar to mossures which could be considered, for the second operable unit after the sources have been removed.

Douglasville Disposal Region #3 #103 on NPL

Douglasville, Pennsylvania

- oil recycling facility;
- site is located adjacent to river and subject to flooding
- in previous actions, drums were removed; lagoons cleaned out and sludges land farmed on-site; spills have contaminated site
- groundwater and soils are contaminated
- river alluvium underlies site; slurry walls are feasibile to cut off lateral flows

Remedy:

Cap site; and build flood control levee; a slurry wall may be part of the groundwater remedy

Comparison to Hardage:

Similarity - groundwater and soil contaminated

Differences - former oil recycling facility; source areas have already been removed; groundwater management is feasible

Remedial Elements:

Source areas have been or will be removed on both sites; the remedies are consistent in that similar wastes are handled in a similar manner (i.e. excavate and treat hazardous wastes).

South Tacoma Channel (Commencement Bay) Region #10 #11 on NPL Tacoma, Washington

- waste oil recycling and tank clean-out facility operated in 1960s
- * filter cake containing tetrachloroethylene (PCE) was used as fill soil
- contaminants from spills are dispersed in the soil and underlying aquifer

Remedy:

Excavate hot spots of PCE and install vapor extraction points in the ground. Continue air-stripping water in a nearby municipal well.

Comparison to Hardage:

Similarites - groun:water contamination

Differences - sourc- of contamination is spill areas which have already dispessed into the groundwater system; groundwater manageent is feasible.

Remedial Elements:

At South Tacoma, the waste is dispersed and source control is not applicable. The cap in this case has a very specific and limited purpose, to allow solvent vapor extraction.

Other comments related to the Feasibility Study process are as follows.

Comment: "A rotary kiln incinerator has the potential for incinerating the site wastes, but its feasibility has not been demonstrated." Process upset could result in the emission of dioxins and furans. The mixture of wastes present would pose problems over and above those associated with a costant waste stream.

Response: Incineration of the <u>specific mixture</u> of wastes present at Hardage has not yet been demonstrated. However, the types of waste present have generally been destroyed in this manner. The problems cited contribute to the cost of over \$300 million estimated for incineration alternatives. Bench tests and possibly pilot studies would be essential to the remedial design as would be emissions testing.

EPA considers incineration on virtually all Superfund sites where organic contamination exists. It is never stated that the construction and operation of an incinerator would be simple, only that at this point it appears feasible, and warrants consideration due to it's benefits.

Comment: Incinerator ash may be eligible for de-listing as a RCRA hazardous waste on a site specific basis.

Response: If treatment of ash removes the characteristics of a hazardous waste (primarilly EP Toxicity in this case), the ash may be eligible for delisting. Based on a risk-assesment, delisting could be considered after it is demonstrated that the above criteria could be met.

Comment: On-site incineration provides no time advantage over off-site incineration, since the off-site treatment won't take 10 years as assumed in the FS.

Response: The 10 year figure was based on current backlogs for existing units. While capacity may increase in the future demand will also increase. Reduction of the 10 year figure is not warranted at this time.

Comment: Groundwater recovery (pumping) would be feasible in the bedrock and should not have been eliminated from consideration.

Response: The commenter has ignored the extensive data collected indicating fracture zones, uniformly in yield, and the fact that wells pumping from fractured bedrick will produce a small cone of depression. For this reason, withdrawl wells would have to be closely spaced and very dee , creating an large quantity of

Although the system would still allow substantial releases as described in the FS, groundwater recovery by withdrawl from a collection trench system as described in Alternatives 4 and 5, was deemed feasible.

Comment: Technologies for reuse or recycling of waste should have been considered, particularly "Basic Extraction Solvent Technology" (BEST) as employed on the Savanaha site in Georgia.

Response: As noted in the FS, the extreme variability of the wastes at Hardage virtually eliminates the use of known reuse/recycle alternatives. Solvents Extraction is quite useful where wastes are homogerous liquids. However, the waste stream at Hardage is highly varied and much is a high density sludge. The application of solvent extraction to high solids content wastes will only result in a minimal reduction in volume to be dealt with. Reuse/recycle treatments will be considered for certain wastes if technologies become apparent of are developed.

Comment: If the site had been operated after 1980 then capping would have been an acceptable measure for closure under RCRA. Yet EPA states that capping is not viable enough to even consider as an acceptable remedy.

Response: The site was not operated after November 1980, partially due to the operators inability to meet new requirements for hazardous waste land disposal facilities which went into effect at that time. Facilities which legally operated after November 1980 presumably were better managed with at least some safeguards built in. In some cases this may make capping adequate for containing the wastes. The Hardage facility had no such safeguards and bedrock has been found to provide inadequate barriers; therefore, simple closure in-place is not acceptable. (Note: The commenter went on to argue against the application of other provisions of RCRA as applicable or relevant and appropriate requirements).

Comment: The factors used to screen all alternatives and eliminate several were inconsistent with those dictated by the NCP. If the appropriate factors had been applied, then the FS might have reached different conclusions.

Response: Section 300.68(g) of the NCP states that, "Three broad criteria shall, as appropriate, be used in the initial screening of alternatives." The three "broad" factors to be used are cost, acceptable engineering practice, and effectivess. The ranking factors used in screening of alternatives in the FS were:

reliability, implementability, safety, environmental, institutional and cost. The factors considered fell in the broad categories listed in the NCP and are consistent with the screening factors listed in EPA's FS guidance.

Comment: The alternatives which should have been retained for further consideration in the FS were Alternatives: #3-Capping, #5-capping with perimeter drains, #7-On-site landfill, and #10 Off-site disposal.

Response: The commenter suggest considering two alternatives which EPA rejected (#3-Capping and #5- Capping with Perimeter Drains).

Documentation for rejection of alternatives numbered 3 and 5 is provided in the FS on page 3-27,28 and 3-29,30 respectively. The principal reason for rejecting these alternatives is their inability to significantly reduce the release of leachate into the groundwater system.

The commenter also suggest rejecting two alternatives which EPA retained (#8- On-Site Incineration and Disposal and #9-On-Site Incineration/Offsite Disposal). EPA disagrees with the commenter. Congress, in the 1984 ammendments to RCRA, has determined that land disposal of soils contaminated with certain wastes, including many solvents, should be banned, although a two year extension is provided for CERCLA response actions. Prior to such regulation, some facilities may be hesitant to accept a large volume of waste with bans pending on it. Destruction of organics is an enormous benefit, in that the destroyed compounds will no longer be capable of posing threats to the public or environment.

EPA is specifically directed by the NCP to consider alternatives exceeding requirements. Incineration falls into this category and the benefits may prove commensurate with the costs; therefore consideration of incineration is appropriate.

Comment: The adverse effects of waste excavation were not considered.

These may pose unacceptable environmental impacts and be grounds for selecting an in-situ alternative not meeting requirements.

Response: The hazards associated with excavating the site were recognized in the FS. It is believed that releases to all media except air, can be readily controlled. Releases to air will be minimized by dust control measures, handling and excavation techniques aimed at minimizing the volume of waste in the open at any given time, and possibly placement of a temporary structure over the waste excavation. Air monitoring will be performed and the potential threat to adjacent residents will be monitored throughout operations as will be the potential need for their immediate evacuation. Threats to workers are mai; but this is the reason for extensive safety precautions an health monitoring.

Comment: A risk assesment should have been performed on the Hardage site.

Response: A preliminary Public Health Assessment has been prepared and will be supplemented as further data is obtained.

Comment: The detailed development and analysis of alternatives presented in the FS is inadequate and may not allow selection of the most appropriate remedy from the four finalists.

Response: Section 300.68(h)(2) of the MCP sets out the factors to be included, as appropriate, in the detailed analysis. These factors are: 1) refinement and specification of alternatives; 2) detailed cost estimate; 3) engineering evaluation of effectivness, implementability, and constructability; 4) assessment of effectiveness of remedy in meeting remedial objectivies; 5) analysis of alternate technologies; 6) analysis of costs of adverse impacts and their mitigation.

These factors were addressed, as appropriate, and alternatives were refined in sufficient detail to allow selection of an appropriate remedy. The development is not to a design level, but it is not intended to be.

Comment: The findings of fact and conclusions of law arrived in 1982 by the U.S. District Court in Oklahoma City concerning the site should not have been relied upon to develope a remedy.

Response: The findings and conclusions were not used in the FS in the manner that the commenter suggested was the case. The facts which led to development of these findings and conclusions have for the most part been supported by data obtained since 1982, and have therefore been properly considered, along with other relevant investigative and factual information concerning the site. EPA did not mean to imply that these findings and conclusions had to be taken at face value, as they certainly were not during the FS but were re-examined as appropriate.

E) OPPORTUNITY FOR PUBLIC PARTICIPATION

Comments were received which indicate some parties feel EPA should have made a greater effort to involve those parties potentially liable for the site in development of the FS and should have allowed more extensive comments on the FS. The NCP as well as current EPA policy is cited as support for this argument.

Mhere appropriate, EPA will generally involve PRPs in studies and development of response actions. The reasons for this are numerous, not the least of which is the previous experience of the Agency which suggests that those parties most directly involved in studies and most familiar with the rationale for EPA decisions will be most willing to participate in voluntary clean up. At the Hardage/Criner site, the enforcement policy documents which recommend PRP participation in the RI/FS were appropriate, had not been promulgated by EPA at the time the FS was committed. In addition, a PRP search had not yet been completed. For this reason, PRPs were not involved from the outset. In December 1984, an initial group of nearly 300 PRPs was notified of their potential liability on the site. Since that time, approximately 135 parties have formed the Hardage Steering Committee (HSC).

EPA has met with HSC often since its formation. Final documents have been provided in a timely manner; and over 200 requests for documents and information have been answered in writing under the Freedom of Information Act since early 1985. Communication has been frequent between both the technical and legal staffs and have been as open as the enforcement nature of the site allows.

Comment: EPA refused to afford HSC the opportunity to participate in development of the RI/FS. These actions violated EPAs own guidelines including the March 20, 1984 memo from Lee Thoms, "Participation of PRPs in development of RI/FS under CERCLA and the draft CERCLA Settlement Policy".

Response: The March 20, 1984 memo indicates that PRPs may be allowed, to where appropriate, to conduct the RI/FS under an EPA approved scope of work and under a formalized agreement such as a Consent Decree. This policy in no way requires or indicates that EPA will abandon on-going studies merely to allow PRP conduct of an RI/FS. Regional experience has been that when conduct of an RI/FS has been switched from one EPA contractor to another, significant delays result. Even greater delays would be expected in transfer of the RI/FS to a party out-side the Agency. In addition, previous activities of HSC have not indicated that an FS could have been completed by them more rapidly than by EPA. The Hardage Steering Committee had not been organized at the time the FS was initiated in January 1984; aside from this purley practical reason for not allowing HSC to conduct an RI/FS, other factors enter into this situation.

The draft "CERCLA Settlement Policy" referenced to in the comment was issued October 4, 1985, and does not constitute EPA policy. Instead, EPA's settlement policy is contained in the Interim CERCLA Settlement Policy as set forth in the Federal Register on January 5, 1986. At this time the FS was in its later stages of development.

Comment: Insufficient time was allowed for comment on the FS. The document is extensive and detailed, thus a comment period substantially longer than the minimum three weeks required by the NCP would have been appropriate.

Response: There was a 5 week comment period on the FS; this included a 15 day extension requested by HSC. addition, the FS was placed in repositories and provided to the HSC two weeks before the formal comment period began, providing a total of approximately seven weeks for interested parties to review and comment on the FS. While EPA and its contractor did spend approximately eight months compiling the 200 page FS, all data from which this FS was compiled has been available to the public from the time EPA began the FS in mid-1985.

Comment: EPA must afford the HSC an opportunity to finalize and present its own response plan before selecting a remedy.

Response: EPA has repeatedly been told that HSC is or will be preparing some type of response plan. Unfortunantely this work has never been produced, forcing EPA into the conclusion that such work may not be done even if EPA were to wait. Any response plan submitted to EPA will be considered, as have all proposals, documents, advice, and comments in the past, provided such a plan is received in a timely fashion. EPA guidlines and regulations do not, as the commenter states, require EPA to afford the HSC an opportunity to finalize and present this plan.

F) RECOMMENDATION FOR ADDITIONAL STUDY AND/OR INITIAL REMEDIAL MEASURES

The commenters have proposed a general plan for additional studies which in their opinion, should be conducted prior to selection of a remedy for the site. These studies would supplement EPA work and be aimed at developing a RI/FS for both operable units of the site.

These commenters have also proposed to conduct initial measures aimed at site stabilization. These measures would mainly included:

- 1) fencing of the entire property.
- 2) construction of a temporary cap and collection system for surface seeps
- monitoring of drinking water supplies and construction of alternate water supplies if necessary.

EPA feels that some of the study items suggested by the commenters are appropriate. Some of the additional study items and are being considered by EPA as necessary components of studies for the second operable unit. EPA sees no purpose in rethinking its previous decision to split the site into operable units.

The proposed "removal" actions have also been considered by EPA. An EPA site assessment team was dispatched to the site in June 1986 and, following the teams report, action will be taken as necessary.

G) OTHER COMMENTS

Comment: Has EPA considered incineration and disposal of the entire waste volume at Hardage through underground injection. In this area, formations below 3000 feet often show caverns which take enurmous amounts of fluids and cannot be plugged by addition of sealant or bridging materials.

Response: Two problems would be presented by disposing wastes in the fashion suggested: the actual ability to do this and the legal and permitting constraints.

The physical problems with injection would be significant. The volume of wasta considered for disposal is roughly 179,000 cubic yards, or 36 million gallons, of soils and sludge. To allow injection, the waste would have to be slurried with water, forming a volume in exess of 100 million gallons of waste slurry. While this volume could theoretically be injected in the space of a few weeks, the enormous volume of solids would likely clog cavities rapidly, requiring construction of several wells over an area significantly larger than the site.

Considering the type of waste found at Mardage, it is unlikely such injection wells would be permitted by EPA or the State of Oklahoma.

Comment: EPA should select the On-site incimeration/Off-site Disposal Alternative. This is the only way to achieve a permanent remedy for the Hardage site. Several commentors expressed this sentiment; one felt that the On-site incineration and disposal plan would also be adequate.

Response: EPA favors an on-site disposal plan due to several factors including:

1) the volume of waste present;

2) hazards associated with off-site transport;

- 3) questionable availability of an off-site disposal facility; and
- 4) the fact that an off-site plan merely shifts hazards to another location and population.

EPA will give appropriate consideration to the incineration options. The decision will be available for public comment before being finalized as a Record of Decision.

Comment: Incinceration should not be selected since 100% destruction of compounds such as 2,3,7,8 - tetrachlorodibenzo -p-dioxin (TCDD) cannot be achieved. In addition, particulates should be sampled prior to emmission to the air.

Response: 100% destruction of anything can never be achieved. Incinerator testing by EPA in Missouri has in all cases achieved greater than 99.999% destruction of TCDD and has effectively destroyed even hard to burn compounds such as carbon tetrachloride. EPA sets limits on particulate emissions by incinerators and these solids would be analyzed in test burns and periodically throughout the operations.

Comment: The waste could be disposed as follows:

- seperate water/solids by settlingdispose the water in an injection well
- * heat the solids to dry them
- * seal the solids in a plastic/cement "casket" and bury
- dispose the dirt in another manner

This plan is, in some ways, similar to the on-site disposal option. The waste treatment and handling techniques have not yet been finalized. These comments and plans will be considered in the design phase of remedial planning.

Comment: Do provisions exist for indemnifying contractors involved in remedial work on Superfund sites from possible future liability under CERCLA for hazards arising from the site at some time after this work is completed.

Response: Under current law, the contractor cannot be indemnified even for actions carried out at EPAs direction. Provisions for contractor indemnification will likely be in revised CERCLA statutes being developed Congress.

Comment: EPA should have more thoroughly investigated deep bedrock to identify existing contamination and evaluate the potential for contamination in the future. This needs to be done since it is contamination of deeper ground water and transport through that flow regime which has the potential to affect populations not in the immediate vicinity on the site.

Response: One of the key purposes of the Management of Migration RI/FS will be to define the long-term potential for migration along pathways such as the deeper groundwater. Three wells drilled on-site to depths of 200 feet or more showed no contaminants at detectable leve's.

П

APPENDIX G

DETAILED COST ESTIMATE FOR THE SELECTED REMEDY

HARDAGE INDUSTRIAL WASTE SITE CRIMER, DULANGHA EPA REMEDY WITH EXCHAPTION OPTION

ITEN	QUANTITY	unit Measure	UNIT	EXTENDED COST	
Section 3 - DETAILED REVERY DESCRIPTI	ON				
1,1 Source Removal & Control					
3.1.1 Liquids Resoval and Disposal DRAW REMOVAL					
Equ: paent					
Tracked Excavator (1-CY)	16	HOS	15, 650	#90, 400	
Tracked Escavator (2-CY)	16	HOS	8,000	128,000	
Vacuus Truck	16	106	11,040	176, 540	
Forklift (2 units)	×	HOS	1,517	46, 544	
Backhoe (2 units)	R	HOS	2,725	87,200	
Dump Trucks (6 units)	%	MOS	3,050	252, 800	
Flat But Truck (2 units)	22	105	755	24,150	
Pickup Truck (2 units)	R	HOE	210	16, 320	
Support Equipment	1	LS	112,000	112,000	
Air Emissions Control					
<u>Squipment</u>	P	HOS	1,000	32,000	
Meterial	368	DRYS	300	110, 400	
Labor					
Formen (16hr/day s 2 mm)	11,776	HIS	35.00	412, 160	
Equip Operators (16 hr/day					
z 6 mm)	25, 228	HES	31.50	1,112,832	
Truck Drivers (16 hr/day x					
6 semi	E, 24	HES	2.60	904, 397	
Laborer (16hr/day x 2 mm)	25, 324	HPS	24.60	863, 069	
Industrial Hygiene Tech					
(16 hr/day s 2 mm)	11,776	HES	2.00	37K, 832	
Health/Safety Equipment					
- Class A	7,360	HH-DY	135.00	993,600	
- Class B	LAR	101-DY	75,00	662, 400	
	•		•		
Total					46, 449, 754
DRUPPED WASTE STAGING/CONGOLID	ATION AMER	1			
Site Smading	2,047	CY	10. %	11,965	
Beilding					
Concrete Slab	145	CY	100	33, 300	
Drum Opensing Arms	- 1	ى	14,000	14,000	
Roof Covering	10,000	¥	5. 15	51,500	
Sump Armas	1	ڪا	30,000	30,000	
Conveyor Racks	210	UF.	46	10,080	
Equipment	1	rs	182,800	182,800	

Reproduced from best available copy.

HARDAGE INDUSTRIAL WASTE SITE CRINER, CHLAHOMA EAR REMEDY WITH EXCHARTION OPTION

тө	QUANTITY	UNIT HEASURE	UNIT	EXTENSED COST	
Section 3 - DETAILED REMEDY DESCRIPTION	DN .				
3.1 Source Removal & Control					
3.1.1 Liquids Removal and Disposal					
DRUMMED HASTE STAGING/COMBOLIDA	ATION AREA	- Contin	Hall d		
Labor					
Foresan	4,632	HRS	77.00	309, 120	
Tech - Level 1 (16 hrs)	4,632	HRS	24.60	- •	
Tech - Level 1 (8 hrs)	4, 415	HFS	24.60	- •	
Health/Safety Equipment	i	LS	285, 800		
Maintenance	1	ĿS	11,400	11,400	
Disposal of Organics					
Transportation (150 trips)	75,000	#L	1.75		
Incongration	300,000	BRLS	4,04		
Discosal of Draws	i	ڪا	1,300	1,300	
Closure	1	LS	39, 200	35, 200	
Total					2, 793, 616
REPROTE STORAGE AREA					
Remote Storage Area	1	LS	\$15, 900	919, 900	19, 900
3.1.4 Soil Vapor Entraction					
SOIL VAPOR EXTRACTION					
Sitmork	1	ĻS	110,000	910,000	
D uldings					
Blower Pasiding	2,160	¥		90,000	
Egy 1 papert	•				
Blower - 9,000cfs	5	EA	41,000	205,000	
Tank - 2,000ga1	1	EA	6,000	6,000	
Piging	i	LS		600,000	
Monitoring Probes	100	EA	900	90,000	

HARDAGE INDUSTRIAL ARSTE SITE CRINER, OKLAHOMA EPA REMEDY WITH EXCAMPTION OPTION

ТЭЛ	QUANTITY	UNIT HERSLIFE	UNIT COST	EXTENDED COST	
ection 3 - DETAILED REDIEDY DESCRIPT	TION				
1: Source Removal & Control					
3.1.4 Soil Vapor Extraction					
SOIL VAPOR EXTRACTION - Conti	nund				
SUBTUTAL - Known Costs Only	,			\$1,001,000	
General Conditions 0	5% of 9	LETOTAL		67,635	
Finishes 0	15 of 9	LETUTAL		13, 527	
Electrical #	10% of 9	LETUTAL		135,270	
Instrumentation & Control	1	LETUTAL		67,635	
Yard Piping P	≤ of 9			67,635	
SLETUTAL - Percentage Costs	•		AL		
SUBTUTAL - Known and Percen		•		81, 352, 703	
Mobilization € 5% of \$LBT	UTAL - Know			67,635	
Pilot Studies	1	_	55 0, 000	55 0, 000	
SVE Start-up Services	1	LS	30,000	30,000	
Subtotal					12,000, I
AIR TREATMENT					
Sitmork	1	LS		\$10,000	
Concrete	•	_			
Slab on Brade	257	CY	200	53,400	
Equipment				•	
LP Tank - 18,000sal	1	EA	16,000	16, 000	
Blower	2	EA	30, 500	77,000	
Thermal Oxidation Unit	1	EA	\$12,000	\$12,000	
SUBTUTAL - Known Costs Only				676A, 400	
General Conditions &	54 of 91.	BTUTAL		54, 866	
Electrical P	10% of 94	BTUTAL		109, 771	
Instrumentation & Controls				54,866	
Yard Piping	9 10% of 9L			109,771	
SUNTUIAL - Percentage Costs	Only - 70%	of SUNTUI	A.		
SUBTUTAL - Known and Percent	•			81,097,714	

HARDAGE INDUSTRIAL HASTE SITE CRINER, ONLAHOMA EAR REMEDY WITH EXCAMPTION OPTION

1754	YTTNAMB	UNIT MEASURE	UNIT COST	extensed Cost	
Section 3 - DETAILED REPEDY DESCRIPT	ION				
3.1 Source Removal & Control				•	
3.1.5 Adjacent Source Removal					
REMOVAL OF ROJECTION WASTES					
North Pond Area					
Excavation	5, 800	CY	945. 15	1251, 370	
Placement under cap	5, 800	CY	11.77	44,244	
Drus resediation					
Trensport	750	Mi	175	2,813	
Incineration	1,465	BAL	4,04	5,999	
Hest Fond Area					
Exc/Yeal/Placement	63,200	CY	17.29	1,092,728	
U tr ench					
Exc/Hee]/Placement	2,704	CY	15.54	44,724	
V trench					
Exc/Hex1/Placement	11,085	CY	16.54	183, 346	
Sil trench					
Exc/Hav1/Placement	1,275	CY	16.54	21,089	
East Farm Pond \$2 (HSC)	1	LS	171,000	171,000	
East Farm Pond 82 (HSC)	1	LS	317,000	317,000	
REMEDY TOTAL				•	82, 164, 834

225

CRIMER, OKLOHOMA

EAR REPEDY WITH EXCRURITION OPTION

!TEN		EXCAVATION OPTION				
Section 3 - DETAILED MEDERY 1 Source Americal & Cone; 1 6 Source Area Capping SITE DASS Stormer	DESCRIPTION DESCRIPTION	UNIT UNIT MEASURE COST	ete o ed Oet			
Stormater Berg Artention Basin Clean Soil Placement Development Cap Basin Wills Scale Brass	5, 800 L	UF S \$4.00 TY 10,000	\$16,000 10,000 46,072			
Disc 6. 24° Clay 80 mil Hone 12° Sand Strip Doc	400 EA 400 EA 33.10 AC 72,937 SY 93,160 CCY	100,00 20,00 50,00 4,19 14,84	40,000 4,000 1,625 12,860			
Geotestile 12" Granular Material Geotestile 18* Natura	64,737 SY 23,580	7,20 63 15,84 64 34,830.00 36 1,880.00 31	77, 934 N, 906 N, 517 , 630 640			
Geometria Megatative Cover	44,359 CEY 14,790 CEY 34,670 LS 4,737 LS	1.20 733,5 5.13 105,4 5.13 227,61 14.81 219,04 1.35 20,239	loo M 3			
		31,058	11,772,605			

·· · Zeg

HARDAGE INDUSTRIAL WASTE SITE CRINER, OKLAHOWA EPA RENEDY WITH EXCAMATION OPTION

•		UNIT	UNIT	EXTERNED					
ITER	BURNTITY	HEAGLIFE	COST	COST					
County on 2 - ACTATION ACCOUNTS	•								
Section 3 - DETAILED REPETY DESCRIPTION									
3.2 Groundwater Extraction & Treatment									
3.2.1 Browningter Trenches GROUNGWATER COLLECTION TRENCHES	P								
V-SHIPED TRENCH	a - Comun								
Mebilization	1	LS	\$20,000	\$20,000					
Soil Excevation	11,400	G G	2.07	23, 598					
Bornhole dia (3*) 77 holes	4.042	। ਜ	£.40	264, 385					
Borshole dia (2*) A36 holes		FI	34.55	1,521,735					
Annove Ribs	5, 358	ξÝ	20.25	108, 500					
Insert and pipes (77 holes	3,330	L 1	20.23	100,500					
s \$3.5 FT/hole)	4, 120	FT	161.05	K7 5%					
Place coarse gravel	123	CY	15.00	22,155					
Place medium sand	3,419	כי	15.92	155, 316					
Place soil liner	133	EY .	16.50	10, 445					
Replace subgrade to grade	11,400	Ω,	2.4	28, 272					
Withdrawal wells (6 mach)	,	•,							
Person		EA	1.265.00	7,550					
Electric cables	3, 330	UF	2.00	6,660					
Terlion discharge hoses	4	_		4					
to piping	330	LF.	1.00	990					
Collection Lines		_							
Trench lines	2, 900	ij.	5.43	16, 907					
Laturel to Plant	100	LF.	1.89	989					
Trenching cost (Escava-									
tion & Sackfill)	3,000	LF	1.75	5, 250					
Pump controllers	1	LS	5,000	5,000					
Withdramal Wells									
P.E. Screen (6 inch dia)	60	FT	20.00	1,200					
P.E. Caurng (& inch dia)	303	LF.	16, 50	5,000					
Protective casing	6	5 4	250,00	1,500					
Course Sand Backfill	77	CY	15.安	1,225					
Low Purm Soil Backfill	5	CY	20.00	100					
Labor	1	LS	6, 780, 00	£, 780					
Observation Hells (71 sech)								
P.E. Screen (4 inch dia		_							
x 10 LF/mm11)	710	uf	£ 10	4, 331					
P.E. Casing (4 inch dia									
x 50 LF/mmil)	3,546	Ŀ	4, 17	14, 954					
Gravel Fill (71 mells)	970	CY	15.92	15,442					
Low Perm Soil Backfill	56	CY	20,00	1,120					
Protective casing	71	EA	150.00	10,650					
Labor	1	LS	A, 970.00	A , 970					
Sub Subtotal			•	3, 037, 596					

227

HAPPAGE INDUSTRIAL MASTE SITE CRINER, DILAHOMA EPA REMEDY WITH EXCAMPTION OPTION

ופוז	QUANTITY	UNIT HEASURE	UNIT COST	EXTENDED COST
Section 3 - DETAILED REMEDY DESCRIPTION	DN .			
3.2 Groundwater Extraction & Treat				
3.2.1 Broundmeter Trenches				
GROUNDIATER COLLECTION TREMOVE	S - Contin	NAC		
SOUTHMEST TREMEN Mobilization	1	LS	\$20,000	620,00 0
Soil Excavation	2,400	C.	2.07	4, 968
Screnole dia (3°) - 17 sa	444	fΤ	66.40	22,403
Borshole dia (2°) - 176 sa	5,051	FT	1.5	186,634
Remove Ribs	599	CY.	20.25	12, 130
Insert and pipes (17 0 30*	510	-	161.05	12.13
Place coarse grevel	134	CY.	15,00	4,600
Place sedium sand	1,008	£7	15.92	16,047
Place soil liner	134	CY	16.50	2,211
Replace subgrade to grade	2,400	CY	2.44	1,52
Withdrawal wells	·			
Pemps	2	EA	1255.00	2, 530
Electric cables	760	ĿF	೭ೲ	1,520
Teflow discharge homes				
to piping	60	UF.	1,00	180
Collection Lines				
Trench Lines	600	Ŀ	5.63	3,498
Lateral to Plant	1,200	LF.	2.89	11,068
Trenching Cost (Excava-				
tion & Anchfill)	1,800	LF.	1.75	3, 150
Pump controllers	1	LS	5,000.00	5,000
In-line pump to transport		_		
over 8° line	1	LS	5,000.00	5,000
Withdramal Hells		_		
P.E. Screen (6 inch dia)	20	FT	20.00	400
P.E. Casing (6 inch dia)	74	UF	16.50	1,221
Protective casing	2	EA	250.00	500
Course Sand Fill	13	CY	15.92	207
Low Perm Soil Backfill	2	CY	20.00	40
Labor	1	گا	1,620.00	1,620
Observation Wells (15 sect		_		
P.Emay (4" x 10"/ma)	150	LF.	€ 10	915
P.E. Casing (4" x 27"/sq)	400	LF.	4,17	1,660
C Sand Fill (15 mmlls)	101	CY	15.92	1,508
Low Prog Soil Backfill	15	CY	20,00	240
Prote Live casing	15	EA	150.00	2,250
Labor	1	LS	2, 2000، 00	2,000
Sub Subtota.				387,618

HARDAGE INDUSTRIAL MASTE SITE CRINER, OKLAHOMA SPA REMEDY WITH EXCAMATION OPTION

17E4	QUANTITY	UNIT HEAGURE	LINIT	EXTENSED FROST	
Section 3 - DETAILED REVERY DESCRIPTI	DN				
3.2 Groundwater Extraction & Treat					
3.2.1 Broundwater Trenches					
GROUNOMATER COLLECTION TREMOLE	5 - Contin	wed			
NISCELLANEOUS ITEMS					
Reserve Pumps, cables,					
Discharge hoses	1	LS	13,080	43,060	
Generations	5	EA	5,000	25,000	
Sub Subtotal			•	29,000	
Supt ot al					43,453,294
3.2.2 Brownshatur Treatment BROUNDHATER TREATMENT					
Effluent Pond					
Excavation	5,000	CY	s3	915,000	
Backfill	5,000	CY	5	25,000	
Spillney	i	LS	10,000	10,000	
Hear It high	1	وع	5,000	5,000	
Recycle Line					
4" HDPE Pipe	1,000	Ŀ	15	15,000	
Equipment					
Tanks - 15,000ga1	1	ERCH	130,000	9.30, 000	
Mixers - 1 Hp	•	EACH	12,000	44,000	
Pumps - Diaphrage 1/8hp	5	EACH	600	1,200	
0il/Nater Separators	5	EACH	10,000	20,000	
Ozl Pump	2	ERCH	1,200	2,400	
Solids Pump	2	EACH	7,800	15, 600	
Package Treatment System					
Metals	2	EACH	85,000	170,000	
Lime Food System	3	ERCH	4,630	13, 890	
Settler - Second	6	EACH	20,000	150,000	
SI udge Pump	3	EACH	1,200	3,500	
Media Filter	2	EACH	21,000	55,000	
Effluent Pusp	S	ERCH	500	1,200	
Effluent Tank	2	EACH	25,000	50,000	
Acid Metering System	2	ERON	4,630	9, 250	
Bactument Pump	2	EACH	80 0	1,600	
Bacimesh Storage Tank	-	EACH	20,000	20,000 600	
Decant Pump	1	EACH	500	2,400	
Sludge Putp - 3M	2	ERCH	1,200	•	
Stripper Pump	2	EACH	800	1,600	

Reproduced from best svallable copy.

223

HARDARE INDUSTRIAL WASTE SITE CRIMER, OKLAHOMA ERA REMEDY WITH EXCRARTION OPTION

		דוש	UNIT	exte ge d Cost
ITEN	QUANTITY	HEARLIE	COST	(LG)
Section 3 - DETAILED REMEDY DESCRIPTION	DN .			
3.2 Groundwater Extraction & Treet				
3.2.2 Groundwater Treatment				
GROUNDMATER TREATMENT - CONTUN	ued			
Equipment - Continued				
Air Strippers	2	ERCH	50,000	100,000
Air Blower	5	EACH	2,000	4, 000
GRC - Hater	4	ERCH	20,000	80,000
Str. Effl. Page	2	BICH	800	1,600
Sludge Storage Tank	1	ENOH	10,000	10,000
Sludge Mixer	1	EROI	12,000	12,000
Filter Press	2	BROH	15, 000	70,000
Filter Press Pesp	2	SECH	1,200	٤, 400
Tank - B. E.	1	ERCH	3,000	1,000
D. E. Hiner	1	ESCH.	1,200	1,200
Filtrate Tank	1	ERCH	3,000	3,000
Filtrate Pump	1	ERCH	600	600
Emergency Generator - 60%	ı	ERCH	25,000	25,000
Sump Pump	3	BROH	1,200	1,600
Air Compressor	1	EACH	12,500	12,500
Piping to Pond	i	LS	15,000	15,000
Emergency Shower & Eyement	1	ENDH	1,000	1,000
Operations/Maint Hermal	ı	ENCH	10,000	10,000
Betch Treatment Equipment	1	ERCH	100,000	100,000
Labor				
Operator (15 hrs.)	5, 336	HRS	31.50	168,084
Operator (8 hrs)	5,336	HRS	31,50	168, 084
Health & Safety Equipment	1	LS	143, 420	143, 420
Closure	1	LS	10, 900	10, 900
SUSTUTAL - Known Costs Only				\$1,582,738
General Cord Tions 8	94 of 9	LETUTAL		119, 904
Finishes ®		LETUTAL		47,962
Electrical ?	10% of 9			239, 809
Instrumentation & Controls				119,904
Yard Piping 8	12% of 9			287,771
SUBTUTAL - Percentage Costs			TAL	
SUBTOTAL - Known and Percent	ame Costs	Only		12, 394, 085
Mobilization 9 5d of SURTU	TAL - Know	m + 1		119,904
17001110011001 T C T T OO T		•		

2,517,992

Subtotal

3.2.3 Allevial Groundheter Ammediation
ALLEVIAL GROUNDMATER PROGRAM

COST INCLIDED IN Section 3.3.3 Passedial Monitoring

HARDAGE INDUSTRIAL HASTE SITE CRINER, DILLHOMA EPA RENEDY WITH EXCHARTION OPTION

ITEN	QUANTITY	UNIT MEAGURE	UNIT COST	EXTENSED COST	
Section 1 - DETAILED REJEDY DESCRIPTI	ON				
3.3 Other Remodial Features					
3.3.1 Remedial Support Facilities					
SEMERAL.					
Bonds and Insurance (2% of					
Construction Subtotal)	1	LS	9600,000	9600,000	
Equipment Mob/Demob (0.54					
of Construction Sustotal)	1	LŞ	150,000	150,000	
Community Melations					
Labor	216	HPS	45.00	9, 720	
Motorials	1	LS	10,000	10,000	
Utility Service					
Telephone, weder, electric	1	L	52, 800	58, 800	
Subtotal					1021, 52 0
SITE SUPPORT					
Health/Safety Program	1	کا	205,000	209,000	
Air Monitoring	1	L3	171,100	171, 100	
Project Administration	1	ى	65,000	65,000	
Subtotal			•		445, 100
SUPPORT FACILITIES					
Construction Office	1	LS	120,000	\$20,000	
Restroce Trailer	1	LS	21,800	21,800	
Guard Station	1	LS	10,000	10,000	
Guard Servace	1	LS	101,430	101, 430	
Equipment Maint, Shop	1	LS	136, 240	136,240	
Storage Shed	1	LS	9,000	5, 000	
On Site Laboratory	1	LS	805, 300	809, 300	
Medical Services Stat on	1	LS	155,400	155, 400	
Metarological Station	1	LS	£, 700	6, 700	
Decontamination Stations	1	LS	489, 100	483, 100	
Roadways	1	ى	204, 700	204, 700	
Subtotal			•		1,963,670

HANDAGE INDUSTRIAL WASTE SITE CRINER, DRUAHCHA SERVICEN WITH EXCRAFTION OPTION

ITEI	QUANTITY	UNIT MERSURE	UNIT COST	exte o ed Cost	
Section 3 - DETAILED RENEDY DESCRIPTION	N N				
3.3 Other Resedia! Features	-				
3.3.2 Surface Water Controls					
STORMATER CONTROL					
Pertension Pond					
Excavation -	4,000	CY	13.00	\$12,000	
Backfill	4,000	CY	1.00	20,000	
Soillney	1	LS	10,000	10,000	
Liner	142,000	CY	1.00	142,000	
Discharge Line					
4" HOPE LIME	800	Œ	15.00	12,000	
Subtotal			`		01 % , 000
3.3.3 Assertial Monitoring					
MONITORING PROGRAM					
Monstoring Well Installation	6	EA	43,000	\$1 8, 000	
Monitoring Piezometers	31	EA	750	23,250	
Subtotal			•		41,250
3.3.4 Institutional Controls					
INSTITUTIONAL CONTROLS					
Deed Restrictions					
Legal Fors	1	LS	150,000	650 , 000	
Field Markers	25	EA	250	6,250	
Easonemits & Property Perchases	ŀ			552,000	
. Subtotal			•		606, 250

HARDAGE INDUSTRIAL MASTE SITE CRINER, CHLANDAG ERA RENEDY WITH EXCAMATION OFFICE

UNIT UNIT EXTENDED TO COST COST COST

Section 3 - DETAILED REJETY DESCRIPTION

CONSTRUCTION SUBTOTAL 12L 30L L38 CONTINGENCIES Bid Contingency 155 4,246,026 5,661,34 Scope Contingency 201 9, 907, 333 Subtotal CONSTRUCTION TOTAL 136, 214, 231 IMPLENTATION COSTS 3, 821, 423 Engineering Design 101 2, 674, 996 Permitting and Legal 7% 1,121,42 Services During Construction 104 10, 317, 842 Subtotal TOTAL CAPITAL COST Based on October 1986 Bollars 946, 532, 073 Engineering News Record Construction Cost Index Dallas September 1989 3189 Dellas October 1968 3185 Multiplier to change base to September 1989 - L.0013 944, 555, 165 TUTAL COPITAL COST Based on September 1989 Dollars 14, 309, 500 OPERATIONS & MAINTENANCE COSTS Present Worth of 9661,900 Annual D&M Costs assuming 5% Interest Rate over 30 years and #639,700 Armual Old Costs assuming 55 over 8 years TOTAL COPITAL COST Including Operations & Maintenance 662, 904, 663

	·		